Build A Radon Monitor And Keep Your Home Safe

Electronics NOW®

FEBRUARY 1994

48783

Combined with Radio Electronics®

TAKE BACK CONTROL OF YOUR TELEPHONE



Build This Calling Number Identifier

Add a long-range
Body-Heat Detector
to your security system

Build an
Experimenters Clock
Based on the 68705 microcontroller

How to put
Stepper Motors
to work as shaft encoders

Put Microchip Technology's
PIC microcontrollers to work with our
PIC Programmer

PLUS: Video News • Audio Hacker
Hardware Hacker • And Lots More!

A GERNSBACK PUBLICATION

$3.50 U.S
$3.95 CAN

#BXNBQWF CAR-RT SORT ** CR03
#HRR5165M093 4#750456 OAP61

DEC
E PATRICK HARRIGAN 02RE
5165 S MAGELLAN DR
NEW BERLIN WI 53151-8142

The Fluke 79: More Of A Good Thing

More high-performance features. More advanced measurement capabilities. More of the vital information you need to troubleshoot even the toughest problems — with both analog and digital displays.

Meet the latest, greatest member of our best selling 70 Series II family — the new Fluke 79 digital multimeter.

It picks up where the original family left off. In fact, it's a quantum leap forward — in performance, value and affordability.

It's got the features you'd expect from Fluke. Including high resolution. Fast autoranging. Patented, automatic Touch Hold®. A quick continuity beeper. Diode test. Automatic self-test. Battery-conserving sleep mode. And it's just as rugged and reliable as the rest of the 70 Series II family. Easy to operate, too — with one hand.

And thanks to the Fluke 79's proprietary new integrated circuit technology, that's only the beginning. When it comes to zeroing in on tough electrical problems, the Fluke 79 leaves the competition behind:

Hz

Frequency: The Fluke 79's built-in frequency counter lets you measure from below 1 Hz to over 20 kHz. And while you view frequency on the digital display, the analog bar graph shows you AC voltage. So you can see if potentially hazardous voltage is present.

Fast 63-segment analog bar graph: The Fluke 79's bargraph moves as fast as the eye can see, updating at a rate of 40 times per second to simulate the functionality of an analog needle. You get the high speed *and* high resolution you need to detect peaking, nulling and trending.

Capacitance: No need to carry a separate dedicated capacitance tester; the Fluke 79 measures capacitance from 10 pF to 9999 µF.

Actual Size

40Ω

Lo-Ohms range: Our proprietary Lo-Ohms function lets you measure resistance as low as 0.01 ohms. High noise rejection and a test lead Zero Calibration function make the Fluke 79 ideal for detecting small resistance changes.

SMOOTHING

Smoothing™: Our exclusive new Smoothing mode gives you a stable digital readout for unstable signals — by displaying the running average of eight readings. No more jitter or "digit rattle" due to noisy signals.

Get a good thing going: To put more meter to work for you — at a price that works for you, too — head for you nearest Fluke distributor. For the name of your nearest distributor, or for more product information, call **1-800-87-FLUKE.**



The Fluke 79 comes with a yellow holster and patented Flex-Stand™ — easy to hang from a door or pipe, clip onto a belt or tool kit, or stand at virtually any viewing angle. There's even storage space for test leads.

Fluke 79 Series II
$185*
4000 Count Digital Display (9999 in Hz, capacitance, and Lo-Ohms)
63-segment Analog Bar Graph
0.3% Basic DC Voltage Accuracy
Automatic Touch Hold
Diode Test, Audible Continuity Beeper
Autoranging, Manual Ranging
Holster with Flex-Stand
Frequency Counter to over 20 kHz
Capacitance, 10 pF to 9999 µF
Lo-Ohms Range with Zero Calibration
Smoothing
700 Hours Battery Life (alkaline)
3-Year Warranty

** Suggested U.S. list price*

John Fluke Mfg. Co., Inc. P.O. Box 9090, M/S 250E Everett, WA 98206. © Copyright 1993. Prices and specifications subject to change without notice. Ad No. 00425.

FLUKE®

CIRCLE 121 ON FREE INFORMATION CARD

Mini-Spur™ 1.0

turns your PC into a Spectrum Analyzer



Spot Spurious Signals Easily...
choose the best mixer for your design problems

Introducing Mini-Spur™, the software simulation program for analysis of system spurious responses. Using actual data on Mini-Circuits mixers, spurious signal levels are calculated and then displayed.

Operation is simple. The user defines the input frequency and power level, the program then graphically displays the various outputs including all the spurs (up to 10xLO ± 10xRF) falling within the user-defined IF filter bandwidth. As the user tunes the frequency, the output spectrum scrolls across the screen just like that of a sophisticated spectrum analyzer.

Required hardware; IBM AT or compatible with 640k memory, and EGA or VGA display. Optional, dot matrix, laser printer or plotter.

So maximize design efficiency... use Mini-Spur™ only from Mini-Circuits.

$49.95

Free... 740 page RF/IF Designer's Handbook with purchase of Mini-Spur® program

place order as ***Designer's Special, DS-1***

finding new ways ...
setting higher standards

Mini-Circuits® WE ACCEPT AMERICAN EXPRESS AND VISA

P.O. Box 350166 Brooklyn, New York 11235-0003 (718) 934-4500 Fax (718) 332-4661

Distribution Centers NORTH AMERICA 800-654-7949 • 417-335-5935 Fax 417-335-5945 EUROPE 44-252-835094 Fax 44-252-837010

...iled specs on all Mini-Circuits products refer to • THOMAS REGISTER Vol. 23 • MICROWAVES PRODUCT DIRECTORY • EEM • MINI-CIRCUITS' 740-pg HANDBOOK.

CUSTOM PRODUCT NEEDS... ***Let Our Experience Work For You.***

F167 REV. A

CIRCLE 184 ON FREE INFORMATION CARD

24 HOUR SHIPPING

ELENCO • HITACHI • B&K PRODUCTS
GUARANTEED LOWEST PRICES

TO ORDER
CALL TOLL FREE
1-800-292-7711
1-800-445-3201 (Can.)

AFFORDABLE - HIGH QUALITY
2 YEAR WARRANTY

STANDARD SERIES
S-1325 25MHz $349
S-1340 40MHz $495
S-1365 60MHz $849

Features:
- High Luminance 6" CRT
- TV Sync
- 1mV Sensitivity
- 2 - x1, x10 Probes
- X-Y Operation
- Complete Schematic
- Voltage, Time, + Frequency differences displayed on CRT thru the use of cursors (S-1365 only)
- Plus much, much more

ELENCO OSCILLOSCOPES



DELUXE SERIES
S-1330 25MHz $449
S-1345 40MHz $575
S-1360 60MHz $775

Features:
- Delayed Sweep
- Dual time base
- Automatic Beam Finder
- Illuminated internal gradicule
- Z Axis Modulation
- Built-in Component Test
- Plus all the features of the "affordable" series

Hitachi Compact Series Scopes

V-212 - 20MHz Dual Trace	$399
V-525 - 50MHz, Cursors	$995
V-523 - 50MHz, Delayed Sweep	$949
V-522 - 50MHz, DC Offset	$895
V-422 - 40MHz, DC Offset	$795
V-222 - 20MHz, DC Offset	$649
V-660 - 60MHz, Dual Trace	$1,149
V-665A - 60MHz,DT, w/cursor	$1,325
V-1060 - 100MHz, Dual Trace	$1,395
V-1065A - 100MHz, DT, w/cursor	$1,649
V-1085 - 100MHz, QT, w/cursor	$1,995
V-1100A - 100MHz, Quad Trace	$2,495
V-1150 - 150MHz, Quad Trace	$2,895

B&K OSCILLOSCOPES

2120 - 20MHz Dual Trace	$389
2125 - 20MHz Delayed Sweep	$539
1541B - 40MHz Dual Trace	$695
2160 - 60MHz Dual Trace, Delayed Sweep, Dual Time Base	$949
2190 - 100MHz Three Trace Dual Time Base, Delayed Sweep	$1,395
2522A - 20MHz / 20MS/s Storage	$875

Digital Capacitance Meter
CM-1550B by Elenco

$58.95

9 Ranges
.1pf-20,000ufd
.5% basic accy.
Zero control w/ Case

Big 1" Display

Digital LCR Meter
LC-1801

$125

Measures:
Coils 1uH-200H
Caps .1pf-200uf
Res .01-20M

Big 1" Display

by Elenco

Digital Multimeter
DVM-638



$39.95

11 Functions with Case

FLUKE MULTIMETERS

Scopemeters		(All Models Available Call)	
Model 93	$1,225.00	**70 Series**	
Model 95	$1,549.00	Model 70II	$65.00
Model 97	$1,795.00	Model 77II	$149.00
10 Series		Model 79II	$169.00
Model 10	$62.95	**80 Series**	
Model 12	$79.95	Model 87	$289.00

Quad Power Supply XP-580

$79.95

2-20V @ 2A
12V @ 1A
5V @ 3A
-5V @ .5A

Fully regulated and short circuit protected
Made in USA by Elenco

Triple Power Supply XP-620

Assembled $75
Kit $50

2 to 15V @ 1A,
-2 to -15V @ 1A
(or 4 to 30V @ 1A)
and 5V @ 3A

Made in USA by Elenco
All the desired features for doing experiments.
Features short circuit protection, all supplies.

AM/FM Transistor Radio Kit
with 52 page Training Course

$27.95 Elenco AM/FM 108

14 Transistors ◆ 5 Diodes
Makes a great school project
AM Radio Kit AM550 $18.95

True RMS 4 1/2 Digit Multimeter
M-700T

$135

.05% DC Accuracy
.1% Resistance
with Freq. Counter
Data Hold

by Elenco

Sweep/Function Generator
with Freq. Counter

$239

Elenco Model GF-8026

Sine, Square, Triangle, Pulse, Ramp
.2 to 2MHz, Freq Counter .1-10MHz
Internal Linear & Logic Sweep

Function Generator Blox
#9600 by Elenco

$28.95

Provides sine, triangle, square wave from 1Hz to 1MHz AM or FM capability

Kit $26.95

Learn to Build and Program Computers with this Kit
Includes: All Parts, Assembly and Lesson Manual

Model MM-8000



$129.00

by Elenco

Starting from scratch you build a complete system. Our Micro-Master trainer teaches you to write into RAMs, ROMs and run a 8085 microprocessor, which uses similar machine language as IBM PC.

Elenco Wide Band Signal Generators

SG-9000 $119

RF Freq 100K-450MHz AM Modulation of 1KHz Variable RF output

SG-9500 w/ Digital Display & 150MHz built-in counter $239

XK-500 Digital / Analog Trainer

A complete mini-lab for building, testing, prototyping analog and digital circuits

Elenco's Digital/Analog Trainer is specially designed for school projects, with 5 built-in power supplies. Includes a function generator with continously variable, sine, triangular, square wave forms. All power supplies are regulated and protected against shorts.

Power Supplies
- Variable Power Supply
- +1.25 to 20VDC @ .5 Amp (+1.25 to 15VDC @ 1 Amp)
- -1.25 to -20VDC @ .5 Amp (-1.25 to -15VDC @ 1 Amp)
- +12VDC @ 1 Amp
- -12VDC @ 1 Amp
- +5VDC @ 1 Amp
- 30VAC Center tapped @ 15VAC at 1 Amp

Analog - Section
- Function Generator Sine, Triangular, Square wave forms
- Frequency adjustable in five ranges from 1 to 100KHz
- Fine frequency adjust
- Amplitude adjust
- DC offset
- Modulation FM-AM

Digital - Section
- Eight data swiches
- Two no bounce logic switches
- 8 LED readouts TTL buffered
- Clock frequency 1 to 100KHz
- Clock amplitude 5VPP square wave

Breadboards
- 2 breadboards, each contain: 840 tie points (total 1,680)



$159.95 Assembled

$129.95 Kit

WE WILL NOT BE UNDERSOLD
UPS SHIPPING: 48 STATES 5% OTHERS CALL
IL RES add 7.75% TAX
PROBES INCL ALL SCOPES & METERS

C&S SALES INC.
1245 ROSEWOOD, DEERFIELD, IL 60015
FAX: 708-520-0085 • (708) 541-0710

VISA MasterCard

15 DAY MONEY BACK GUARAN
FULL FACTORY WARRANTY
WRITE FOR FREE CATALOG
PRICES SUBJECT TO CHANGE

CIRCLE 109 ON FREE INFORMATION CARD

February 1994

Electronics NOW®

Vol. 65 No. 2

BUILD THIS

33 TAKE BACK CONTROL OF YOUR TELEPHONE
Our easy-to-build Caller-ID unit lets you know who's calling before you pick up the phone.
Terry J. Weeder

38 LONG-RANGE BODY-HEAT DETECTOR
For home-security, or for science experiments, this detector picks up infrared emissions of body heat.
Robert Iannini

48 PIC MICROCONTROLLER PROGRAM
This month we build the PIC165CX microcontroller programmer.
Fred Eady

59 68705-BASED EXPERIMENTER'S CLOCK
Put your custom-programmed 68705 microcontroller to use in a clock circuit.
Brian Beard

66 RADON MONITOR
Learn more about radioactivity as you build this monitor to protect your family from the possible threat of radon.
Paul Neher

TECHNOLOGY

53 STEPPER MOTORS AS SHAFT ENCODERS
Take a different approach to shaft encoders.
Neil W. Heckt

DEPARTMENTS

8 VIDEO NEWS
What's new in this fast-changing field.
David Lachenbruch

18 EQUIPMENT REPORTS
ITT Pomona Logic Scope Probe.

73 HARDWARE HACKER
Hacker's data exchange, and more.
Don Lancaster

80 AUDIO UPDATE
Audiophile silliness.
Larry Klein

82 DRAWING BOARD
Our automotive power supply comes to life.
Robert Grossblatt

88 COMPUTER CONNECTIONS
The National Information Infrastructure.
Jeff Holtzman

Long-Range
BODY-HEAT DETECTOR
Build this instrument that detects the infrared emission of humans and animals for security or for performing science experiments.

PAGE 38

PAGE 48

AND MORE

96 Advertising Sales Offices
96 Advertising Index
91 Buyer's Mart
16 Letters
26 New Lit
21 New Products
10 Q&A
6 What's News

ON THE COVER


Build A Radon Monitor And Keep Your Home Safe
Electronics NOW
TAKE BACK CONTROL OF YOUR TELEPHONE
Build This Calling Number Monitor
Body-Heat Detector
Experimenters Clock
Stepper Motors
PIC Programmer
Video News • Audio Hacker
Hardware Hacker • And Lots More!

Do you find the phone to be as much a bother as a convenience? Are you the target of sales calls that always come just as you're sitting down to dinner? Caller-ID can put an end to that problem. The service allows you to see the phone number of the person who is calling you, so that you can decide if you want to take the call before you pick up the receiver. If you'd like to be able to screen your calls with Caller-ID, first check with your local phone company to see if the service is available where you live. If it is, turn to page 33 for instructions on how to build your own Caller-ID circuit. You'll never again have your dinner interrupted by annoying telephone solicitors or chatty friends with bad timing!

COMING NEXT MONTH

THE MARCH ISSUE GOES ON SALE FEBRUARY 3.

PC-BASED FUNCTION GENERATOR
Our full-featured sweep generator offers frequency coverage from 4 to 2000 MHz.

POWER-LINE MODEM
Send X10 control signals over power lines.

CIRCUIT COOKBOOK
A close-up look at transistor audio preamplifier circuits.

As a service to readers, ELECTRONICS NOW publishes available plans or information relating to newsworthy products, techniques and scientific and technological developments. Because of possible variances in the quality and condition of materials and workmanship used by readers, ELECTRONICS NOW disclaims any responsibility for the safe and proper functioning of reader-built projects based upon or from plans or information published in this magazine.

Since some of the equipment and circuitry described in ELECTRONICS NOW may relate to or be covered by U.S. patents, ELECTRONICS NOW disclaims any liability for the infringement of such patents by the making, using, or selling of any such equipment or circuitry, and suggests that anyone interested in such projects consult a patent attorney.

ELECTRONICS NOW, (ISSN 1067-9294) February 1994. Published monthly by Gernsback Publications, Inc., 500-B Bi-County Boulevard, Farmingdale, NY 11735. Second-Class Postage paid at Farmingdale, NY and additional mailing offices. Canada Post IPM Agreement No. 334103, authorized at Mississauga, Canada. One-year subscription rate U.S.A. and possessions $19.97, Canada $27.79 (includes G.S.T. Canadian Goods and Services Tax, Registration No. R125166280), all other countries $28.97. All subscription orders payable in U.S.A. funds only, via international postal money order or check drawn on a U.S.A. bank. Single copies $3.50. © 1993 by Gernsback Publications, Inc. All rights reserved. Printed in U.S.A.

POSTMASTER: Please send address changes to ELECTRONICS NOW, Subscription Dept., Box 55115, Boulder, CO 80321-5115.

A stamped self-addressed envelope must accompany all submitted manuscripts and/or artwork or photographs if their return is desired should they be rejected. We disclaim any responsibility for the loss or damage of manuscripts and/or artwork or photographs while in our possession or otherwise.

Electronics NOW®

Hugo Gernsback (1884-1967) founder

Larry Steckler, EHF, CET, editor-in-chief and publisher

EDITORIAL DEPARTMENT
Brian C. Fenton, editor
Marc Spiwak, associate editor
Neil Sclater, associate editor
Teri Scaduto, assistant editor
Jeffrey K. Holtzman computer editor
Robert Grossblatt, circuits editor
Larry Klein, audio editor
David Lachenbruch contributing editor
Don Lancaster contributing editor
Evelyn Rose, editorial assistant

ART DEPARTMENT
Andre Duzant, art director
Injae Lee, illustrator
Russell C. Truelson, illustrator

PRODUCTION DEPARTMENT
Ruby M. Yee, production director
Karen S. Brown advertising production
Kathryn R. Campbell production assistant
Lisa Rachowitz editorial production

CIRCULATION DEPARTMENT
Jacqueline P. Cheeseboro circulation director
Wendy Alanko circulation analyst
Theresa Lombardo circulation assistant
Michele Torrillo reprint bookstore

Typography by Mates Graphics
Cover by Loewy Design, photo by Michel Tchrevkoff, Image Bank

Electronics Now is indexed in *Applied Science & Technology Index*, and *Readers Guide to Periodical Literature*, *Academic Abstracts*, and *Magazine Article Summaries*.
Microfilm & Microfiche editions are available. Contact circulation department for details.

Advertising Sales Offices listed on page 98.
Electronics Now Executive and Administrative Offices
1-516-293-3000.
Subscriber Customer Service:
1-800-288-0652.
Order Entry for New Subscribers:
1-800-999-7139.

Audit Bureau of Circulations **Member**

Earn A Bachelor of Electronic Engineering Technology Degree from

Introducing a New Era In Technical Training.

World College, an affiliate of the Cleveland Institute of Electronics, was created to provide a four year, independent study, technical degree program to individuals seeking a higher education. The Bachelor of Electronics Engineering Technology Degree, offered by World College, prepares students for high-paying careers in electronics, telecommunications, electrical power, computer and control systems. World College's curriculum is taught in an effective, time-proven, independent study environment. With World College's flexible study schedule, students have the opportunity to work or spend time with their family without having to worry about rigid scheduling residential colleges offer.

A Quality Education with a Flexible Schedule.

In a world heavily dependent on electronic equipment, people who understand electronics will have no problem putting their knowledge to work... in high-paying careers. The staff and faculty of World College have invested over ten years developing, what we believe to be, the finest independent-study, baccalaureate degree program available. World College's mission is to instill in each student the knowledge, *education, and training* that employers are seeking for the many technical positions available today. It's a program created to provide the best education and training possible with a flexible schedule to match your busy lifestyle.

World College is currently seeking approval to confer the Bachelor Degree from the Virginia Council of Higher Education.

WORLD COLLEGE

Bringing Technology Home!

Lake Shores Plaza
5193 Shore Drive, Suite 113
Virginia Beach, VA 23455-2500

Send For Your Free Course Catalog.

Take the first step towards a new start in life. Send for World College's Free Independent Course Catalog today and discover how easy and affordable it is to get started on your Bachelor Degree.

World College is affiliated with

ICE

Complete the Entire Degree Program Under One Roof. Yours!

Only World College offers an independent study, four year technical degree which can be completed through one school. All lab equipment*, parts, and software are included in your tuition and the program's 300-plus laboratory experiments can be completed in your own home.

You Pay Only For Time Actually Used.

World College not only provides a means to earn a Bachelor Degree while fulfilling current obligations, but there are no restrictions on how fast you can complete the program. At World College, you pay tuition only for the actual upper-level semesters it takes to graduate. The quicker you complete the program, the less you pay in tuition. It's an effective way to keep you motivated in order to complete the course and move on to a better paying position as quickly as possible.

Currently not available in Ohio.
* Student must have access to a personal computer system.

☐ **YES!** Please send me World College's Free Course Catalog detailing the full curriculum.

Name: _____

Address: _____

Apt: _____

City: _____

State: _____ Zip: _____

Phone: (_____) _____

Age: _____

Return to: **WAE06**
World College
Lake Shores Plaza
5193 Shore Drive, Suite 113
Virginia Beach, VA 23455-2500

WHAT'S NEWS

A review of the latest happenings in electronics.

Digital Dolby comes home

Dolby Laboratories (San Francisco) and Zoran Corporation (Santa Clara, CA) introduced integrated circuitry that they say is a giant step toward including Digital Dolby Surround Sound in consumer home-theater equipment. Their programmable, fixed-point, digital signal processor (DSP) and a related family of ICs are intended for installation in various types of audio and speech equipment.

Zoran's ZR38000 is the only single-chip DSP capable of encoding and decoding six-channel audio processed with Dolby's AC-3 low bit-rate surround-sound algorithm. It will be installed first in Dolby Laboratories' professional theater decoders. Consumer products that include the chips are expected to reach the market sometime during 1994.

The ZR38000 has a general-purpose register file, unified data address registers, single memory address space, and large on-chip memory. It is said to be easily programmable. Dolby's licensees can add custom features in addition to AC-3 decoding. The DSP is priced less than $25 each in large quantity purchases.

The first two user-programmable DSPs to be offered will be the ZR38000 and the ZR38001. They are intended for applications that need relatively large off-chip program or data memories, or for systems that permit the customer's programs to be incorporated into the on-chip ROM. The ZR38000 offers 8K words of program/coefficient ROM and 2K words of RAM for data storage.

The ZR38001 offers a 1K word on-chip program RAM, 2K words of on-chip data-storage RAM, and a 1.5K word ROM for coefficient storage. No external memory other than a single EPROM is needed to use the device.

The two companies also announced three application-specific ICs and development software. The ZR38500 provides six-channel AC-3 decoding for home theater products, and the ZR38501 provides two-channel Dolby AC-3 decoding for cable television and computer multimedia. Both of the ICs can also perform Dolby Pro Logic decoding.

The ZR38511 is optimized for two-channel audio decoding for computer multimedia and CD-ROMs. The ZR38000 assembler, linker, and simulator software package gives the programmer with a Windows-based computer tools for developing and debugging algorithms written in ZR38000 assembly language.

Multimedia LCD panel

A liquid-crystal display panel that is compatible with multimedia has been introduced by Sharp Corporation (Osaka, Japan). It is capable of displaying text, graphics, and both broadcast and pre-recorded video images. Those images can be obtained from such sources as television, VCRs, and laser discs. Sharp expects the LCD panels to find applications in various equipment including business presentation systems, security monitors, and video-conferencing systems.

The 10.4-inch active matrix LC-10V1 display will display 24-bit color, which can form more than 16 million hues, the present industry maximum. The LCD panel's low-reflecting front face reduces ambient light glare to one-tenth the value of earlier Sharp products. This is said to permit relatively glare-free viewing even when viewed in brightly lit rooms.



Sharp's multimedia-compatible color liquid-crystal display panel displays video images as well as text and graphics.

The LC-10V1 is compatible with, and can be connected directly to, Macintosh LC, II, and Quadra series personal computers, IBM PCs, and other makes. A microprocessor built into the display performs automatic centering, calibration, and screen control. In the RGB mode, it can automatically adjust for off-center images and for the variations in analog output levels expected from different PCs.

An on-screen, menu-driven display allows the user to set variables including switching between RGB and video inputs, selecting the PC display mode, adjusting the RGB level/gain, and controlling the serial port.

Hams in Nobel company

A 1993 winner of the Nobel Prize for physics credits much of his success in science to his participation in amateur radio. The winner, Dr. Joseph H. Taylor, K1JT, of Princeton University, said that he developed many of his scientific skills as an amateur radio operator while a student at Moorestown Friends Academy in New Jersey.

Dr. Taylor went on to earn a bachelor's degree from Haverford College and a doctorate in astronomy from Harvard University. He shared the Nobel Prize with Princeton colleague Dr. Russell A. Hulse. The physics prize was granted to the pair of scientists for their study of the gravitational forces exerted by pulsars. The results of their study are said to confirm the predictions of Einstein's General Theory of Relativity. Ω

4331H $29.95
Hardcover



4061P $9.95



3258P $19.95

3374P $16.95



3550H-XX $34.95
Counts as 2/Hardcover



3627P $19.95



3739P $22.95



3759P $19.95



3700H-XX $36.95
Counts as 2/Hardcover



3765P $18.95



4111H $27.95
Hardcover

4358P $24.95



2880P $15.95

3107P $18.95

2613P $18.95



3777H-XX $32.95
Counts as 2/Hardcover



2800P $17.95



3632P $10.95



3677H-XX $34.95
Counts as 2/Hardcover



3672P $18.95



003961H-XX $40.00
Counts as 2/Hardcover



3795P $19.95



1938H-XXX $60.00
Counts as 3/Hardcover

As a member of the Electronics Book Club . . .

. . . you'll enjoy receiving Club bulletins every 3-4 weeks containing exciting offers on the latest books in the field at savings of up to 50% off regular publishers' prices. If you want the Main Selection do nothing and it will be shipped automatically. If you want another book, or no book at all, simply return the reply form to us by the date specified. You'll always have at least 10 days to decide. And you'll be eligible for *FREE* BOOKS through our Bonus Book Program. Your only obligation is to purchase 3 more books during the next 12 months, after which you may cancel your membership at any time.

Publishers' prices shown. All books are softcover unless otherwise noted. If you select a book that counts as 2 choices, write the book number in one box and XX in the next. If you select a Counts as 3 choice, write the book number in one box and XXX in the next 2 boxes. A shipping/handling charge & sales tax will be added to all orders. ©1994 EBC

If coupon is missing, write to:
Electronics Book Club, Blue Ridge Summit, PA 17294-0810

Your most complete and comprehensive source for the finest electronics books

Electronics Book Club®

Blue Ridge Summit, PA 17294-0810

YES! Please send me the books listed below, billing me for just $4.95 plus shipping/handling & tax. Enroll me as a member of the **Electronics Book Club** according to the terms outlined in this ad. If not satisfied, I may return the books within 10 days without obligation and have my membership cancelled.

If you select a book that counts as 2 choices, write the book number in one box and XX in the next.
If you select a Counts as 3 choice, write the book number in one box and XXX in the next 2 boxes.

Name _____

Address _____

City/State _____

Zip _____ Phone _____

Valid for new members only, subject to acceptance by EBC. Canada *must* remit in U.S. funds drawn on U.S. banks. Applicants outside the U.S. and Canada will receive special ordering instructions. All books are softcover unless otherwise noted. Publishers' prices shown. A shipping/handling charge & sales tax will be added to all orders. RPIE294

VIDEO NEWS

What's new in the fast-changing video industry.

DAVID LACHENBRUCH

• **For HDTV compatibility.** Still another change in the proposed parameters for high-definition television has been approved by the FCC's Advanced TV Advisory Committee (ATAC). ATAC approved an increase to 1080 active lines from the previous 960. That change is designed to enhance compatibility with computers and increase the likelihood that Europe and Japan will adopt compatible systems. Japanese broadcasting authorities, now transmitting an analog system of 1035 active lines, have already indicated a willingness to switch to 1080 lines when they adopt a digital system, and there is an indication that Europe will seriously consider dropping from 1125 active lines to 1080.

The ATAC also approved a proposal to permit both interlaced and progressive scan. Although that will increase receiver cost initially, it appears to be necessary because of the current unavailability of progressive scan technology and components. For digital audio, ATAC approved the incorporation of a Dolby system. The new moves will result in a four- to five-month delay in the testing schedule, with testing probably to start next October instead of June. The eventual goal is to allow the broadcasting of the 1986 Olympics from Atlanta in HDTV.

• **Million HDTV's in 1996.** Zenith Chairman Jerry Pearlman thinks that the American public will buy between one and two million HDTV sets in 1996, the first year of their availability. That is a far more optimistic view than has been expressed by other industry members, who have pointed out that it was 10 years from the start of color TV broadcasting to the first million-set year. In addition, Pearlman forecast that 10% of American homes would have HDTV four to five years after introduction.

Despite their added cost, Pearlman cited the versatility of HDTV sets, which should be able to provide at no charge many services for which consumers now pay. Among those enhancements are elimination of the $200–$300 cost of a digital cable box and a $50 digital data recorder, the existence of a built-in video adapter for the audio CD player, the capability of acting as a video telephone, and the incorporation of a deluxe digital audio system.

• **CD-ROM at Blockbuster.** If there was any question that CD-ROM has arrived as a successful medium, it was dispelled when the world's biggest video retailer, Blockbuster, announced plans to sell and rent digital interactive hardware and software. The company is now testing various types of interactive systems at its 52 stores in the San Francisco area, and plans to go nationwide after analyzing the results of that test. Blockbuster is renting software for IBM and Macintosh PC's and 3DO, CD-I, and Sega CD multimedia systems. Itis renting the hardware for the last three.

Blockbuster charges $4 for a three-evening software rental, and gives renters a $5 credit toward the future purchase of a program. Equipment rental at $19.95 includes three software titles along with the player. Blockbuster has been testing rental of CD-I hardware and software in 100 stores for the past year.

• **Who'll make the box?** Be prepared to witness a battle royal over the future home terminal in the digital age. With digital transmission of video on demand, video telephone service, and computer data over the so-called "information superhighway," computer, semiconductor, TV, cable-equipment, telephone, and video-game manufacturers will be vying to supply the consumer equipment. Each of those groups probably has some claim to the right to sell (or rent) the equipment.

Some cable-TV equipment manufacturers insist that the "TV set" of the future will be nothing but a box with a picture tube and a few video circuits. The idea, of course, is for cable systems to rent all of the additional reception equipment to consumers' homes. Having been stung in the past by exorbitant cable fees, consumers might feel wary of entrusting cable operators to supply virtually all of their equipment.

At the other extreme is the TV-set manufacturer, who naturally doesn't want to be relegated to the position of making nothing but a "tube in a box." TV manufacturers say that they hope to supply self-programming digital terminals, which can adapt to virtually any system entering the home. For scrambled programs, they hope that dealers or cable operators eventually will supply plug-in smart cards to decipher pay programming.

• **Apple enters TV.** Already the lines between computers and TV sets are blurring, with TV boards now available for many computers. The boldest stroke yet is Apple's Macintosh TV, which is a cross between a TV and a computer—or a combination of both. However, there's very little interaction between computer and TV sections—the computer can't be used to edit home videos, for instance. It can freeze a TV frame or it can let the user listen to TV sound while computing, but that's about it. It's hard to figure out the purpose of a Macintosh TV, but Apple suggests that it might be useful in crowded college dorm rooms where there's not room for both a TV set and a computer.

Is it possible that as a next step, a major TV manufacturer will bring out a computer with a 60-inch projection screen. Useful, maybe, for processing very long words or displaying very w-i-d-e spreadsheets. Ω

WHY CARRY ALL THESE?

WHEN YOU CAN CARRY ALL-IN-ONE!

MODEL	391	390	389	388A
% DCV ACCURACY	0.05	0.1	0.25	0.5
DISPLAY	4½ LCD	3¾ LCD	3¾ LCD	3¾ LCD
ANALOG BAR GRAPH		●	●	
CAPACITANCE		●	●	●
FREQUENCY	●	●	●	●
LOGIC LEVEL	●			●
TEMPERATURE		●		
RUGGEDIZED, RUBBER BOOT	●	●	●	●
PRICE	$179	$159	$139	$119

Meet the new TEST BENCH® DMMs, with more of what made the original a best seller.
B+K PRECISION's original TEST BENCH testers became overnight best sellers because they fused the power of many instruments in one compact meter. These new models also out-feature ordinary DMMs, and outperform them as well. All are ruggedized, offer long battery life and carry a three-year warranty.

With True RMS, 4½ digit, 20,000 counts and 0.05% DCV accuracy, the Model 391 is a *BEST BUY.*
Now you can have very high accuracy, extra resolution and True RMS reading at a very affordable price. The Model 391 Test Bench DMM also has frequency, logic, duty cycle and data hold. It's even water resistant.

There's a TEST BENCH DMM to fit every application and budget.
Choose from three, 3¾ digit TEST BENCH DMMs, starting with the Model 388A. All measure AC/DC voltage or current, ohms, frequency, logic levels and test components and continuity. The Models 389 and 390 add 41 segment bar graphs for smooth peak, null or level adjustments; Min/Max, memory and relative modes. The 390 also has a temperature probe.
So why carry an ordinary DMM, when you can grab a TEST BENCH! See your local distributor for immediate delivery.

BUILT FOR THE ROAD

COVERS FULL PERFORMANCE 3 YEAR WARRANTY A B+K PRECISION FIRST

BK PRECISION
MAXTEC INTERNATIONAL CORP.
Domestic and International Sales
6470 W. Cortland St., Chicago, IL 60635
312-889-1448 • FAX: 312-794-9740

CIRCLE 77 ON FREE INFORMATION CARD

Q & A

Write to Q & A, Electronics Now, 500-B Bi-County Blvd., Farmingdale, NY 11735

PARALLEL PROCESSING

I've heard a lot of talk about parallel processing in computers but I'm not sure exactly what the term means. Does it refer to a lot of stand-alone computers working on different parts of one problem at the same time, or does it mean something else?—F. Boffer, Procon, NY

Parallel processing is really not a new idea. Mainframe computer users are showing new interest in parallel processing because they are rapidly approaching a limit to the speed and processing power that can be obtained from a single central processor manufactured with existing technology. There have been incredible advances in microelectronic component density and in IC chip technology. However, when you are at the point where the width of internal IC traces are measured in terms of electron dimensions, you're up against a pretty formidable obstacle.

Your notion of parallel processing is correct in that it refers to the idea of having several microprocessors working on the same problem at the same time. However, those microprocessors are not the kind that you'll find inside a home computer, but specially designed RISC (reduced instruction set computer) chips. For an example of how RISC works, consider an Intel 386-based computer with a 387 numeric coprocessor. There's no reason to have the 386 do any floating point calculations because the 387 can do them. To go a step further, any of the 386's instructions intended specifically for floating-point calculations could be removed from the instruction set, simplifying it and making the chip more efficient.

To put parallel processing in perspective, back in the old Apple II days, you would add an 80-column card to expand the video display. An 80-column card had a dedicated microprocessor that handled all of the video memory. Since both the 6502 on the Apple's motherboard and the 6845 on the 80-column card had access to the same (video) memory, this was a "shared memory system"—one of the two main types of parallel processing architecture currently in use.

The second road being explored is a "distributed memory system" in which each microprocessor has its own array of memory and can, if the need arises, access any element of any other microprocessor's memory array.

The advantage of a shared memory system is that it's much easier to write the software needed to have each dedicated microprocessor work on that part of the problem for which it was designed. The difficulty with this setup is that the speed of the entire system is limited by the hardware network that connects it together. This limitation is similar to the one designers are confronting with single microprocessor computer designs.

In a distributed memory system, each microprocessor has its own set of memory, so the hardware problem is reduced. However, the software needed to let any microprocessor access any memory array in the system is incredibly complicated.

Most of the major computer manufacturers recognize the inherent limitations of a single-CPU computer design, and are experimenting with the idea of parallel processing for future machines. The final design will probably be some compromise between the two basic arrangements of memory and hardware. As things stand now, parallel processing is slowly creeping into the PC market. All the so-called "video accelerator cards" are smart cards with their own microprocessors—and the same is true of disk-controller cards. It's only a matter of time before the main processor is reduced to the role of a high-speed controller whose main job is to coordinate the activities of other special-purpose microprocessors on the motherboard.

FAN SHUT-OFF

I have a wood-burning stove with a fan that blows hot air. My problem is that when the stove cools off, the fan keeps blowing. Is there any simple solution that will turn the fan off when the stove cools down?—J. Rego, Pickering, Ont

I had a similar problem and spent several hours at the bench to arrive at a simple solution. It's not a terribly complex design problem, and I had a few possible approaches worked out on paper when my wife came up with the best one, which I used immediately.

Sometimes working on a problem and breaking it down to smaller parts blinds you to the obvious. The easiest and best way to handle your problem is to do exactly what I did—install a thermostat to control the fan. Any store-bought thermostat is designed to open and close a relay at a settable temperature, and that's exactly what you want to do.

The chances are that your fan motor is not the best designed piece of electrical machinery in the world, so rather than having the thermostat control the fan directly, it's a good idea to have it control a relay that will turn the fan on and off.

There are three other advantages to using a thermostat. The first is that it can be located anywhere you want in the room, and you can use very thin wire to connect it to the relay that's mounted near the motor. The third reason, more important to my wife, is that the thermostat isn't an eyesore.

DANGEROUS CLEANER

I have a small digital radio with pushbutton presets. When one of the buttons stopped working, I sprayed it with tuner

KELVIN ELECTRONICS

10 HUB DRIVE, MELVILLE, NY 11747

(800) 645-9212
(516) 756-1750
(516) 756-1763/FAX

Established 1945
M/C & VISA $20 Minimum Order
KELVIN CATALOG $3
Stock No. 650412

RE-ENGINEERED & DESIGNED FOR 1994

150 LE - Student 200 LE - Technician 400 LE - Engineer

Standard Features - ●AC & DC VOLTAGES ●DC CURRENT ●RESISTANCE ●TRANSISTOR ●CONTINUITY TEST - Buzzer ●DIODE TEST ●3 1/2 Digit LCD ●10M ohm INPUT IMPEDANCE

150 LE	200 LE	400 LE
BATTERY TEST TRANSISTOR DC CURRENT 10 Amp	FREQ COUNTER up to 20MHz TRANSISTOR CAPACITANCE from 1pF to 20uF AC/DC CURRENT 10 Amp	INDUCTANCE Resolution 1uH FREQ COUNTER up to 20MHz CAPACITANCE from 1pF to 200uF AC/DC CURRENT DUTY % 20 Amp
Stock # 990122	Stock # 990123	Stock # 990124
$29.95	$49.95	$79.95

Designed to meet IEC-348 & UL-1244 safety specifications

2 Year Warranty (Parts & Labor)

"Not only does the ***Kelvin* 94** boast alot of features ... the features go the extra distance."

"If we had to run into a burning building to do some emergency trouble-shooting and could carry in only one piece of equipment, the ***Kelvin* 94** would be it!"

Popular Electronics Reviewed - May 1993

KELVIN 94 *The Ultimate Meter*

LCR | Hz | dBm | True RMS | Logic Probe

The only meter with **0.1% Accuarcy** on DC Voltages, built-in **True RMS, Freq Counter to 20MHz** Res: 10 Hz, **LCR-Inductance Tester** Res: 10 uH, **DC/AC Voltages** Res:0.1mV, **Ohm Meter** Res: 0.1 ohms

TRUE RMS PLUS

Model 94
#990111
$199.95
*See Standard Features Listed below

12 INSTRUMENTS IN ONE - **AC & DC VOLTMETERS, AC & DC CURRENT, dBm, OHMMETER, DIODE TESTER, AUDIBLE CONTINUITY TEST, 20 MHz FREQ COUNTER, CAPACITANCE METER, INDUCTANCE METER, LOGIC PROBE**

ENGINE ANALYZER PLUS

Model 95 #990112
$199.95
A Must For Auto Mechanics

Standard Features plus - TEMP, TACHOMETER & DWELL ANGLE TESTER, DUTY CYCLE, 10M OHM IMPEDANCE, ANALOG BAR GRAPH, K-TYPE TEMP PROBE, ALLIGATOR CLIP TEST LEADS, INDUCTIVE PICKUP CLIP, 6' TEST LEADS & DELUXE CARRYING CASE

*** Standard Features - Models 94 & 95**

- DC/AC VOLTMETERS
- AC/DC CURRENT
- OHM METER
- DATA HOLD
- RELATIVE MODE
- FREQ COUNTER to 4 MHz (Model 95)
- AUDIBLE CONTINUITY TEST
- DIODE TEST
- MAX/MIN AVERAGE MEMORY RECORD
- 10A HIGH-ENERGY FUSE PROTECTION
- AUTO SLEEP & AUTO POWER OFF

KELVIN 100 Basic

990087
$19.95



- AC & DC VOLTAGES
- DC CURRENT
- RESISTANCE
- CONTINUITY TEST-Buzzer
- 3 1/2 Digit LCD
- LOW BATTERY INDICATOR
- DIODE TEST ●BATTERY TEST

CAPACITANCE METER

KELVIN 250 LE

990126
$59.95

- ACCURACY: 0.5%
- **RANGES:** 20mF, 2000uF, 200uF, 20uF, 2uF, 200nF, 20nF, 2000pF, 200pF
- Zero Adjust
- Safety Test Leads
- Test Socket for Plug-in Components

AUTO-RANGE METER

KELVIN 300 LE

990125
$49.95
AUTO-RANGE

- ACV & DCV
- DC CURRENT
- RESISTANCE
- CONTINUITY TEST
- DIODE TEST 3 1/2 Digit LCD
- 10M ohm INPUT IMPEDANCE

INSTRUMENTS

20 MHz SCOPE
Dual Trace 2 Yr Warranty-Parts & Labor
Stock No. 740085 ..... $385

40 MHz SCOPE 2 Yr Warranty
Dual Trace with Delayed Sweep
Stock No. 740086 ..... $655

TEST ACCESSORIES

SCOPE PROBES
60 MHz, X1 & X10 SPECIAL
700072 .... $18.95
150 MHz, X10
700073 ..... $39.95

IC CLIPS

SOLDER TYPE SPRING LOADED

Stock No.	COLOR	COST	25+ Qty
990104	BLACK	$.65 ea.	$.50 ea
990105	RED	$.65 ea.	$.50 ea

DC TOY MOTORS

DC Toy Motor
Stock No. 850647
$.80 ea
$.75 ea / 50+ Qty
6V DC High Speed

Solar Motor Stock No. 850646
$.60 ea 1.5V DC
$.55 ea / 50+ Qty

Solar Cells 3 3/4" L x 2 9/16" W
Stock No. 260099 1000mA .45V
$5.95 ea
$5.50 ea / 3+ Qty

DIGITAL TRAINER

Laptop Digital Trainer comes with 100 page instruction manual, power supply, built-in 1 digit true Hexadecimel display, two independent clocks with user adjustable freq & duty cycles, 4 data bit switches and 4 LED displays. ***Assembled***
Stock No. 840460 ..... $99.95

BINARY QUARTZ CLOCK w/Alarm



ORIGINAL DESIGN - 24 Hr. Binary Quartz Accurate Clock with 2 color LED's. Built-in **Alarm** and **Alarm Display** in binary code. **DESIGNED FOR LEARNING** *about digital circuitry & binary code.* Built with individual IC components. **Battery Memory Loss Prevention.** *Comes with rechargeable battery, DC wall transformer and* detailed instruction manual. **Advanced Level Kit**
Stock No. 840589 ..... $79.95

Electronic VOICE PAD



An electronic note pad, able to record your message & replay it later. It has a built-in photo cell & as soon as it senses your presence, it will automatically playback the message left for you. The components are PC mounted. The IC can record a message up to 20 seconds & no mechanical parts or tape - only a digital integrated circuit.
Intermediate Level Kit
Stock No. 840606 ..... $49.95

BREADBOARDS



Stock No.	Post	Contacts	YOUR COST
680093	0	500	$ 4.25
680097	0	840	$ 5.95
680098	2	1380	$11.75
680100	4	2390	$22.95

WIRE JUMPER KIT
Pre-cut, Pre-Stripped
330289 140 Piece Set ..... $ 4.95
330290 350 Piece Set ..... $ 8.95

COMPONENTS

WHOLESALE PRICES!

Stock No.	TYPE	(10 Pc. Min.) YOUR COST
600021	**555 TIMER**	$.29 ea
600029	**556 DUAL TIMER**	$.40 ea
600039	**LM566 PPL** FUNCTION GENERATOR	$.60 ea
600018	**741C OP-AMP** INTERNALLY COMPENSATED	$.30 ea
600026	**1458 OP-AMP** DUAL 741C OP-AMP	$.35 ea
630041	**2N2222**	$.20 ea
630383	**PN2222**	$.08 ea
600023	**7805 Voltage Reg**	$.36 ea

SILICON CONTROLLED RECTIFIER
(Similar to GE C106C1) 4.0 amp, 100PIV
600014 ..... $.89 ea ..... $.79 ea/10+

THERMISTER - 100 ohm
110097 ..... $1.35 ea ..... $1.00 ea/20+

THERMISTER - 10K ohm
110097 ..... $1.35 ea ..... $1.00 ea/20+

PROJECT PARTS

Project Speaker
2", 8 Ohm, .1 Watt
Stock No. 350009
59 ¢

Project BUZZER
3 - 9 Volt DC, 80 db
Stock No. 680089
$1.59 ea
$1.39 ea / 10+ Qty

Soldering IRON
with STAND
LONG LIFE TIP
Stock No. 990098
$3.95 ea

LED T 1 3/4

Stock No.	Color	100+ Qty	1000+ Qty
260020	RED	$.05 ea	$.045 ea
260027	GREEN	$.08 ea	$.07 ea
260026	YELLOW	$.08 ea	$.07 ea
260078	2 COLOR RED/GREEN	$.32 ea	$.29 ea

XENON STROBE TUBE
Stock No. 260050
$3.25 ea
$2.95 ea / 20+ Qty

TRIGGER COIL
for XenonStrobe Tube
Stock No. 320037
$1.25 ea
$ .89 ea / 20+ Qty

INFRARED LED
IR Pair, LED infrared transmitter and receiver
Stock No. 260061
$1.95 ea



NEON LAMP
NE2, 2" Lead
Stock No. 260003
$.15 ea
$.12 ea / 100+ Qty

PHOTO CELL
Photo Cell - 450 ohm
Stock No. 260017
$.65 ea $.45 ea /20+ Qty
Photo Cell - 1.5K ohm
Stock No. 260018
$.65 ea $.45 ea /20+ Qty

PUSH-BUTTON SWITCH
PUSH-ON, PUSH-OFF
Stock No. 270021
$.55 ea
$.49 ea / 100+ Qty

SUB-MINIATURE MOMENTARY SWITCH
Stock No. 990002
$.35 ea
$.28 ea / 100+ Qty

MINIATURE TOGGLE SWITCH
Stock No. 270034
$.90 ea Type - SPST
$.79 ea / 50+ Qty

CIRCLE 187 ON FREE INFORMATION CARD

cleaner, but I oversprayed and now some of the elements of the LCD display aren't working. I've tried drying it with a hair dryer and other less direct methods but nothing has worked. Any ideas?—J. Brown San Mateo, CA

I hate to tell you this, but I think the problem is not that something is keeping the display from working, but that it's been damaged permanently by the spray. A similar thing happened to my friend's VCR controller and we spent uncountable hours trying to fix it. I found that the tuner cleaner he used was also a lubricant, and while the cleaner solvent evaporated pretty quickly, it left a residue of lubricant which, as you might suspect, was also a conductor. Even though we dried the unit before putting the batteries back in, the remaining lubricant caused shorts between some of the LSI chip pins, and when we turned it on, the display blinked a few times and then disappeared into hyperspace.

The VCR controller was toasted, but the important lesson here is that if we had cleaned off the lubricant before applying power no damage would have been done. While I don't hold out a lot of hope for your radio, it's probably worthwhile to see if there's any residue from the cleaner hiding between the pins of either the display or the IC that's controlling it.

The high price paid for designing the radio to sell for a low retail price is the old warning "No user serviceable parts inside." That warning is more important now than it ever was. This is why it's usually cheaper to replace a unit of consumer electronics rather than have it repaired.

Design and Verify Circuits. Fast.

Analog Module includes:

- complete control over all component values
- ideal *and* real-world models for all active components
- resistors, capacitors, inductors, transformers, relays, diodes, Zener diodes, LEDs, BJTs, opamps, bulbs, fuses, JFETs and MOSFETs
- manual, time-delay, voltage-controlled and current-controlled switches
- independent, voltage-controlled and current-controlled sources
- multimeter
- function generator (1 Hz to 1 GHz)
- dual-trace oscilloscope (1 Hz to 1 GHz)
- Bode plotter (1 mHz to 10 GHz)
- SPICE simulation of transient and steady-state response



Digital Module includes:

- fast simulation of ideal components
- AND, OR, XOR, NOT, NAND and NOR gates
- RS, JK and D flip-flops
- LED probes, half-adders, switches and seven-segment displays
- word generator (16 eight-bit words)
- logic analyzer (eight-channel)
- logic converter (converts among gates, truth table and Boolean representations)

Complement Your Test Bench

Here's why Electronics Workbench belongs on *your* test bench: Wires route themselves. Connections are always perfect. And the simulated components and test instruments work just like the real thing. The instruments are indestructible and the parts bin holds an unlimited supply of each component. The result, thousands of electronics professionals and hobbyists save precious time and money. **Over 90% would recommend it to their friends and colleagues**. Electronics Workbench: the ideal, affordable tool to design and verify your analog and digital circuits before you breadboard.

And now the best is even better - Electronics Workbench Version 3.0 is here. It simulates more and bigger circuits, and sets the standard for ease of use. We guarantee it.*

NEW Features in Version 3

- new components include JFETs, MOSFETs, controlled sources, manual, time-delay and controlled switches
- real-world models for opamps, BJTs, JFETs, MOSFETs and diodes
- MS-DOS version now supports up to 16 MB of RAM for simulation of bigger circuits
- new Microsoft® Windows™ and Macintosh® versions available
- support now available on CompuServe®



Just $299!

Electronics Workbench®

The electronics lab in a computer™

Call: 800 263-5552

INTERACTIVE IMAGE TECHNOLOGIES LTD.
908 Niagara Falls Blvd. #068, North Tonawanda, NY 14120-2060
Telephone: (416) 361-0333 FAX: (416) 368-5799

*30-day money-back guarantee.

Prices in U.S. dollars, shipping $15. Offer valid in U.S. and Canada only.
All trademarks are the property of their respective owners.

INTERACTIVE

CIRCLE 182 ON FREE INFORMATION CARD

Ni-Cd RESISTANCE

Can you suggest a simple circuit that could measure the internal resistance of a Ni-Cd battery?—T. Ng, East Irvine, CA

I can't imagine why you would want to do something like this and, to tell you the truth, I've never thought much about it. While the cell's internal resistance is one of the parameters given by the battery's manufacturer, I suspect it's a value that's measured indirectly rather than by doing something like putting an ohmmeter directly across the battery terminals (and possibly destroying the meter in the process).

If I wanted to know the internal resistance of the battery, I believe that the best way to measure it is to put a known load across the terminals, measure the voltage and current, and then use Ohm's law to calculate the total resistance of the circuit. Once this is done, the battery's internal resistance could be determined by simply subtracting the measured load from the total circuit resistance.

You could check the results indirectly by measuring the battery's voltage while it's under load, and using that number, along with the current flow, to determine the cell resistance.

Ni-Cds aren't cheap, so before you start messing around with them it's a good idea to contact a Ni-Cd battery manufacturer and ask him for some advice as well. I'll bet that what you'll hear is either that you need specialized equipment for the job or that there's a standard load figure you have to use. Ω

Just like these Fully Trained Electronics Professionals

"Thanks to CIE I have tripled my previous salary, and I am now in a challenging and rewarding new field where only the sky is the limit."
Daniel Wade Reynolds
Industrial Electrician
Ore-Ida Foods

"CIE was recommended to me by my boss. It was appealing since I could study at my own pace at home and during business travel."
Dan Parks
Marketing Manager/Consumer Products
Analog Devices, Inc.

"I loved the flexibility CIE offered. It was the only way I could continue both school and my demanding job."
Britt A. Hanks
Director of Engineering
Petroleum Helicopters, Inc.

"I liked the way the school was set up with laboratory assignments to enforce conceptual learning. The thing which impressed me the most about CIE's curriculum is the way they show application for all the theory that is presented."
Daniel N. Parkman
Missile Electro-Mechanical Technician
U.S. Air Force

"Completing the course gave me the ability to efficiently troubleshoot modern microprocessor based audio and video systems and enjoy a sense of job security."
Tony Reynolds
Service Manager/Technician
Threshold Audio & Video

Graduate with an Associate Degree from CIE!

CIE is the best educational value you can receive if you want to learn about electronics, and earn a good income with that knowledge. CIE's reputation as the world leader in home study electronics is based solely on the success of our graduates. And we've earned our reputation with an unconditional commitment to provide our students with the very best electronics training.

Just ask any of the 150,000-plus graduates of the Cleveland Institute of Electronics who are working in high-paying positions with aerospace, computer, medical, automotive and communications firms throughout the world. They'll tell you success didn't come easy...but it did come...thanks to their CIE training. And today, a career in electronics offers more rewards than ever before.

CIE'S COMMITTED TO BEING THE BEST...IN ONE AREA...ELECTRONICS.
CIE isn't another be-everything-to-everyone school. CIE teaches only one subject and we believe we're the best at what we do. Also, CIE is accredited by the National Home Study Council. And with more than 1,000 graduates each year, we're the largest home study school specializing exclusively in electronics. CIE has been training career-minded students for nearly sixty years and we're the best at our subject...
ELECTRONICS...
IT'S THE ONLY SUBJECT WE TEACH!

CIE PROVIDES A LEARNING METHOD SO GOOD IT'S PATENTED.
CIE's AUTO-PRO-GRAMMED® lessons are a proven learning method for building valuable electronics career skills. Each lesson is designed to take you step-by-step and principle-by-principle. And while all of CIE's lessons are designed for independent study, CIE's instructors are personally available to assist you with just a toll free call. The result is practical training... the kind of experience you can put to work in today's marketplace.

LEARN BY DOING...WITH STATE-OF-THE-ART EQUIPMENT AND TRAINING.
CIE pioneered the first Electronics Laboratory Course and the first Microprocessor Course. Today, no other home study school can match CIE's state-of-the-art equipment and training. And all your laboratory equipment, books and lessons are included in your tuition. It's all yours to use while you study and for on-the-job after you graduate.

PERSONALIZED TRAINING....TO MATCH YOUR BACKGROUND.
While some of our students have a working knowledge of electronics others are just starting out. That's why CIE has developed twelve career courses and an A.A.S. Degree program to choose from. So, even if you're not sure which electronics career is best for you, CIE can get you started with core lessons applicable to all areas in electronics. And every CIE Course earns credit towards the completion of your Associate in Applied Science Degree. So you can work toward your degree in stages or as fast as you wish. In fact, CIE is the only school that actually rewards you for fast study, which can save you money.

Send for CIE's FREE Course Catalog and See How We Can Help Your Career Too!

FREE CATALOG

YES! I want to get started. Send me my CIE course catalog including details about the Associate Degree Program. (For your convenience, CIE will have a representative contact you - there is no obligation.)

Please Print Clearly **AE59**

Name _____

Address _____

City _____

State ____ Zip _____ Age ____

Phone No. _____

Check box for G.I. Bill Benefits.
☐ Veteran
☐ Active Duty

Cleveland Institute of Electronics, Inc.
1776 East 17th Street
Cleveland, OH 44114

A School of Thousands.
A Class of One. Since 1934.

LETTERS

Write to Letters, Electronics Now, 500-B Bi-County Blvd., Farmingdale, NY 11735

TELEPHONE RING AMPLIFIER

In *Q&A* (**Electronics Now**, Page 12, September 1993), M. Mitchell of Kansas City was looking for an amplifier circuit that would boost the ring level on a telephone. However, the answer published did not include a circuit that a reader could build to perform that very same function.



FIG. 1—TELEPHONE "BELL" amplifier circuit will let you hear (or see) an enhanced alarm if you are away from your telephone.

I designed the amplifier circuit shown in Fig. 1 so that I could hear my phone "ring" in my back yard. My "bell" is actually a horn of unknown origin that I found in my junk box. The power supply for this circuit can be any off-the-shelf 9- to 12-volt, 0.250-ampere wall outlet adapter.

If a higher powered signal is required, a relay or an optocoupler with a triac output can, with care, control a 120-volt AC horn, light, or both, replacing my "bell."

D.A. Butch
Tallahassee, FL

TESLA DEFENDED

I see that Don Lancaster continues to denigrate Nikola Tesla's. name. In a past column he referred to Tesla as a "lousy theoretician," and in the September 1993 column of *Electronics Now* he labeled Tesla "a superb con artist."

It appears that Lancaster paints all organizations with any connection to Tesla with one large, black paint brush. In one of his past columns, he listed our group, the Tesla Coil Builders Association, under "Resources at the Fringe," while in another we appear under "Free Energy" resources.

The Tesla Coil Builders Association is by no means a *fringe free-energy* organization. We resent these comments which, if directed at a living person, would be grounds for a libel suit. We request that Lancaster refrain from listing our group in future columns and that, if he does, our name be deleted before publication.

Judging from his bias on the subject of Tesla, I assume that Lancaster is unaware of tributes made to Tesla by such American electronics pioneers as Edwin H. Armstrong, John S. Stone, and L. W. Austin. In addition, his work was much admired by the French communications pioneer E. Girardeau and the German radio expert A. Slaby.

It is important that your readers be aware of the wide appreciation of Tesla's work and not be influenced by Lancaster's distorted opinions that were apparently formed in hindsight with a lack of knowledge.

HARRY GOLDMAN
Tesla Coil Builders Association
Queensbury, NY

LIGHTNING CONTROL UPDATE

On page 12 in the August 1993 *Q&A* column of **Electronics Now**, Fig.1 shows two simple circuits to that will debounce mechanical switch contacts—one with a positive and the other with a negative output pulse.

As a laboratory teaching assistant for a digital design class, I have seen those circuits in several textbooks. However, when my students actually built them, they failed to do what they were supposed to do—semester after semester. Moreover, when I built the circuit myself, it still did not work.

Figure 2-*a* is a copy of the earlier circuit, but the circuit shown in *b* is one that I designed. After building and testing it, I found that it works well.



FIG 2—CONTACT DEBOUNCERS revisited. The switch contact debouncer circuit *a* appeared in the August *Q&A*. However, a reader reports that the Schmitt-trigger version shown in *b* really works.

The new circuit is similar to the one shown in *a* in that it uses the same filtering principle. However, in place of the inverter logic shown, it has a Schmitt trigger inverter (such as a TTL 7414), which helps to prevent retriggering from switch-contact bouncing.

K. F. YEE
Raleigh, NC

SOURCE CORRECTION

The article "The Photoresist Method" (**Electronics Now**, December 1993) listed *Skychaser* as a

source in a list of circuit board manufacturers that provide prototyping and full production services for boards with up to 16 layers. We wish to advise you that Skychaser has changed its name to *Computerese*, and it has moved to 675 Sterling Drive, Charleston, SC 29412. The new phone number is 803-762-4809. We would like to apologize for any inconvenience that might have been caused by publishing an outdated name and address.—Editor

STORMY WEATHER

There were a few errors that found their way into my Weather Station article that appeared on page 40 in the November 1993 issue of **Electronics Now**.

First, I provided the wrong number for rain-gauge calibration. The number published was for a half gallon, *not* for one quart as stated. I'd like to point out that one quart of water through the rain gauge is equivalent to 1.15 inches of rainfall—and that amount is more than enough water for an accurate rain-gauge calibration.

Second, the anemometer and rain gauge connections shown in Fig. 4 on page 44 are incorrect. The anemometer connection should be between pins 8 and 21 on the J14 DB25F and the rain-gauge connection should be between pins 9 and 22.

Finally, Table 1, which was missing from the article, is presented here. RONALD M. JACKSON

TABLE 1—BAROMETER CALIBRATION

PRESSURE INHG	CALIBRATION VOLTAGE
31.1	5.120
31.0	4.985
30.9	4.851
30.8	4.716
30.7	4.581
30.6	4.446
30.5	5.312
30.4	4.177
30.3	4.042
30.2	3.907
30.1	3.773
30.0	3.638
29.9	3.503
29.8	3.368
29.7	3.234
29.6	3.099
29.5	2.964
29.4	2.829
29.3	2.695
29.2	2.560
29.1	2.425
29.0	2.291
28.9	2.156
28.8	2.021
28.7	1.886
28.6	1.752
28.5	1.617
28.4	1.482
28.3	1.347
28.2	1.213
28.1	1.078
28.0	0.808
27.9	0.808
27.8	0.674
27.7	0.539
27.6	0.404
27.5	0.269
27.4	0.135
27.3	0.000

COMBUSTIBLE GAS ALARM WARNING

Dave Williams, in his article entitled "Combustible Gas Alarm" (**Electronics Now**, July 1993), describes how reducing gases,

Be an FCC LICENSED ELECTRONIC TECHNICIAN!

No costly school. No commuting to class. The Original Home-Study course prepares you for the "FCC Commercial Radiotelephone License." This valuable license is your professional "ticket" to thousands of exciting jobs in Communications, Radio-TV, Microwave, Maritime, Radar, Avionics and more...even start your own business! You don't need a college degree to qualify, but you do need an FCC License.

No Need to Quit Your Job or Go To School This proven course is easy, fast and low cost! GUARANTEED PASS—You get your FCC License or money refunded. **Send for FREE facts now. MAIL COUPON TODAY!**

COMMAND PRODUCTIONS
FCC LICENSE TRAINING, Dept. 90
P.O. Box 2824, San Francisco, CA 94126
Please rush FREE details immediately!
NAME _____
ADDRESS _____
CITY _____ STATE _____ ZIP _____

AMAZING ELECTRONIC PRODUCTS and KITS

Remember those Martian Space Ships in HG Wells **War of the Worlds?**



MYSTERY Levitating Device
Objects float on air and move to the touch. Defies gravity! Amazing gift, conversation piece, magic trick or great scientific project.
ANT1K Easy-Ass'y Kit/Plans $19.50

3 MILE FM Wireless Microphone!
Crystal clear, ultra-sensitive pickup transmits voices, sounds to any FM radio. For security, monitoring children, invalids. Be the local DJ!
MVP1 Plans $7.00
MVP1K Kit/Plans $39.50

3 MILE Telephone Transmitter!

Automatically transmits 2 sides of phone conversation to any FM radio. Tunable, easy-assembly PC board. Operates only when phone is in use.
VWPM7 Plans $7.00
VWPMK7 Kit/Plans $39.50



TV & FM Joker/Jammer
Pocket size device lets you remotely disrupt TV or radio reception. Great gag! Discretion required. Easy-build electronic kit. **EJK1KM $19.50**

100,000 V - 20' Range Intimidation Device!
Electronic module, may be enclosed for handheld, portable, or fixed uses.
ITM2 Plans (creditable to kit) **$10.00**
ITM2K Kit & Plans $49.50

READY-TO-USE, AUTOMATIC Phone Recording System
Complete with extended play tape recorder & line interface switch. Automatically records both sides of conversation. *Check Local Laws on Proper Use!* Ready-to-Use System.
TAP20X System $149.50

Laser Pen
Pen sized laser, great for movies, drive- ins, pointer. Ready to use, with batt's. **LAPN1 Laser Pen . $149.50**

Pocket Laser Kit
3mw or 5mw kits, with solid state 670nm diode. Caution, Class IIIa item.
VRL3KM 3mw Laser Kit ... $99.50
VRL5KM 5mw Laser Kit .. $119.50

***MORE* Laser Kits!**
LAS1KM 1mw Laser, 632nm, HeNe Easy to Build Kit $69.50
LAS4KM 3mw Version, Kit $99.50

LATO5 Low Cost HeNe Laser Tube! .5mw Tube & Plans .. only $24.50
Other parts available separately.
Great Low Budget Science Project!

Shocker Force Field Vehicle Electrifier



Make hand shock balls, shock wands electrify objects, charge capacitors. Great pay back for those wise guys!
SHK1KM Easy-Assembly Kit $24.50

INFORMATION UNLIMITED
Dept RE-4 Box 716, Amherst NH 03031
Phone 603-673-4730 FAX 603-672-5406
MC, VISA, COD, Check Accepted. ADD $5 S&H.

Order by Mail, or by 24 Hr Order Phone: 800-221-1705

CATALOG! *with many more items!* **FREE with order, or send $1 P&H**

Measure It All!

The DMM/LCR Meter/ Frequency Counter. All in One.

Troubleshoot down to the component level — any component! Verify poorly marked parts, test for tolerances and damage. Wavetek's new DM27XT is not only a full-function DMM, but also includes complete inductance, capacitance, and frequency measurement capabilities.

- **Wide LCR range:**
  10 Ω to 2000 MΩ
  10 pF to 2000 µF
  100 µH to 20 H
- **Autoranging frequency meter 10 Hz to 20 MHz**
- **Ac and dc current to 20 A**
- **Logic test, diode test, max reading hold, continuity beeper, input warning beeper, fused input protection, battery saver**

Consolidate your test bench with one meter that does it all — Wavetek's high-performing, full-function XT Series DMM. It's all in one compact, rugged, field-ready package with a big 0.7-inch, 3½-digit display. Insulated probes and alligator clip leads are included, and there is a huge selection of accessories, including current, rf and HV probes, temperature converters, holsters, and cases. Ask for Wavetek DMMs. They're the meters to pick when you have things to fix.

$119.95

Other XT Series DMMs from $89.95

U.S.A.: (619)279-2200
Europe: (44/243) 531323
Asia Pacific: (852)865-1903

©1993 Wavetek Corporation

WAVETEK

CIRCLE 98 ON FREE INFORMATION CARD

such as methane, butane, propane, and carbon monoxide, can be detected with a tin-dioxide sensor-based alarm.

In that article the reader is advised to position the alarm near the ceiling because methane is lighter than air, and would therefore collect near the ceiling. However, in giving that advice, Mr. Williams did not point out that many reducing gases are *heavier* than air. Carbon monoxide, propane, and butane, for example, can accumulate at floor level to reach dangerous concentrations well before a ceiling-mounted alarm would be triggered.

In the interests of personal safety and the prevention of fires and explosions, please advise your readers of this fact.

R.C.S.
Excelsior, MN

LOOKING AT IR SIGNALS

I enjoyed the article "Remote-Control Tester" (*Electronics Now*, March 1993), but I have an easier approach. Although infrared (IR) is invisible to the human eye, the IR used in most remote controls is detectable with a common camcorder, because CCDs are sensitive to IR. To test a remote control, simply point the remote control at the camcorder and say cheese. You'll see the IR LED flash in the view finder if the remote control is operating properly.

JAMES SIUNIAK
Santa Paula, CA



Countersurveillance

Never before has so much professional information on the art of detecting and eliminating electronic snooping devices—and how to defend against experienced information thieves—been placed in one VHS video. If you are a Fortune 500 CEO, an executive in any hi-tech industry, or a novice seeking entry into an honorable, rewarding field of work in countersurveillance, you must view this video presentation again and again.

CALL NOW!

1-516-293-3751

HAVE YOUR VISA or MC CARD AVAILABLE

Wake up! You may be the victim of stolen words—precious ideas that would have made you very wealthy! Yes, professionals, even rank amateurs, may be listening to your most private conversations.

Wake up! If you are not the victim, then you are surrounded by countless victims who need your help if you know how to discover telephone taps, locate bugs, or "sweep" a room clean.

There is a thriving professional service steeped in high-tech techniques that you can become a part of! But first, you must know and understand Countersurveilance Technology. Your very first insight into this highly rewarding field is made possible by a video VHS presentation that you cannot view on broadcast television, satellite, or cable. It presents an informative program prepared by professionals in the field who know their industry, its techniques, kinks and loopholes. Men who can tell you more in 45 minutes in a straightforward, exclusive talk than was ever attempted before.

Foiling Information Thieves

Discover the targets professional snoopers seek out! The prey are stock brokers, arbitrage firms, manufacturers, high-tech companies, any competitive industry, or even small businnesses in the same community. The valuable information they filch may be marketing strategies, customer lists, product formulas, manufacturing techniques, even advertising plans. Information thieves eavesdrop on court decisions, bidding information, financial data. The list is unlimited in the mind of man—especially if he is a thief!

You know that the Russians secretly installed countless microphones in the concrete work of the American Embassy building in Moscow. They converted what was to be an embassy and private residence into the most sophisticated recording studio the world had ever known. The building had to be torn down in order to remove all the bugs.

Stolen Information

The open taps from where the information pours out may be from FAX's, computer communications, telephone calls, and everyday business meetings and lunchtime encounters. Businessmen need counselling on how to eliminate this information drain. Basic telephone use coupled with the user's understanding that someone may be listening or recording vital data and information greatly reduces the opportunity for others to purloin meaningful information.

CLAGGK INC. EN
P.O. Box 4099 • Farmingdale, NY 11735

Please rush my copy of the Countersurveillance Techniques Video VHS Cassette for a total cost of $53.95 each (which includes $4.00 postage and handling).

No. of Cassettes ordered _____.
Amount of payment $_____.
Sales tax (N.Y.S. only) _____.
Total enclosed _____.
Bill my ☐ VISA ☐ MasterCard
Card No. _____
Expire Date _____ / _____

Signature _____
Name _____
Address _____
City _____ State _____ ZIP _____

All payments in U.S.A. funds. Canadians add $4.00 per VHS cassette. No foreign orders.

The professional discussions seen on the TV screen in your home reveals how to detect and disable wiretaps, midget radio-frequency transmitters, and other bugs, plus when to use disinformation to confuse the unwanted listener, and the technique of voice scrambling telephone communications. In fact, do you know how to look for a bug, where to look for a bug, and what to do when you find it?

Bugs of a very small size are easy to build and they can be placed quickly in a matter of seconds, in any object or room. Today you may have used a telephone handset that was bugged. It probably contained three bugs. One was a phony bug to fool you into believing you found a bug and secured the telephone. The second bug placates the investigator when he finds the real thing! And the third bug is found only by the professional, who continued to search just in case there were more bugs.

The professional is not without his tools. Special equipment has been designed so that the professional can sweep a room so that he can detect voice-activated (VOX) and remote-activated bugs. Some of this equipment can be operated by novices, others require a trained countersurveillance professional.

The professionals viewed on your television screen reveal information on the latest technological advances like laser-beam snoopers that are installed hundreds of feet away from the room they snoop on. The professionals disclose that computers yield information too easily.

This advertisement was not written by a countersurveillance professional, but by a beginner whose only experience came from viewing the video tape in the privacy of his home. After you review the video carefully and understand its contents, you have taken the first important step in either acquiring professional help with your surveillance problems, or you may very well consider a career as a countersurveillance professional.

The Dollars You Save

To obtain the information contained in the video VHS cassette, you would attend a professional seminar costing $350-750 and possibly pay hundreds of dollars more if you had to travel to a distant city to attend. Now, for only $49.95 (plus $4.00 P&H) you can view ***Countersurveillance Techniques*** at home and take refresher views often. To obtain your copy, complete the coupon or call.

EQUIPMENT REPORTS

ITT Pomona Logic Scope Probe

Turn your oscilloscope into a logic analyzer!



CIRCLE 14 ON FREE INFORMATION CARD

Many technicians and hobbyists need a logic analyzer occasionally, but not often enough to justify the purchase of a full-featured unit. That's just who the *Logic Scope Probe* is built for. The Logic Scope Probe, from ITT Pomona (1500 E. Ninth Street, Pomona, CA 91766) turns any analog oscilloscope into a simple logic analyzer.

The Logic Scope Probe is housed in a small, beige, plastic box that measures about 4½ × 2½ × 1½ inches. An eight-inch cable extends from the right side of the unit; a BNC connector on its end allows connection to an oscilloscope. Up to eight digital data lines can be connected to the unit through a special cable. That ribbon cable plugs into the bottom of the Logic Scope Probe; its other end is terminated in eleven small *Micrograbber* clips.

Eight of the clips serve as data inputs, one as a clock input, and the final two are used to supply power to the unit. Normally, the probe is powered from the unit under test. An external supply, which prevents the instrument from loading down the circuit under test, is available as an option.

The Logic Scope Probe has three modes of operation. First is the logic-analyzer mode in which the oscilloscope becomes an 8-channel logic analyzer with a memory depth of 16 words. Each channel is displayed as one horizontal line on the oscilloscope's screen in a timing-diagram fashion. Three independent memory banks are available, each with a depth of 16 words.

The second mode of operation is the trigger-probe mode, in which the unit generates a trigger signal whenever an 8-bit user-selected condition is met. Because the scope's signal inputs aren't connected to the Logic Scope probe in that mode, so the scope can be used to observe analog signals.

The third mode is the MUX or multiplexer mode in which the scope displays eight digital signals in real time simultaneously. No data is acquired and stored in memory, however.

Up to three Logic Scope Probes can be daisy chained in all modes, to provide a 16- or 24-channel system. However, one scope channel is required for each probe input; a three-channel scope would be required to view 24 channels simultaneously. If simultaneous viewing isn't imperative, the three units can be hooked up to the scope sequentially.

In the logic analyzer mode, the probe operates in two cycles: display and acquisition. First, data is acquired and stored in one of three 16-word memories. Then it is displayed on a oscilloscope with eight traces corresponding to the eight input channels. (A trigger signal is also provided for the scope.) A START/STOP pushbutton is used to switch the probe between its display and acquisition modes.

If the TRIGGER POSITION switch is set to BEGIN, the Logic Scope Probe will begin storing data when the data at its inputs correspond to the trigger word set by eight three-position switches on the top panel. Each switch can be set to logic high, low, or "don't care." When the input to the eight data lines matches the switch settings, a trigger is generated and the probe begins storing data in memory.

If the TRIGGER POSITION switch is set to END, the probe will stop storing data with the trigger condition is met. The Logic Scope Probe can be set to sample the data on either the rising or falling edge of the clock pulse.

The Logic Scope Probe can be used to capture data that occurs both before and after the trigger event. To do that, the acquisition would be repeated twice, once with TRIGGER POSITION set to BEGIN and once with it set to END. The first acquisition would be stored in memory position 1, and the second in memory position 2. Two probes could be used in a similar manner to capture the data simultaneously.

The Logic Scope Probe cannot replace a logic analyzer because of its limited functionality. For example, its operating frequency range is limited to 20 MHz. Its memory depth is limited to 16 words, and it has no provisions for saving the memory to disk. In the best case, only 24 data channels can be displayed.

However, the Logic Scope Probe is not intended to be a substitute for a full-function analyzer, but to provide a portable, easy-to-use instrument for quick troubleshooting in the field, and occasional use on the bench. It does all those things well, and at a suggested retail price of $330, it seems like a good buy. Ω

NEW PRODUCTS

Use the Free Information Card for more details on these products.

STAMP-SIZED SINGLE-BOARD COMPUTER. The *BASIC Stamp* miniature single-board computer from *Parallax, Inc.* runs BASIC. Not much larger than a postage stamp, the 1 × 2-inch computer board is intended for data acquisition, interfacing, and industrial control in systems where the low cost of components is an important consideration.

The *Stamp* is available separately or as part of a development kit that also includes a three-pin downloading cable, editor software, and a manual. The editor is used for developing programs for the *stamp* on a personal computer. Those programs can be converted into PBASIC tokens at the touch of a key, downloaded through the three-pin cable, and executed.

The *Stamp's* PBASIC program is said to be easy to learn. Instructions are provided for high-speed digital, analog, and serial input/output as well as for debugging, power control, table look-up, and on-board EEPROM access. Program size is limited to about 80 PBASIC instructions, but several *Stamps* can be connected to perform longer programs.

CIRCLE 16 ON FREE INFORMATION CARD

Each *Stamp* includes an 18-pin RISC microcontroller and an 8-pin EEPROM. The microcontroller interprets PBASIC and manages the I/O lines, while the EEPROM stores the tokens. About 2000 PBASIC instructions can be executed each second. A small prototyping area on the board allows circuitry to be added to the *Stamp's* eight general-purpose I/O lines.

A single *Stamp* is priced at $39, and the development kit sells for $139. PBASIC interpreter chips, which are used in custom circuits, are available for $6 each in minimum quantities of 25.

Parallax, Inc.
3805 Atherton Road #102
Rocklin, CA 95765
Phone: 916-624-8333
Fax: 916-624-8003
BBS: 916-624-7101

VGA-TO-VIDEO CONVERTER. *JDR Microdevices' VGA–NTSC Converter* is a personal computer accessory that is capable of driving an NTSC monitor. The converter, when connected to the PC, allows presentations to be displayed on low-cost video monitors instead of large-screen VGA monitors. It is intended for use in seminars, lecture halls, or in video-tape production. Light in weight and small in size, it can be used "on the road" with notebook or laptop computers.

CIRCLE 17 ON FREE INFORMATION CARD

The converter output can be plugged into a standard or S-video VCR, permitting the production of custom training tapes. A built-in flicker filter is said to reduce eye fatigue, and TV auto blanking and brightness controls keep the displays sharp.

JDR Microdevices offers an optional video splitter/buffer capable of driving up to eight monitors from a single VGA card for presentations that require more than one VGA monitor.

The *VGA–NTSC* converter is priced at $299.95.

JDR Microdevices
2233 Samaritan Drive
San Jose, CA 95124
Phone: 408-559-1200
Fax: 408-559-0250

CELLULAR/DATA LINK. The *Intelligent Data Equipment Adaptor (I.D.E.A.)* from *Ora Electronics* allows any modem or fax machine to be connected directly to a portable cellular phone. This "intelligent" cellular telephone data link permits data or faxes to be sent and received automatically when it is plugged into the cellular telephone.

The microprocessor-controlled *I.D.E.A* system generates a dial tone, controls the functions of the portable cellular telephone, and includes a standard RJ-11 interface for modem or fax connections. Completely transparent to the modem or fax machine, the system works with all popular communication and fax software packages. It is compatible with all modem-equipped computers or fax machines that have RJ-11 interfaces, without the need for purchasing additional software.

The *I.D.E.A.* system is available for most popular

CIRCLE 18 ON FREE INFORMATION CARD

cellular telephones, such as those offered by AT&T, Motorola, NEC, and OKI. However, an optional cellular-telephone adaptor cable allows it to be used with other portable cellular telephone brands. The system includes the *I.D.E.A.*, a cellular-phone-specific cable, a modular telephone cord, a 9-volt battery, and a user's guide.

The *Intelligent Data Equipment Adaptor* system is priced at $249.95.

ORA Electronics
9410 Owensmouth Avenue
Chatsworth, CA 91311
Phone: 818-772-2700

DIGITAL SYNTHESIZER CARD. *Novatech's DDS3 PC* direct digital synthesizer is a 12-MHz precision signal source for IBM and compatible personal computers. It has a stated 5-ppm accuracy and 10-ppm/year stability. *Novatech* claims that it offers spectral purity comparable to that of its earlier and more costly digital synthesizers.



CIRCLE 19 ON FREE INFORMATION CARD

Phase noise is specified as less than −90 dBc at 1 KHz offset, spurious signals are specified as below −45 dBc, and harmonics are specified as less than −40 dBc. Output amplitude is 12 volts peak-to-peak into an open circuit, and this can be attenuated in 10-dB steps to 70 dB.

The *DDS3 PC* can generate sine and TTL- and HCMOS-compatible clock signals simultaneously from 2 Hz to 12 MHz in 2-Hz steps. The card includes a C-language program that runs under DOS to make the setting of frequency and attenuation easier. The program also permits users to set or to sweep through a set of frequency, attenuation, and dwell time settings. A driver for a Windows-based ATE program is available as an option.

The *DDS3 PC* direct digital synthesizer card is priced at $399.

Novatech Instruments, Inc.
1530 Eastlake Avenue East
#303
Seattle, WA 98102
Phone: 206-328-6902
Fax: 206-328-6904

AUDIO ANALYZER SYSTEM. *Liberty Instruments'* new *IMP Audio Analyzer* is a full-featured fast Fourier transform spectrum, impedance, and network analyzer. It is intended for use with IBM- or compatible personal computers.

The *IMP Audio Analyzer* connects to the PC through the PC's printer port. The analyzer has inputs for two clip probes and one microphone which are included. The instrument has an output for rectangular pulses or optional maximum-length-sequence (MLS) test signal.

The *IMP's* graphically-based software package allows the extraction of quasi-anechoic acoustic measurements, transient response analysis in three-dimensional "waterfall" format, and correction for microphone response. It permits the merging of data taken from multiple measurements, delay compen-

FAX DIRECTORY LISTING

COMPANY	FAX NUMBER
Alfa Electronics, Inc.	(609) 275-9536
All Electronics Corporation	(818) 781-2653
A.M.C. Sales, Inc.	(303) 494-4924
B.G. Micro	(214) 271-2462
Caig Laboratories, Inc.	(619) 451-2799
Chemtronics, Inc.	(404) 717-2111
Communications Specialists, Inc.	U.S. – (800) 424-3420 Int'l – (714) 974-3420
C&S Sales, Inc.	(708) 520-0085
Danbar Sales Company	(909) 592-2940
Electronic Rainbow, Inc.	(317) 291-7269
Fair Radio Sales Co., Inc.	(419) 227-1313
Fusion Electronics, Inc.	(516) 599-6495
Gateway Products Corp.	(305) 974-6818
Gateway Electronics	(314) 427-3147
Global Specialties	(203) 468-0060
Goldstar Precision Co. Ltd.	(310) 921-6227
Hameg Instruments	(619) 630-6507
Interactive Image Technologies Ltd.	(416) 368-5799
Jameco Electronic Components & Computer Products	(800) 237-6948
Mark V Electronics, Inc.	(213) 888-6868
MCM Electronics	(513) 434-6959
Mondo-Tronics, Inc.	(415) 455-9333
Moody Tools, Inc.	(401) 885-4565
Mouser Electronics	(817) 483-0931
MWK Industries	(909) 278-4887
Northeast Electronics	(508) 695-9694
Number One Systems Ltd.	011 44 480 494042
PC Boards	(205) 933-2954
People's College of Independent Studies	(407) 847-8793
Print Products International	(800) 545-0058
Howard W. Sams & Company	(317) 298-5604
Sencore, Inc.	(605) 339-0317
Sibex, Inc.	(813) 726-4434
Startek International, Inc.	(305) 537-5577
Suncoast Technologies	(904) 596-7599
The Engineers Collaborative, Inc. (TECI)	(802) 525-3451
Toroid Corp. of Maryland	(410) 860-0302
Wavetek Corp. (formerly Beckman Industrial)	(619) 565-9558

Electronics NOW® FAX FORM

DIRECT READER/MFR CONTACT

Need data in a hurry?

Don't worry!

Just clip this form carefully along the dotted lines, fill it out (PLEASE PRINT) and fax it to the company of your choice today!

For fastest response, please send directly to manufacturers.

Fax numbers are on the page to the left.

If you need more than one form, please make copies of this original.

Electronics Now provides this fax form as a service to its readers. A quick response from you indicates your company's willingness to do business with the sender.

Electronics NOW® FAX RESPONSE

TO: _____
Company Name Fax Number

I urgently need more information about your _____ products.

I saw your products on Page _____ in the _____ issue of **EN**;
(Month/Year)

ADDITIONAL NOTE:

_____

_____

_____

_____

FROM: _____
Sender's Name Title

_____
Company Name:

_____
Street

_____
City Country

_____
Phone Fax

We are a(n) ☐ manufacturer ☐ service center ☐ engineering company
☐ R&D center/laboratory ☐ other ( )

Electronics NOW®

500-B Bi-County Boulevard, Farmingdale, NY 11735 Tel: 1-516-293-3000 Fax: 1-516-293-3115



CIRCLE 20 ON FREE INFORMATION CARD

sation, and inductor- or capacitor-value measurement.

Automated macro operations can be performed, and the analyzer is capable of extracting loudspeaker parameters from their impedance curves. Measured data can be saved to and retrieved from disk, and all screen graphics can be printed out. Version "M" of the software provides on-line help, mouse interface, overlay plots, on-trace markers, and it can support the MLS hardware option. Both dynamic range and noise immunity can be enhanced while measurement time can be reduced with an IMP/MLS enhancement board that is an option.

The *IMP Audio Analyzer* with "M" 2.0 software and the MLS enhancement option is priced at $599. A basic kit version without an enclosure sells for $275.

Liberty Instruments, Inc.
P. O. Box 1454
West Chester, OH 45071

FUNCTION GENERATOR. The new *Fluke PM 5135* function generator is a benchtop instrument suitable for many different general-purpose applications. These include education and training, audio and electronics servicing, production testing, and product development.

According to *Fluke*, the *PM 5135* is easy and fast to set up because of its clean, logical front panel control layout. Frequency is selected by pushbuttons in four decade ranges, a logarithmic dial, and a Vernier control with a range of ± 20% of the dial setting. The standard sine, triangle, and square waveforms are also pushbutton selected. The function generator's duty cycle is a standard 50 %.

Frequency sweeping can be single or continuous, with a logarithmic characteristic and a continuously variable sweep ratio from 1 to 2000. The sweep range is 3.5 decades, and the sweep period is continuously adjustable over a range of 10 to 150 seconds. It can be triggered with a pushbutton or from an external source.



CIRCLE 21 ON FREE INFORMATION CARD

The attenuation range of the *PM 5135* is 0 to 60 dB in 10-dB increments, or it is continually variable over a 0 to 20-dB range. Both modes are pushbutton selectable. The function generator's output is protected from short circuits.

Fluke PM 5135 function generator is priced at $795.

Fluke Corporation
P. O. Box 9090
Everett, WA 98206
Phone: 800-44-FLUKE
Fax: 206-356-5116

VOLTAGE-MONITORING IC'S WITH BATTERY BACKUP SWITCH. *Rohm Corporation* is offering the *BA6129F* and *BA6162/F*, new voltage-monitoring integrated circuits. Each includes two factory-set thresholds. The circuits



CIRCLE 22 ON FREE INFORMATION CARD

monitor the voltage to external devices such as volatile RAM memories in memory cards, palmtop computers, and scanners.

If the host equipment's supply voltage falls below the first threshold, the voltage monitor switches to a standby mode. If the second threshold is reached, the monitor IC automatically switches demand from the primary power supply to a battery backup supply.

The detection voltage for the *BA6129F* is 3.5 volts for the standby mode and 3.3 volts for the backup mode. The detection voltage for the *BA6162/F* is a higher 4.2 volts, but its backup mode switching voltage is also 3.3 volts. Internal circuitry provides hysteresis to prevent circuit instability during power supply switching.

Both voltage-monitoring IC's are available in 8-pin surface-mount, small-outline IC (SOIC) packages, and the *BA6162/F* is also packaged in an 8-pin DIP.

The *BA6129F* and BA6162/F voltage-monitoring ICs are priced at $.50 each in 1000-piece quantities.

Rohm Corporation
3034 Owen Drive
Antioch, TN 37013
Phone: 615-641-2020
Fax: 615-641-2022

TEMPERATURE SIMULATORS. Two new handheld temperature simulators from *Wavetek* can be adjusted in 1° and 0.1° increments over a wide range. Both Models *473* and *475* can measure a 4- to 20-milliampere signal while simulating temperature. The simulators are intended for calibrating temperature transmitters and signal conditioners.

Both temperature simulators can simulate four different sensors for calibration purposes and measure their output for display on an LCD digital temperature indicator. The LCD readouts and a user-friendly keypad are said to make the simulators easy to read and use. Their compact size and long battery life make them suitable for field servicing.



CIRCLE 23 ON FREE INFORMATION CARD

The *473* is intended for thermocouple calibration. It directly emulates type K, J, and T thermocouples, and it will source up to 100 millivolts DC to simulate other thermocouples. The *475* simulates resistance temperature detectors (RTD). It will directly simulate both 0.00385 and 0.00392 type platinum 100-ohm RTDs and copper 10-ohm RTDs. It will also source up to 1000 ohms for the calibration of other RTDs, and it can also calibrate standard potentiometer settings.

The *473* temperature simulator is priced at $795 and the *475* is priced at $895.

Wavetek Corporation
9145 Balboa Avenue
San Diego, CA 92123
Phone: 619-279-2200

TINY VOLTAGE-CONTROLLED OSCILLATOR. *Z-Communications* claims its new *Model SMV2500 VCO* is the world's smallest voltage-controlled oscillator (VCO) integrated circuit. It was developed for wireless local-area networks (LAN). Small package size was emphasized to minimize its "footprint" on the "credit-card-" size circuit boards that fit in laptop personal computers.

The *SMV2500 VCR* will oscillate in the 2.4 GHz to 2.485 GHz frequency range. It operates from a 3-volt DC supply voltage, and typically draws only 16 milliamperes. Phase noise is specified at −85 dBc/Hz at a 10 kHz offset, and its second harmonic minimum is −20 dBc. The VCO package measures 0.3×0.3×0.117 inch.

CIRCLE 24 ON FREE INFORMATION CARD

The *SMV2500* voltage-controlled oscillator is priced at $5.75 each in 100,000 quantities. Samples are priced at $150 each.

Z-Communications, Inc.
9939 Via Pasar
San Diego, CA 92126
Phone: 619-621-2700
Fax: 619-621-2722

RF SWEEP GENERATOR. *Lurie Instrument's* new *LI10A* radio frequency sweep generator has two built-in channel amplifiers. It can permit the frequency responses of two S-parameters to be monitored on a two-channel oscilloscope.



CIRCLE 25 ON FREE INFORMATION CARD

The benchtop 1.2-GHZ sweep generator offers fast continuous sweep, marker grids with single crystal time base, and stepped and continuous level adjustment. Sweep width is variable from 2 MHz to full range. The 50- and 75-ohm accessories available include a detector head, a reflection bridge with built-in detector, and a signal divider. Also available from *Lurie* are a bias tee, a 20-dB attenuator, and a 50/75-ohm minimum loss pad.

The *LI10A* RF sweep generator is priced at $1685.

Lurie Instruments
2738 Orange Avenue
La Crescenta, CA 91214
Phone: 818-957-7714
Fax: 818-957-2208

DUAL AND QUAD VIDEO OP AMPS. The *EL2210* and *EL2211* dual video operational amplifiers and *EL2410* and *EL2411* quad versions of those op-amps from *Elantec* are made with the complementary bipolar (BiCMOS) process. The op-amps were developed specifically for consumer video equipment.

The *EL2210* and *EL2211* dual op-amps operate from ± 5-volt supplies with a gain of +1 with 50-MHz bandwidth. Both the dual op-amps will drive a 150-ohm load to +2 volt and −1 volt with a 100-MHz bandwidth. Slew rate is 130 volts per microsecond.

EL2410 and *EL2411* quad versions operate at ± 5 volts at a gain of +2 with 100 MHz of bandwidth. Differential gain for the quad op-amps is specified at 0.07%, and differential phase at 0.15°.

The dual op-amps are available in 8-pin plastic DIP packages and 8-lead small-outline transistor (SOT) packages. The quad versions are available in 16-pin plastic DIP and 16-lead small-outline packages.

The pricing for the video op-amps begins at $2.40 each in 100 quantity.

Elantec, Inc.
1996 Tarob Court
Milpitas, CA 95035
Phone: 408-945-1323
Fax: 408-945-9305 Ω



CIRCLE 26 ON FREE INFORMATION CARD

A tradition of technical excellence continues. . .

Howard W. Sams & Company is proud to announce a new alliance with **Prentice Hall Computer Publishing**. Sams is now the Master Distributor of Prentice Hall titles in the electronic distribution market. What does this mean to you, the Howard W. Sams & Company customer? We are now able to offer you nearly a thousand titles on technical and computer subjects with the dependability and thoroughness you have come to expect from Sams' products. Contact your local Sams distributor or a customer service representative at our toll-free number for more information.

alpha books · Hayden Books · NRP New Riders Publishing · que · Brady · SAMS PUBLISHING · PROMPT PUBLICATIONS

800-428-7267

Howard W. Sams & Company
2647 Waterfront Parkway, East Drive
Indianapolis, Indiana 46214

CIRCLE 180 ON FREE INFORMATION CARD

Try the

Electronics NOW®

bulletin board system

(RE-BBS)
516-293-2283

The more you use it the more useful it becomes.

We support 1200 and 2400 baud operation.

Parameters: 8N1 (8 data bits, no parity, 1 stop bit) or 7E1 (7 data bits, even parity, 1 stop bit).

Add yourself to our user files to increase your access.

Communicate with other R-E readers.

Leave your comments on R-E with the SYSOP.

RE-BBS
516-293-2283

NEW LITERATURE

Use The Free Information Card for fast response.

Total Recall: The Ultimate Guide to Memory Management; by Gary Saxer and Ellen Sander. Osborne McGraw-Hill, 2600 Tenth Street, Berkeley, CA 94710; Phone: 510-549-6600; Fax; 510-549-6603; $19.95.

This book will give you a clear understanding of personal computer memory—both concept and actual hardware. It's information you'll need to make informed purchasing decisions and solve any problems related to memory that you might encounter.

CIRCLE 40 ON FREE INFORMATION CARD

This guide by Saxer and Sander delves into the history of computer memory, and explains how and why the various kinds of computer memory evolved. You'll find a straightforward explanation of how the memory in your personal computer works, how your applications software finds the memory it needs, and how to provide more memory for those applications. You'll also find out how to master memory management with DOS 6 and other memory mangers, and you'll learn how to troubleshoot problems in DOS and Windows operating systems and local-area networks (LAN).

You'll find the information you need to install and configure memory, and you'll learn how memory works in the multitasking environment. The guide also tells you how to determine how much memory your computer is using. A special question-and-answer section is devoted to many common memory problems and their solutions, including how to respond to memory error messages and how to solve hardware conflicts that can prevent your PC from booting or cause it to crash.

Amateur Radio RV Antennas; by Robert K. Benson, W2HZF. Tiare Publications, P. O. Box 493, Lake Geneva, WI 53147; Phone: 414-248-4845; $14.95 plus $2 shipping and handling.

This is the book for amateur radio operators who want to take their avocation along with them when they take off on their vacations. Existing amateur radio equipment makes it practical to take your radio gear with you in a recreational vehicle or set it up at a campground. You can even operate from a yacht, if you so desire.

The author cautions that the right antenna is essential for good communications with a ham station in the field. The book explains what to look for in antennas—construction, materials, size and directivity—if you want to purchase a factory-built antenna for field



CIRCLE 39 ON FREE INFORMATION CARD

use. It also gives you guidance on how to build and install suitable antennas if you elect the do-it-yourself route.

The special operating conditions found on a wide variety of recreational vehicles such as motor homes, campers, trailers, and even boats are described. This book will help the amateur match his antenna system to the RV of his choice to obtain maximum communications efficiency.

Benson's book describes the antennas best suited for receiving and transmitting while you are driving, and it identifies those best suited for operating at a fixed location such as a campground. The recommended mounting positions and procedures are detailed. Tips are provided on the selection and installation of ancillary equipment for an efficient mobile ham station.

The Mac Internet Tour Guide: Cruising the Internet the Easy Way; by Michael Fraase. Ventana Press, P. O. Box 2468, Chapel Hill, NC 27515; Phone: 919-942-0220; Fax: 919-942-1140; $27.95, including diskette.

This combination book and disk will help Mac computer users master the Internet. It does this by replacing obscure Unix commands with the icons and boxes familiar to Mac users. The book explains how to get connected and make use of Internet in a simple, step-by-step format that allows readers to proceed at their own pace.



CIRCLE 38 ON FREE INFORMATION CARD

Fraase's book will be a roadmap to Internet's information resources for both novices and experienced Mac computer users. It explains network benefits, and it provides an overview of the history and growth of Internet with predictions about its future growth. Fraase also explains how the Internet is organized and its networking protocols. He also discusses the requirements for good networking "manners."

The disk contains file-transfer software that lets users visit remote sites quickly and easily to download desired programs and files. Included are E-mail

5 sure steps to a fast start as a high-paid computer service technician

1. Choose a complete training program for a secure tomorrow



Jobs for computer service technicians will almost double in the next 10 years, according to the latest Department of Labor projections. For you, that means unlimited opportunities for advancement, a new career, or even a computer service business of your own.

But to succeed in computer service today, you need training—complete, practical training that gives you the confidence to service any brand of computer. You need NRI training.

Only NRI—the leader in career-building, at-home electronics training for 80 years—gives you useful knowledge, hands-on skill, and real-world experience with a powerful 486sx computer you keep. NRI is all you need to succeed in this growing, profitable field.



2. Move beyond "book learning" to try things for yourself

NRI knows you learn better by doing. So NRI training works overtime to give you that invaluable practical experience. You first read about the subject, studying diagrams, schematics, and photos that make the subject even clearer. Then you do. You build, examine, remove, test, repair, replace. You discover for yourself the feel of the real thing, the confidence gained only with experience.

3. Get inside a 486sx computer system

If you really want to get ahead in computer service, you have to get inside a state-of-the-art computer system. That's why NRI now includes a high-speed 486sx mini-tower computer as the centerpiece of your hands-on training.

As you build this 1 meg RAM, 32-bit CPU from the keyboard up, you actually see for yourself how each section of your computer works. You assemble and test your computer's "intelligent" keyboard, then interface the power supply and high-density floppy disk drive. But that's not all.

You go on to install a powerful new 200 meg hard disk drive and Super VGA Color Monitor, today's most wanted computer peripherals. Now not only will you dramatically increase your computer's storage capacity, but you'll get to enjoy the drama and impact of a full-color display!

Plus, now you train with and keep the latest in diagnostic hardware and software: the R.A.C.E.R. plug-in card and QuickTech software program, both from Ultra-X. Using these state-of-the-art diagnostic tools, you learn to quickly identify and service virtually any computer problem on IBM-compatible machines.



4. Make sure you've always got someone to turn to for help

Throughout your NRI training, you've got the full support of your personal NRI instructor and the entire NRI technical staff. Always ready to answer your questions and help you if you should hit a snag, your instructors will make you feel as if you're in a classroom of one, giving you as much time and personal attention as you need.

5. Start a bright new future by sending for your FREE catalog today!



Discover for yourself how easy it is to succeed in computer service. Return the coupon to get NRI's big, full-color catalog describing every aspect of NRI's incomparable computer training, as well as training in TV/video/audio servicing, telecommunications, industrial electronics, and other growing high-tech career fields. Find out more about how step-by-step training the NRI way will help get you where you want to go!

If the coupon is missing, write to: NRI Schools, McGraw-Hill Continuing Education, 4401 Connecticut Avenue NW, Washington, DC 20008.

NRI Schools

McGraw-Hill Continuing Education Center
4401 Connecticut Avenue, NW, Washington, DC 20008

For career courses approved under GI Bill ☐ check for details.

☑ **CHECK ONE CATALOG ONLY**

- ☐ **Microcomputer Servicing**
- ☐ TV/Video/Audio Servicing
- ☐ Telecommunications
- ☐ Industrial Electronics/Robotics
- ☐ Basic Electronics
- ☐ Computer Progamming
- ☐ PC Applications Specialist
- ☐ Multimedia Specialist
- ☐ Programming in C++ with Windows
- ☐ Bookkeeping & Accounting

Name _____

Address _____

City _____ State _____ Zip _____

Accredited Member, National Home Study Council 3-0194

software that converts Internet's Unix commands to a form that is easier for Mac owners to use and decompression software that decodes files from most personal computers.

30th Anniversary Catalog. Jensen Tools Inc., 7815 South 46th STreet, Phoenix, AZ 85055-5399; Phone: 800-426-1194; Fax: 800-366-9662; free.

Jensen's 256-page master catalog describes the company's product line. Photographs and pricing information accompany each item described. The catalog includes tool kits, cases and carts, personal computer accessories, telecommunications equipment, and test equipment for local-area networks and fiber optics. It also includes wire, cable, crimpers, wire-wrap tools, and soldering equipment.

CIRCLE 37 ON FREE INFORMATION CARD

For the workplace there are workbenches, tools, boxes and containers that prevent damage from electrostatic discharge, circuit boards, lighting fixtures, and cleaning equipment. The catalog contains color-coded pages to simplify the search for desired products, a table of contents, and a detailed index.

Silicon Photodiodes 1994 Catalog. Centronic, Inc., 2088 Anchor Court, Anchor Business Park, Newbury Park, CA 91320; Phone: 805-499-5902; Fax: 805-499-7770; free.

This full-color, 50-page catalog from Centronic includes product photographs and specifications for the company's standard and application-specific photodiodes. Included are charts and data that will help buyers select the right photodiode for any given application.



CIRCLE 36 ON FREE INFORMATION CARD

The catalog includes a handy photodiode selection guide and a six- page technical tutorial on photodiodes. It covers structure, theory of operation, and spectral response. The text explains temperature effects and key parameters, and includes typical circuit diagrams and commonly used abbreviations. The catalog includes outlines of photodiode dies, package outlines, and precautions for handling photodiodes.

WordPerfect 6: The Pocket Reference; by Mella Mincberg. Osborne McGraw-Hill, 2600 Tenth Street, Berkeley, CA 94710; Phone: 510-549-6600; Fax; 510-549-6603; $9.95.

This pocket-sized reference book is said to contain all the information needed to guide WordPerfect 6 users to expert-level proficiency in a step-by-step format. It is arranged to give readers the answers they need as fast as possible, and it contains an alphabetical listing of all the important WordPerfect 6 functions and features. This version includes such features as desktop publishing, mail-merging, changing styles, and preparing tables and columns.



CIRCLE 35 ON FREE INFORMATION CARD

An overview section covers such general topics as cursor movement, codes, and blocking. A handy pull-out command card consolidates the most important commands and features. The book is said to be more streamlined than a manual, but far more detailed than a command card.

Hands-on exercises allow novices to work at their own pace as they build their skills. All the basic features from typing and editing to retrieving, saving, and printing documents are described. The reader with experience in word processing who is upgrading to WordPerfect 6 from an earlier version will find all the information needed to switch over and become productive quickly.

All Thumbs Guide to Home Security; by Robert W. Wood. Tab Books Inc., Blue Ridge Summit, PA 17294-0850; Phone: 1-800-233-1128; $9.95.

This illustrated guide is offered with the claim that it will provide homeowners and renters with all the information they'll ever need to safeguard their homes against burglary and fire. Moreover, it is sold with a money-back guarantee that novices will be able to complete the projects successfully without outside help.



CIRCLE 34 ON FREE INFORMATION CARD

According to its author, Bob Wood, you don't need formal training in wiring and electricity to carry out the inexpensive security measures he discusses. Wood claims that, if organized effectively, the projects detailed in the book can reduce the risk of fire and intrusion significantly—and they might even help to reduce insurance rates.

It includes easy-to-follow directions on how to install burglar alarms, smoke detectors, outdoor lighting, and indoor and outdoor motion sensors. You'll find instructions on the installation of deadbolt, anti-slide and other security locks on doors and windows. It even explains how to position shrubs and plants around a house to deter unwanted intrusion.

Build Your Own Low-Cost Data Acquisition and Display Devices; by Jeffrey Hirst Johnson. Tab Books Inc., Blue Ridge Summit, PA 17294-0850; Phone: 1-800-233-1128; $19.95.

Here is a book that explains how to make flexible and affordable data-acquisition and display devices for any IBM-compatible computer. It includes all the information that you'll need to turn a personal computer into a high-performance data-acquisition system.

Johnson's book includes circuit designs and step-



CIRCLE 33 ON FREE INFORMATION CARD

by-step instructions for building a wide variety of portable plug-in devices that allow fast, effective data communication in many different situations. After presenting the basic principles of data transmission, Johnson tells you how to program interfaces for serial and printer ports. He also explains how to design circuits for parallel and serial interfacing and digital sensing and measurement.

Included in the book is a complete project for building a versatile digital voltmeter and writing a simple data-acquisition program. Also included are software routines to support the hardware and information on data formats and rates, cabling and connectors, and troubleshooting. Ω

From the Lab to your Living Room!

Does your VCR have a "Head Cold?"

Probably not! However, through constant playing and using of degrading dry or wet cleaners, the output of your video tapes has slowly diminished to an unacceptable level and the VCR plays as if it has a head cold! The culprit is most likely clogged and dirty video and/or audio heads.

The **3M Black Watch™ Head Cleaner Videocassette** uses a patented magnetic tape-based cleaning formation to remove head clogging debris. No foreign substances such as cloth, plastics or messy liquids and no harsh abrasive materials are present. The cleaner's usable life is 400 cleanings or more!

It's easy to use. Place the **3M Black Watch™ Head Cleaner Videocassette** in the VCR and press the Play button. A pre-recorded message appears clearly on your screen and an audible tone is heard, telling you that the cleaning process is now completed. No guess work, you never over clean!

3M Black Watch™ Head Cleaner Videocassette S-VHS VHS.....$19.95

Once your VCR's head cold is cured, and the unit plays like new, consider using the finest videocassette you can buy—the **3M Black Watch™ T120 Hi Pro VHS 4410 Videocassette.** The 4410 is the highest performing videocassette available today for use with all standard format VHS recording hardware!

Here's what you hear and see....A sharp, clear picture—brightest colors—freedom from streaks, flashes and snow—outstanding high-fidelity audio reproduction—optimum camcorder performance—maintains recording integrity. **3M Black Watch™** video tape is 100% laser inspected to guarantee surface smoothness and drop-out free performance.

3M Black Watch™ T120 Hi Pro VHS 4410 Videocassette VHS.....$8.00

CLAGGK INC. — *3M VHS Special Offer*
P.O. Box 4099, Farmingdale, New York 11735

Yes, I like your offer and here is my order for 3M Black Watch™ products!

___ 3M Black Watch™ Head Cleaner Videocassette ($19.95 each) _____$

___ 3M Black Watch™ T120 Hi Pro VHS 4410 Videocassette ($8.00 each) $ _____

Shipping and handling per order **$ 4.00**

Total Amount in U.S. Funds only $ _____

New York State residents add local sales tax. Canadians add $6.00 per order. No foreign orders. Do not send cash.

Bill my ☐ VISA ☐ MasterCard Expire Date ___/___/___

Card No. _____

Signature _____

Name (Please print) _____

Address _____

City _____ State _____ ZIP _____

GET THE LATEST ADVANCES IN ELECTRONICS

WITH A SUBSCRIPTION TO

Electronics NOW®

Radio Electronics® Combined with

Electronics NOW
December 1993
BUILD A MINIATURE VIDEO TRANSMITTER that works with virtually any video camera!
Build an AUDIO SCRAMBLING SYSTEM and keep your phone conversations private!
Learn how to make HIGH-QUALITY PC BOARDS at home!
Build our high-tech XMAS ORNAMENTS and add color to your holidays!
Learn how to put TRANSISTOR OSCILLATORS to work in your next design!
Build our EPROM EMULATOR for working with microcontrollers
GERNSBACK PUBLICATION

Electronics Now gives you exciting articles like:

- Buyer's Guide to Digital Oscilloscopes
- Build A Scanner Converter
- Single-Chip Voice Recorder
- Build A MIDI Interface for your PC
- Troubleshoot Microprocessor Circuits
- Build A High-Power Amplifier for your Car
- Add Music On Hold to your Phone
- All About Binaural Recording
- VGA-to-NTSC Converter

ENJOY THE WORLD OF ELECTRONICS EACH MONTH!

Subscribe to the best electronics magazine—the one that brings you the latest high-tech construction projects, feature articles on new technology, practical troubleshooting techniques, circuit design fundamentals, and much more.

Electronics Now looks to the future and shows you what new video, audio and computer products are on the horizon. What's more you'll find helpful, monthly departments such as Video News, Equipment Reports, Hardware Hacker, Audio Update, Drawing Board, Computer Connections, New Products, and more. All designed to give you instruction, tips, and fun.

BUILD AN ULTRASONIC RADAR STATION and keep tabs on your surroundings!
Build this COMPUTERIZED WEATHER STATION and track temperature, pressure, wind, and humidity!
A look at PC-BASED TEST EQUIPMENT
Use our CIRCUIT COOKBOOK to build working transistor circuits!
Build a triple-output POWER SUPPLY for your test bench!
How to use HEAT MANAGEMENT techniques to protect your projects!
Learn TV SERVICE techniques by ex...
OCTOBER 1993
NOVEMBER 1993
BOOST THE PERFORMANCE OF ANY CAR STEREO
Get better FM reception and eliminate picket-fencing with our diversity antenna circuits!
TOUCH-TONE DECODER Display dialed digits on an LCD readout!
TRACK THE WEATHER Computer-controlled monitoring station is a forecaster's dream!
100-WATT DUMMY LOAD For trouble-free transmitter tuneup
TRANSISTOR COOKBOOK Increase your know-how

FOR FASTER SERVICE CALL TODAY

1-800-999-7139

DON'T DELAY SUBSCRIBE TODAY!

Just fill out the order card in this magazine and mail it in today.

7RB44

TAKE BACK CONTROL OF YOUR TELEPHONE

Know who's calling you before you pick up the phone with this easy-to-build Caller-ID circuit.

TERRY J. WEEDER

HAVE YOU EVER BEEN TOO BUSY TO answer your phone but afraid of missing an important call? Are you tired of spending your dinner time brushing off annoying telephone salesmen? Build our caller-ID circuit and you will see the telephone number of the calling party *before* you answer. *You* can decide whether or not you want to talk to the caller. The caller ID system can also retain in memory the phone number of the five most recent calls, and the time of day that they were received.

About caller ID

The service that makes it possible to display the number and time of incoming calls is known as CND (calling number delivery). This service is now available in most major communities. Check with your local telephone company to see if it is available in your area. CND is a subscriber feature that transmits digital data that indicate the date, time, and number of the calling party during the silent period between the first and second ring. You must subscribe to the service to receive the data, which will be received whether the caller subscribes or not. (Most phone companies, however, provide a means for a caller to block the transmission of his number.) The fee for the Caller-ID service is about $6.50 per month.

The date and time information is sent on all calls, but the actual calling number will be available only from parties who are calling from within your area. At the present time your area consists of local calls that originated from where the CND is available. The number can be blocked by the calling party, in which case a special code is sent in place of the number indicating that this is the case. A special code is also sent if the call originated from outside your area.

The data is transmitted serially with the least-significant bit first, at a rate of 1200 bits per second. The data is modulated using frequency-shift keying (FSK), with 1200 Hz being a logical 1 (mark) and 2200 Hz being a logical 0 (space). Each 8-bit word is preceded by a start bit (space) and followed by a stop bit (mark). In addition, up to 10 mark bits can be added between words.

The portion of the message that contains the calling number is preceded by a "type code" of 04 hex. The first word to follow is a "length" word, which is the number of words in the message. That is followed by the date, time, and number in ASCII format, and a "check sum." For example, the data for a call made at 1:30 PM on February 12 would be sent as follows:

typelength
02129413305135551212
checksum

Note that the time is in the 24-hour format.



FIG. 1—THE HEART OF THE CALLER ID circuit is microcontroller IC1 which processes the serial data from IC2, outputs ASCII characters to DISP1, and monitors switches S1–S3.



FIG. 2—TIMING RELATIONSHIPS between the data present on the phone line (top), and the output pins of IC2.

Circuit theory

A schematic diagram of the Caller-ID circuit is shown in Fig. 1. Motorola's new MC145447 calling line identification receiver chip (IC2) strips the FSK tones from the telephone line and converts them to TTL-level data. The tones are coupled through C3, C4, R2, and R3 to the input pins 1 and 2 of IC2. Bridge rectifier BR1 converts the ring voltage to DC and applies it through attenuator R4-R6 to the RING-DETECT inputs (pins 3 and 4) of IC2. Figure 2 shows the timing relationship of IC2's output pins when the data is being received.

The heart of the circuit is IC1, a PIC16C55 EPROM-based 8-bit CMOS microcontroller manufactured by Microchip Technology, Inc. This microcontroller has two 8-bit I/O ports and one 4-bit I/O port. An internal EPROM memory holds the program that decodes the data output by IC2, controls the LCD display, and senses any input from three switches. A preprogrammed PIC16C55 is available from the supplier listed in the Parts List. Code for programming the chip yourself is available on the *Electronics Now BBS* (516-293-2283, 1200/2400, 8N1) as a file called CID.ZIP.

Figure 3 is a flowchart of the operating software. The RING DETECT pin of IC2 is constantly monitored by IC1. When a low is detected on this pin (indicating a valid ring pulse on the telephone line) IC1 pulls pin 7 of IC2



FIG. 3—FLOWCHART of the operating software for the microcontroller. A pre-programmed microcontroller is available from the source mentioned in the Parts List.



CALLER ID COMPONENT SIDE.



CALLER ID SOLDER SIDE.



FIG. 4—PARTS-PLACEMENT DIAGRAM. The 14-conductor ribbon cable that should be used to connect the display module to Pin 1 on the main board is indicated by a rectangular pad instead of a oval one.

low, placing the chip in the active mode. IC1 then waits for a low on the CARRIER DETECT pin. If a low is not detected within 1.5 seconds, IC1 aborts the process and resumes monitoring RING DETECT. If a CARRIER DETECT does occur within this time period, IC1 looks for the first start bit on IC2's DATA pin. If the start bit does not occur within 1 second, the process is again aborted. This "find or abort" process of monitoring the outputs of IC2 ensures that IC1 knows exactly when the data is going to be sent and is not fooled by glitches on the telephone line (such as those caused by lifting the receiver), or by the detection of any ring pulses after the first one.

The microcontroller does not have an I/O port specifically designed for serial input, so the programming software converts the serial data output from IC2 into 8-bit parallel data. When a start bit is detected on IC2's DATA line, IC1 waits for a time period equal to 1.5 bits before it reads the data line. That ensures that the DATA line is midway through the first bit after the start bit when being read. The most-significant bit of IC1's receive register is initially set to equal the state of the data line. The register then shifts one place to the right, waits for a time period equal to 1 bit (placing it mid-way through the second bit), and then reads IC2's DATA line. IC1 again sets its receive register's MSB equal to IC2's DATA line and then shifts the register one place to the right. After eight cycles of reading and shifting, IC1 holds one 8-bit word in its receive register. After IC1 verifies that there is a stop bit, it either stores the 8-bit word in a separate register or discards it as depicted in the flowchart.

The first word of the calling number stream is 04 hex. When that word is received, IC1 knows that the data that follows is calling-number data. As IC1 receives the data from IC2, it identifies the characters which will be sent to the 16-character LCD readout (DISP1) and stores them in 16 internal registers (one register for each character space in the display). After receiving all the calling-number

PARTS LIST

All resistors are ¼-watt, 10%, unless otherwise specified
R1—130 volts RMS varistor
R2, R3, R10–R12, R15–R18—10,000 ohms
R4—470,000 ohms
R5—18,000 ohms
R6—15,000 ohms
R7—270,000 ohms
R8, R9—2000 ohms
R13, R19—47,000 ohms
R14—10,000 ohms, trimmer potentiometer
Capacitors
C1, C2—0.2 µF, 100 volts, Mylar
C3, C4—470 pF, 50 volts, ceramic disc
C5—0.22 µF, 35 volts, tantalum
C6, C9, C10, C12—0.1 uF, 50 volts, Mylar
C7, C8—15 pF, 50 volts, ceramic disc
C11—47 uF, 35 volts, electrolytic
Semiconductors
BR1—1-amp, 200-PIV, full-wave bridge rectifier
D1—1N753, 6.2-volt Zener diode
IC1—PIC16C55, 8-bit microcontroller (Microchip)
IC2—MC145447, calling line identification receiver (Motorola)
Q1—MPSA13, NPN Darlington transistor
Other components
DISP1—16×1 LCD module
XTAL1—3.58-MHz TV colorburst crystal
S1–S3—SPST momentary push-button switch
Miscellaneous: Enclosure, PC board, IC sockets, 9-volt alkaline battery or 9-volt AC-to-DC wall adapter, telephone cord with modular plug, battery clip, ribbon cable, wire, solder, etc.
Note: The following items are available from Weeder Technologies, P.O. Box 421, Batavia, Ohio 45103:
- **Double sided PC board (WTCID-B)—$9.50**
- **Kit of all board-mounted components including preprogrammed PIC16C55 (WTCID-C)—$24.50**
- **LCD display module (DISP16X1)—$18.50**

All orders must include an additional $3.50 for shipping and handling. U.S. and Canadian orders only. Ohio residents must add 6% sales tax.
Note: Call your local telephone company to verify that Caller-ID service is available in your area before ordering.

data and changing the time from a 24-hour format to a 12-hour format, IC1 outputs the contents of its 16 registers to the LCD display through port C. The LCD display is wide enough to display only the time of day and the 7-digit telephone number, so the date and area code is discarded.

If the calling party is blocking the transmission of his number, a letter "P" will be received immediately after the date and time. In this case IC1 loads—along with the time—the word "PRIVATE" into its registers in place of a telephone number. Similarly, if the calling party is outside your area, a letter the letter "O" is received instead of the telephone number. IC1 then loads, along with the time, the message "OUT AREA" in its registers.



FIG. 5—THE COMPLETED PROTOTYPE. The small project case is the perfect size to place next to your telephone.

The LCD has its own internal memory which holds five 16-character messages. Each time a call comes in, IC1 addresses and writes to the next 16-character block, returning to the first block after reaching block number 5. Therefore DISP1 will always be holding the last five calls in memory. If IC1 detects an input from switch S1 or S2, it sends the instructions to DISP1 to shift the display backward or forward; it still remembers the address of the last block written to, however, and returns the display to this block when a new call comes in. If IC1 detects an input from S3, it clears the display and erases all contents in the display memory.

The circuit can be powered by either a 9-volt battery or DC wall adapter. A regulator is formed by Q1, D1 and R19, which drops the 9 volts down to 5 volts. The regulator is specifically designed to draw low current for longer battery life. The circuit draws only about 1 milliampere in the standby mode, and about 12 to 14 milliamperes when a call comes in.

Construction

The circuit is assembled on a 2.5- × 3-inch double-sided PC board. The foil patterns for the PC board are provided for those who wish to etch their own board. A pre-made PC board is also available from the source mentioned in the Parts List. Follow the parts-placement diagram shown in Fig. 4. Start by mounting IC sockets for IC1 and IC2. Pay particular attention to the pads on IC1 which have traces running between them. It is very easy to create a bridge of solder between those pads and the traces if you're not very careful.

Mount the resistors, capacitors and all other components. Pay attention to the orientation of the polarized components such as C5, C11, and D1. The pad spacing for Q1 is very tight, so extra care should be observed when soldering this component. Crystal XTAL1 should not be seated all the way down onto the board when soldering it because there is a chance that the metal case of the crystal will short the pads together. Use twisted pairs of insulated hookup wire to connect the switches as shown. However, make sure the switches are installed in the case cover before you solder the leads to them.

Use a length of 14-conductor ribbon cable to connect the display module to the board. Separate the wires on each end of the cable for a length of about 1 inch to make it easier to solder them to the PC board and the display

Continued on page 84

Long-Range BODY-HEAT DETECTOR

Build this instrument that detects the infrared emission of humans and animals for security or for performing science experiments.



ROBERT IANNINI

A PYROELECTRIC DETECTOR IN THIS battery-portable instrument detects the presence of animal or human intruders night or day by sensing their body heat. The detector can supplement your home security system, or you can monitor animals for nature study or find sources of heat loss.

This project will introduce you to the fundamentals of infrared emission and detection. The instrument could help you locate hidden or buried heat sources that could be wasting heat in your home. Detectors capable of "seeing" in the nonvisible infrared region have proven themselves extremely useful in nighttime law enforcement and in military operations on land and in the air around the clock.

This instrument can detect the presence of humans or animals up to several hundred feet away by sensing their body heat, which corresponds with a specific wavelength emission. Its narrow 8° field of view makes it suitable for detecting intruders passing through doors or moving along corridors inside a building. In addition, it can detect the presence of persons or animals entering the defined sensitive zone along roads or paths outdoors.

The best results will be obtained if the instrument is mounted on a camera tripod or other rigid support. When securely mounted, it can be panned manually or by electric drive over a wide sector to obtain a wider field of view. That makes it easier for the user to discriminate between true and false targets.

Pyroelectric detector

The heat sensitive elements in this instrument are two lithium tantalate ($LiTaO_3$) crystals within the TO-5 metal transistor case of the pyroelectric detector. The metal case has a rectangular silicon window in its cap for admitting infrared energy as well as a high-value resistor, and a low-noise field-effect transistor (FET).

The pyroelectric detector and pinout are shown in Fig. 1-*a*, and Fig. 1-*b* is a simplified schematic of the sensor circuit. Thermal compensation within the case prevents errors due to ambient temperature variations. The detector has a spectral range of 6 to 14 microns centered on 10 microns in the infrared band. This range is determined by the characteristics of the silicon window at the end of the TO-5 case.

The infrared emission from human and animal body heat is in the 10 micron infrared (IR) band that corresponds to the "black body" temperature of 100°F (300 K) and a frequency of 30,000 GHz. All objects whose temperature exceeds absolute zero (0 K) radiate energy as a function of the fourth power of temperature.

When the pyroelectric detector is exposed to infrared radiation in the 6 to 14 micron band, the temperatures of its lithium tantalate crystals change, unbalancing the charges on each crystal's surface. This unbalanced condition, which shows up as a voltage variation at the output of the sensor, indicates that infrared energy has been detected. The dual crystals in the detector cancel signals obtained from sunlight, open fires, or radiators because the crystals in the device are oppositely polarized.

To detect infrared emission, either the heat-emitting target must be moving or a shutter must periodically break or "chop" the path between the target and sensor. In this detector, the path is chopped by a motor-driven shutter whose speed can be controlled.



FIG. 1—DUAL-ELEMENT PYROELECTRIC detector pinout arrangement (*a*) and simplified schematic (*b*).

Although a moving source will produce a changing signal, a rapidly moving object could be missed because of the instrument's narrow viewing angle and relatively slow detector response. As a result, you will probably want to operate the chopper motor for most object detection.

The infrared energy is focused on the sensitive rectangular window at the end of the detector case with a translucent plastic Fresnel lens, which has a focal length of approximately 5 centimeters. This translucent lens is transparent to infrared energy in the 10 micron region.

Operating modes

The thermal detector operates



FIG. 2—SCHEMATIC FOR THE INFRARED DETECTOR CIRCUIT. Panel potentiometer R15, J1 and J2, and LED1 are located on the end cap of the amplifier section.



NOTES:

1. IC1, IC2, IC3, MOUNTED IN SOCKETS
2. RESISTORS MOUNTED VERTICALLY:

R2, R4, R5, R6, R7, R8, R12
R14, R16, R17, R18, R19
R21, R22

3. PERFORATED BOARD 0.42 IN HOLES, 0.1×0.1 IN GRID
4. WIDTH DIMENSION TO FIT ID OF TUBE (SEE TEXT)

FIG. 3—LAYOUT OF THE CIRCUIT BOARD showing optimum component placement for point-to-point wiring. The circuit board width is determined by the inside diameter of the housing tube.

All resistors are ¼-watt, 10% unless otherwise specified.

R1, R20—10,000 ohms
R2, R3, R5, R6, R7, R10, R12, R13, R14. R16, R21—39,000 ohms
R4, R8—1,800,000 ohms
R9—1000 ohms
R11—25,000 ohms trimmer potentiometer, 8 mm vertical PC mount, Mouser Electronics 32RM403 or equivalent
R15/S1—1000 ohms control potentiometer, miniature panel mount, Mouser Electronics 31CT301 or equivalent
R17, R18—1,000,000 ohms
R19—390,000 ohms
R22—470 ohms
R23—200 ohms, trimmer potentiometer, 8 mm horizontal PC mount, Mouser Electronics 32RH202 or equivalent.

Capacitors

C1, C5, C8—1000 µF, 16 volts, aluminum electrolytic
C2, C4, C7, C9, C11—4.7 µF, 25 volts, aluminum electrolytic
C3, C6, C12—0.01 µF ceramic disc
C10—0.047 µF, 100 volts
C13—1 µF, 50 volts

Semiconductors

PYR1—dual pyroelectric detector, 3-pin TO-5 case, P2288 Hamamatsu Corp.
IC1—LM358N, dual operational amplifier, 8-pin DIP, National Semiconductor or equivalent
IC2—LM393N, dual comparator, 8-pin DIP, National Semiconductor or equivalent
IC3—NE555N timer, 8-pin DIP, Signetics or equivalent
Q1, Q2—N2222 NPN transistor
LED1—Light-emitting diode, T-1, yellow
D1—1N5230 Zener diode, 4.7 volts

Other components

BZ1—Piezoelectric buzzer, 6 volts, Mouser 25MS060 or eqivalent
J1, J2—Jack, 3.5 mm ID
PL1, PL2—Plug, 3.5 mm OD
MOT1—DC motor, 0 to 12 volts, low-torque , slow speed, MCM Electric No. 58-500 or equivalent.
SO1—transistor socket, 3-pin (for PYR1)

Miscellaneous: Fresnel lens, polyethylene, 0.77 focal length, 1½-inch, Fresnel Technical No. IR2 or equivalent, perforated circuit board, 0.1-inch grid (see text), plastic or metal tubing, end cap and inserts (see text), two sockets for 8-pin DIP ICs, T-1 LED snap-in holder, 28 AWG insulated tinned copper wire (nine-strand ribbon cable (see text), two 9-volt battery clips with insulated wires, two 9-volt alkaline transistor batteries, tinned copper wire, plastic adhesive, plastic screw, solder.

Note: The pyroelectric detector is available from Hamamatsu Corp. Bridgewater, NJ (201) 231-0960. The Fresnel lens is available from Fresnel Technical, 101 Morningside Drive, Ft. Worth TX 76110, (817) 926-7474.

The following items are available from Information Unlimited, Box 716 Amherst, NH 03031 (603)-673-4730, fax 603 672-5406;

- **A kit of all parts including tubing cut to length, circuit board, pyroelectric detector, motor and all active and passive components except batteries—$69.50**
- **Pyroelectric detector and motor—$12.50**

Please add $5.00 for shipping and handling. Allow 4 to 6 weeks for delivery.

in two detection modes: moving or stationary target. The moving detection mode permits the user to detect intrusions by *moving* people or animals. The detector's field of view in this mode is narrow enough to be able to sense intrusions in restricted spaces, and its detection range is about 100 meters. In this mode it rejects constant background thermal energy.

The stationary mode permits the detection of stationary "hot spots" against a "cold" background such as a back yard or open space at night. Preferred in a search for hidden persons,



FIG. 4—CUTTING AND FORMING DIRECTIONS for the plastic or aluminum tubes for housing the sensor/amplifier and shutter/lens assemblies.

animals, or heat sources, this mode is so sensitive that some valid responses might seem to be false alarms.

System operation

Refer to the schematic, Fig. 2. The output of pyroelectric detector PYR1 is fed to the input of the low-frequency, dual-stage amplifier and filter IC1. The LM358N amplifier IC1-a, with a gain of about 2500, responds to a frequency of 0.1 to 10 Hz, peaking at about 1 Hz. This range matches the response of PYR1 to the infrared spectrum commonly generated by humans or large animals that is centered at about 10 microns.

The changing output of the filter IC1-b is further amplified by a factor of about 40 by PN2222 transistor Q1. This output can be capacitively coupled to an AC meter through EXTERNAL AC METER JACK J1. The output of J1 is an analog indication of signal strength, which should be between 20 and 100 millivolts.

The AC output of Q1 is also fed to IC2-a and b, an LM393N dual plus or minus "window" comparator. Trimmer potentiometer R11 sets the threshold activation level for buzzer BZ1. The output of IC2-a and b is sent to an AND gate, and its output is sent to the pin 2 TRIGGER input of the NE555N timer IC3.

The output of IC3 can activate buzzer BZ1 and LED1 that are connected in series. LED1 illuminates when a target has been detected. Buzzer BZ1's *on* time is controlled by the 1-megohm timing resistors R17 and R18 across pins 8, 7 and 6, and capacitor C13 at pin 6. Panel potentiometer R15 (located on the end cap of the case) adjusts system temperature range and response to anticipated target size and temperature.

An optional chopper motor speed control consists of PN2222 transistor Q2 and trimmer potentiometer R23. Zener diode D1 provides a positive turn-on signal. Jack J2 provides DC drive for the shutter motor MOT1 through PL2.

External controls

Three access holes are formed in the tubular enclosure for the detector. One access port permits the lens position to be adjusted and the angle of PYR1 to be aligned for optimum results when the finished instrument is being set up. (This port is covered with an opaque band or tape to keep out ambient light when the instrument has been adjusted.)

Two other access holes are formed in the case to permit the two trimmer potentiometers R11 (buzzer threshold) and R23 (chopper motor speed adjust) to be set by a small insulated screwdriver or plastic trimmer adjusting tool. Panel-mount control potentiometer R15 can be set by a knob fitted on its shaft.

Chopper motor MOT1 speed can be set for optimum shutter chopping speed for detecting stationary objects by trimmer potentiometer R23. It produces the necessary "step function" in the infrared input signal.

Case material

Obtain a 12-inch length of aluminum or plastic tubing with an inner diameter of approximately 1.5 inches and a wall thickness of approximately 0.060 inch. Obtain a suitable plastic or aluminum cap with an inside diameter that will fit



FIG. 5—CUTAWAY VIEW OF THE INFRARED BODY HEAT DETECTOR with details for making the shutter, lens mount, and end-cap assemblies.

snugly over the end of the tube.

Also obtain a 10-inch length of aluminum or plastic pipe with an exterior diameter of about 1.5 inches and a wall thickness of about 0.060 inch that telescopes snugly inside the larger tube. Then obtain an aluminum or plastic cap or cup about 1 inch deep that will fit snugly inside the smaller diameter tube.

Circuit board assembly

Refer to the electrical schematic Fig. 2 and the parts layout diagram Fig. 3. The amplifier circuit board was dimensioned to contain all of the electronic components and be able to slide inside the tubular case. The prototype circuit board was cut from perforated board with a 0.1 inch grid to a length of 5¼ inches by 1½-inches, the approximate inside diameter of the housing tube. The width of the board should be cut slightly oversize. It can be sanded or ground down so that it can be press fit snugly inside the tube.

The parts layout as shown in Fig. 3 is intended to keep interconnection leads as short as possible. All connections are made with untrimmed component leads except for a bare wire bus that runs along the edge of the board on the wiring side. However, it might be necessary to solder tinned wire extensions on the ends of some sockets.

With Fig. 3 as your guide, insert the socket for pyroelectric detector PYR1 on the centerline of the board at the edge as shown. Then position the electronic components in the punched holes in the approximate positions shown in Fig. 3. In the prototype, resistors R2, R4, R6, R7, R8, R12, R14, R18, R19, R21 and R22 were all mounted vertically to conserve board space. One lead of each was bent back 180° to form a radial-leaded component.

Pay particular attention to the positions of the polarized devices and the pin 1 positions on the IC sockets. Bend the excess lead lengths on the wire side to form mechanical connections before doing any soldering.

Note the ground bus wire that connects pin 3 of SO1 with the negative sides of resistors R2, R7, R12, R14, R15, R21 and R23, as well as the negative sides of capacitors C2, C8, C12 and C13. In addition, this bus connects pin 4 of both IC1 and IC2 and the cathode of LED1 with one side of S1 (R15).

After completing all component insertion and soldering, check the circuitry visually against the schematic to be sure that all component placement is correct. Check for cold solder joints (dull gray color without evidence of solder flow), inadvertent solder bridges, or excessive solder on joints. Make all corrections before proceeding.



CIRCUIT BOARD AND END CAP assembly with batteries. The pyroelectric detector is at the top.

Mechanical assembly

Form the access holes in the 12-inch length of tubing as shown in Fig. 4. Then cut a slot that measures approximately 5/8-inch by 1/8-inch wide in the 10-inch tube as shown. Cut a small section of pipe that will accommodate the outside diameter of the DC shutter motor. Form a hole in the side of the section to accept the twin-wire power cord, and shape the upper edge of the motor housing to form a saddle so that it will fit snugly against the pipe section.

Refer to the end cap detail in Fig. 5, and form the necessary holes in the tube cap to accommodate the two jacks J1 and J2, the light-emitting diode LED1 in a snap-in holder, and the combined potentiometer R15 and switch S1. Assemble those part in the cap and fasten them with the ring nuts provided.

End cap wiring

Cut approximate ten-inch lengths of No. 28 AWG insulated copper hookup wires required to connect the circuit board with the end cap components. The wires should be long enough to permit the end cap to be removed for replacing batteries B1 and B2 without removing the circuit board. In the prototype, nine-wire 28 AWG, multicolored flat-ribbon cable was used to make the nine connections from the circuit board to the cap.

Separate the individually color-coded insulated wires on both ends as necessary to make the appropriate connections. (If about an 8-inch length of flat cable remains bonded, it is easier to fold the cable back into the housing after final assembly.) Cut the black and red insulated wires from the 9-volt battery clips to about 10-inch lengths. Strip all wire ends, and twist all related pairs of wires before making the connections and soldering them.

Recheck the complete assembly looking for short circuits, cold solder joints, and improper location and orientation of polarized components. The circuitry can now be tested.

Electrical test

Install IC1 and IC2 in their sockets. Preset all potentiometers full counter clockwise with the pyroelectric sensor PYR1 out of its socket. Connect the 9-volt batteries B1 and B2 to their battery clips. Connect an ammeter on the 0 to 100-milliampere scale in series with the common leads of both batteries across switch S1 at test point A (TP-A) and measure the current. It should be between 15 and 20 milliamperes.

Turn the control knob of potentiometer R11 clockwise until the buzzer sounds. Expect to read a current of 60 milliamperes when LED1 is lit simultaneously. A voltage reading of 9 volts should be obtained at test point B (TP-B) and a voltage reading of 8.5 volts should be obtained at test point C (TP-C). Back off R11 slightly until the buzzer sound stops.

Insert pyroelectric detector PYR1 in its socket and slowly turn panel potentiometer R15 clockwise until the buzzer sounds. Keep PYR1 focused on a cold stationary background to prevent the detector circuit from responding erroneously to any movement. Make trial adjustments of R15 to verify the presence of a valid signal by passing your hand near the detector. Maximum sensitivity should be obtained when R15 is full clockwise and R11 is set to the critical activation point.

Connect a sensitive AC millivoltmeter set to the 500-millivolt range to jack J1, and watch for a response as an object or hand is placed in front of the detector.

Instrument housing

Refer to the lens-mount detail on Fig 5. Cut out the end of the aluminum or plastic cup that fits inside the 10-inch tube so that a shoulder about 1/16-inch wide is left as a retainer for the lens. Insert the lens in the aluminum sleeve and fasten it with one or two drops of a suitable adhesive. Then insert the lens assembly in the end of the tube as shown. Cement the assembly in place with an additional one or two drops of adhesive.

Refer to the shutter detail on Fig. 5. Assemble the chopper motor in the prepared housing. Then cut a thin piece of opaque plastic to the approximate dimensions shown, and glue it with suitable adhesive to the motor shaft as shown. After the adhesive has set, insert the shutter into the tube as shown in Fig. 5, and clamp the motor

Continued on page 87

Get 3 Books for only $9.95

Values to $154.50

plus 1 book FREE upon prepayment when you join the *Electronics Engineers' Book Club®*



020984H-XXX $110.50
The collective expertise of more than 100 contributors has been assembled to make this book the most current and comprehensive electrical reference available today. 2,208 pp., 1,421 illus.
Counts as 3



3991H $39.95
Engineers and technicians will find full coverage of standard power supply sources. Covers new frequency devices including insulated-gate bipolar transistors (IGBT) and mos-controlled thyristors (MCTs). 464 pp., 365 illus.



9255H-XXX $105.50
"Outstanding, extensive reference to current technology of electronics. Covers everything from principles to applications."
—Computer Book Review
2,528 pp., 1,800 illus.
Counts as 3



003961H $40.00
Here's your guide to basic electrical measurements, component measurements, system tests, and performance verification. Most of the methods and procedures you'll find here use available off-the-shelf test equipment.
224 pp., 180 illus.



3438H $39.95
Step-by-step instructions and alternative techniques are provided for solving problems in basic arithmetic, algebra, geometry, trigonometry, and calculus. 512 pp., 481 illus.



028735XH-XX $94.50
Put more than 1,100 specific calculation procedures for solving on-the-job engineering problems at your fingertips. Each procedure provides the exact, numbered steps you should follow for a quick, accurate solution. 1,486 pp., 1,292 illus.
Counts as 2

031716H $50.00
Cover the basics of all the important video technologies in this one comprehensive volume. You'll find valuable information on the production, recording, editing, transmission, distribution, and display of video signals. 300 pp., 120 illus.

028977H $48.00
Unleash the power and complexity of the latest generation of controller designs with the information in this guide. The authors show you the various ways a controller can be implemented into hardware such as antilock brakes, cash registers, and robotic systems. 350 pp., 125 illus.



1938H-XX $60.00
For quick-reference and on-the-job use, this sourcebook puts over 1,300 state-of-the-art designs at your fingertips. From A (alarm circuits) to Z (zero crossing detector circuits) this compendium excels in content, scope, and design.
768 pp. *Counts as 2*



032381H-XXX $119.50
Newly revised and updated, this bestselling reference provides detailed information on physical fundamentals, patterns, structures, and design techniques for practical modern antennas.
1,520 pp., 800 illus.
Counts as 3



3589H $27.95
A practical toolbox reference for anyone in the electronics field. Phagan guides you through the practical calculations needed to design and troubleshoot circuits and components.
352 pp., 270 illus.



033157XH $55.00
Use this valuable introduction to fully understand and put to use key concepts in electrical power engineering. It covers both electrical utility companies and large industrial and commercial facilities that have their own power systems. 320 pp, Illus.



3710H $32.95
Understand the basics of receiver operation, the proper use and repair components in RF circuits, and principles of radio signal propagation from low frequencies to microwave.
416 pp., 411 illus.



0456828H $49.50
Taking into account all the provisions of the National Electrical Code® that impact on electrical construction calculations, this handbook focuses on the relationship between calculations and profitability, as well as system adequacy and reliability.
320 pp., 80 illus.



049183P $29.95
Plan and implement telecommunications projects. Acquire products and services. Assess market trends for voice and data services. And define and procure a voice/data premises distribution system with this guide.
384 pp., 159 illus., *Softcover*



044847H-XX **$40.00**
Design the complex wiring systems made necessary by advanced communications equipment. McCliman's book includes discussions of all types of wiring, from conventional to fiber optic. 250 pp., 40 illus. *Counts as 2*

3258P **$19.95**
Here are easy-to-follow, step-by-step instructions for troubleshooting and repairing all major brands of the latest electronic equipment, with hundreds of block diagrams, specs, and schematics.
320 pp., 236 illus., *Softcover*



2962P **$18.95**
This complete EPROM instruction manual provides a detailed explanation of underlying theory, plus 15 different projects, including programmers, erasers, and EPROM-based circuits. 240 pp. *Softcover*

050806H-XX **$58.00**
Covering every aspect of switching power supply design, this book emphasizes circuit, transformer, and magnetics design. It provides examples of transformers and much more. 550 pp., 250 illus. *Counts as 2*



2672H **$49.50**
This book covers linear IC offerings from all the major manufacturers—complete with specifications, data sheet parameters, and price information.
624 pp., Illus.

3279P **$24.95**
Perform routine maintenance and diagnose and repair any kind of computerized device. This popular reference covers large dynamic RAMs, 32-bit processors, 80286, 80386, and Z8001-Z8002 processors.
570 pp., *Softcover*

037504H **$39.50**
Packed with simplified, circuit-by-circuit troubleshooting examples, this handbook provides the practical know-how you need to operate and troubleshoot modern RF equipment. 352 pp., 150 illus.



3837H **$27.95**
This guide focuses on the specific digital circuits used in electronic power applications. It presents state-of-the-art approaches to analysis, troubleshooting, and implementation of new solid-state devices.
272 pp., 197 illus.



4228H **$32.95**
Get all the hands-on instruction you need to translate RF theory into functioning hardware and design working RF power circuits with this guide.
304 pp., 219 illus.

4299P **$34.95**
Code generic data structures that can be used in a variety of applications. The author demonstrates the steps to follow when creating recyclable code and shows you how to enhance your generic code.
320 pp., 136 illus., 3.5" disk
Softcover

Your source for quality, affordable and timely authoritative engineering books.

As a member of the Electronics Engineers' Book Club...

. . . you'll enjoy receiving Club bulletins every 3-4 weeks containing exciting offers on the latest books in the field at savings of up to 50% off of regular publishers' prices. If you want the Main Selection do nothing and it will be shipped automatically. If you want another book, or no book at all, simply return the reply form to us by the date specified. You'll have at least 10 days to decide. And you'll be eligible for *FREE* BOOKS through the Bonus Book Program. Your only obligation is to purchase 3 more books during the next 2 years, after which you may cancel your membership at any time. ©1994 EEBC

All books are hardcover unless otherwise noted. Publishers' prices shown.
If you select a book that counts as 2 choices, write the book number in one box and XX in the next. If you select a Counts as 3 choice, write the book number in one box and XXX in the next 2 boxes.
A shipping/handling charge & sales tax will be added to all orders.

If card is missing, write to:
Electronics Engineers' Book Club, Blue Ridge Summit, PA 17294-0860

Cut along dotted line

ELECTRONICS ENGINEERS'® BOOK CLUB
Blue Ridge Summit, PA 17294-0860

YES! Rush me the following title(s), billing me just $9.95 (plus shipping/handling & sales tax). Enroll me as a member of the **Electronics Engineers' Book Club** according to the terms outlined in this ad. If not satisfied, I may return the book(s) within 10 days for a full refund and my membership will be cancelled. I agree to purchase just 3 more selections at regular Club prices during the next 2 years and may resign anytime thereafter.
☐ Bill me (FREE book not available with this payment option.)

SPECIAL OFFER! Prepay your order by check, money order, or credit card and receive a 4th book of your choice FREE.
☐ **YES!** I want the FREE BOOK indicated at right. My introductory payment of $9.95 plus $9.95 shipping/handling* and applicable sales tax is enclosed.
Code # of my FREE BOOK: SINGLE SELECTION ONLY

Code #'s of my book(s) for $9.95

If you select a book that counts as 2 choices, write the book number in one box and XX in the next.
If you select a Counts as 3 choice, write the book number in one box and XXX in the next 2 boxes.

☐ Check or money order enclosed made payable to: McGraw-Hill, Inc.
Please charge my: ☐ VISA ☐ MasterCard ☐ American Express ☐ Discover

Acct. No. _____ Exp. Date _____

Name _____ Signature _____
(required on all credit card orders)

Address/Apt.# _____

City/State/Zip _____ Phone _____

Offer valid for new members only, subject to acceptance by EEBC. U.S. orders are shipped 4th Class Book Post. Canada must remit in U.S. funds drawn on U.S. banks. *Canadian orders are shipped International Book Post—add $12.50 shipping/handling. Applicants outside the U.S. and Canada will receive special ordering instructions. A shipping/handling charge & sales tax will be added to all orders. DRE294C

We hope you PICed up all the parts you need because it's time to build the PIC programmer.



PIC MICROCONTROLLER PROGRAMMER

FRED EADY

LAST MONTH THE OPERATING THEORY of a PIC programmer was covered. This month, complete construction details are provided, along with details on a programmer for use with PIC17C42 devices.

Programmer construction

The PIC programmer can be assembled with point-to-point wiring, but assembly time and the possibility of wiring errors can be reduced dramatically by using a PC board. If you do not have the facilities to create the double-sided PIC programmer board (the foil patterns are presented here), you can obtain a professionally manufactured one from the source mentioned in the Parts List. To guarantee that the PIC16C5X programmer will operate properly once it's complete, we will simultaneously assemble and test the PIC programmer components as we proceed. Use the parts-placement diagram in Fig. 4 as a guide.

First, build and test the power supply. Install diodes D1–D4, paying attention to the orientation of the cathode bands on the diodes. Next, install bypass capacitors C2 and C10. Install the 7805 voltage regulator, IC6, with the metal tab facing the diodes. Finally, install capacitor C6, being careful to orient the positive lead as noted in Fig. 4. Temporarily attach the 18-volt AC transformer leads to the pads marked "AC" and apply power. You should measure +27-volts DC across C6 and +5 volts DC on pin 3 of the 7805. If all is well, install the remaining capacitors, XTAL1, and all of the resistors.

Apply power and check the +27- and +5-volt points again. If the voltages are correct, disconnect power and install IC5. Apply power again and check for +5.9 volts at the output (pin 2) of IC5. Then remove power, and jumper pin 24 of IC2 to ground. (The 7805's metal tab is a good ground point.) Apply power and check for +4.9 volts at pin 3 of IC5.

If all the voltages are obtained, you have successfully installed the +5-volt supply and the switchable target V_{CC} voltages. Now remove power and install transistor Q1. Jumper IC2 pin 23 to ground, apply power, and check for 0 volts at pin 14 of target socket ZIF1. Remove the jumper from IC2 pin 23 and the voltage at IC4 pin 14 should rise to +5.5-volts DC. Remove power before continuing.

Install voltage regulator IC4, apply power, and check for +13.5 volts at pin 2. If it checks out, remove power and install transistor Q2 and IC3. You can solder ICs directly to the PC board, but IC sockets are recommended. Apply power and check for +13.5 volts DC at pin 15 of IC3. Remove power and jumper IC2 pin 28 to +5 volts DC. The voltage at IC3 pin 15 should be 0 volts with the jumper installed and +13.5 volts with the jumper removed. Remove power and install the remaining IC sockets and DB-25 connector J1. Do not install any other ICs at this time.

After all of the IC sockets are soldered in place, check for +5 volts at pin 7 of the IC1 socket and pin 1 of the IC2 socket. Recheck your work, looking for solder bridges and cold solder joints. Once you are satisfied that everything is correct, install the remaining ICs in their sockets and permanently connect the transformer leads to the board.

For the final test, apply power to the completed PIC programmer board, but do not install any target PICs at this time. Check all components for overheating or any other obvious malfunctions, and correct any problems. Connect the PIC programmer to the serial port (COM1 or COM2) of an IBM-

standard computer. Run the PICPROG terminal program (it is available on the Electronics Now BBS, 516-293-2283, 1200/2400, 8N1, as a file called PICPROG.ZIP) by typing PICPROG and pressing the enter key. You should get a screen full of descriptive text explaining how to use the PICPROG program. Enter "PICPROG B 54 1" if you are using COM1. Enter "PICPROG B 54 2" for COM2. Press the enter key. You should get a banner followed by "PIC IS NOT BLANK" or "PIC IS BLANK." This verifies that the serial port and PIC17C42 on the PIC programmer are functioning. At this point you can install ZIF (zero insertion force) sockets into the target IC sockets. They allow for easy insertion and extraction of target PICs during the program-development process. Your PIC16C5X Microcontroller Programmer is now ready for use. Figure 5 shows what the completed programmer looks like.



FIG. 4—PARTS-PLACEMENT DIAGRAM for the PIC16C5X microcontroller programmer. You can make your own board or you can obtain one from the source mentioned in the parts list.

Using the programmer

To use the PICPROG terminal, simply type "PICPROG" which will display a command syntax screen with an example entry. The PICPROG terminal program is designed to help you use it automatically. For example, if you enter "PICPROG B," an incomplete blank-check command, the program will respond with an error message informing you that you left out a parameter. The correct blank-check command syntax is displayed, and an example blank-check entry is offered to help you enter the correct command. There is very little left to chance when using PICPROG. To make it even easier, many of batch files are included to simplify the PIC programming process. For instance, to blank check a PIC16C54, execute B54.BAT. Likewise, P54.BAT is used to program a PIC16C54 and R54.BAT will read the same device. You can custom tailor the batch files to match your system parameters.



FIG. 5—THE COMPLETED PIC16C5X programmer. The ZIF sockets allow for easy insertion and extraction of target PICs during the program development process.

TABLE 1—FUSE DETAILS

Fuse	S1 Position	Address	Function
FOSC0 FOSC1	1 2	FE00h FE01h	FOSC1, FOSC0: 00 : LP oscillator mode 01 : RC oscillator mode 10 : XT oscillator mode 11 : EC (external clock mode)
FWDT0 FWDT1	3 4	FE02h FE03h	FWDT1, FWDT0: 10 : WDT prescale is 256 01 : WDT prescale is 64 11 : WDT prescale is 1 00 : WDT is a normal timer
FPMM0 FPMM1	5 7	FE04h FE06h	FPMM1, FPMM0: 00 : Microcontroller mode (code protected) 10 : Mircrontroller mode 01 : Extended microcontroller mode 11 : Microcontroller mode
FGLWP	6	FE05h	FGLWP: 0 Global write protection on 1 Global write protection off

PIC17C42 programmer

For those of you who want to build the programmer entirely from scratch, Fig. 6 is a schematic for a PIC17C42 programmer module. All of the 8749H microcode and the PIC17C42



COMPONENT SIDE for the PIC16C5X programmer PC board.



SOLDER SIDE for the PIC16C5X programmer PC board.

PIC16C5X PROGRAMMER PARTS LIST

All resistors are ¼-watt, 5%, unless otherwise noted
R1, R3—237 ohms, 1%
R2—2320 ohms, 1%
R4—866 ohms, 1%
R5—3090 ohms, 1%
R6–R8—10,000 ohms
R9—430 ohms

Capacitors
C1–C5, C7, C10–C12—0.1 µF, 25 volts, monolithic
C6—330 µF, 35 volts, electrolytic
C8, C9—27 pF, 5 volts, NPO

Semiconductors
IC1—MAX233 RS-232 transceiver (MAXIM)
IC2—Pre-programmed PIC17C42 microcontroller (Microchip)
IC3—CD4053B CMOS multiplexer
IC4, IC5—LM317LZ voltage regulator
IC6—7805 5-volt regulator
D1–D4—1N4002 diode
Q1, Q2—PN2222A NPN transistor

Other components
ZIF1—18-pin zero-insertion-force socket for PIC16C54/56 target microcontroller
ZIF2—28-pin zero-insertion-force socket for PIC16C55/57 target microcontroller
XTAL1—10 MHz crystal
T1—18 VAC transformer, 500 mA
J1—PC-mount female DB-25 connector
Miscellaneous: PC board, IC sockets, 25-conductor ribbon cable, etc.
Note: The following items are available from E D Technical Publications, P.O. Box 541222, Merritt Island, FL 32954, Phone/Fax 24 hours 407-454-9905:
- **Complete PIC16C5X kit including PC board, transformer, female DB-25 connector, and all electronic parts (no ZIF sockets or cables)—$69.95**
- **PC board only—$30**
- **Programmed PIC17C42—$30**
- **Software on diskette—$10**

Please add $7.50 shipping for the full kit and $3.00 shipping for parts and software. Check, money order or COD only.

terminal program, both source and executable code, can be obtained from the Electronics Now BBS (516-293-2283) or from the E-D Technical Publications BBS (407-454-3198).

The prototype for this programmer was assembled with wire-wrap techniques. The power system and serial I/O subsystem contained on the PIC16C5X board were used, and the power, data, and control connections were jumpered, via a 40-pin header and matching socket, across to the PIC17C42 programmer module. That makes for quick and easy assembly. You can also build up all the power system and other components on one breadboard if you wish. A 7407 open-collector buffer (IC5) emulates the open-collector pins on the PIC16C5X programmer.

Be sure to provide adequate heatsinking for the LM7805 regulator (IC6) as it is supplying power for most of the non-CMOS parts. Bypass capacitors C2–C5 are a must. Although parts placement is not critical, it is recommended that you stick close to the prototype layout shown in Fig. 7.

An 8749H (IC2) controls the programming process, and an 8255 (IC3) provides the extra I/O pins that are necessary to accommodate the 16-bit data bus



FIG. 6—PIC17C42 PROGRAMMER MODULE. The PIC16C5X programmer uses a pre-programmed PIC17C42, and this module will let you program it yourself.

of the PIC17C42. Most of the control functions are provided by the on-board I/O of the 8749H. The completed PIC17C42 programmer communicates via a serial connection to the terminal program. You can use the same MAX233 serial I/O circuit that was used on the PIC16C5X programmer. Also note that T1 is the input pin on the PIC17C42 programmer.

The PIC17C42 is programmed like other PIC16C5X MCUs, with the exception that an internal ROM-programming routine built into the PIC17C42 eliminates much of the programming overhead that is usually required for such devices. Data is transferred via the 8749H data bus to the data bus of the 8255 I/O subsystem. The 8255 passes the 16-bit programming between the target PIC17C42 and the 8749H. The 8255 also reads the configuration fuse settings that are set up by DIP switch S1. Table 1 gives the fuse details. Setting a switch to read "0" at the 8255 input port pin will blow (set to "0") that particular fuse.

The PIC17C42 requires that a clock signal be fed into CLKIN (pin 19) for programming, and

SEEPIC

The author has developed a simple program and hardware combination (shown here) for the PIC16C5X Microcontroller Programmer called SEEPIC. It will execute a PIC instruction or set of PIC instructions and display the resulting PIC register file contents on your terminal or PC with a 9600 BPS serial link. To use SEEPIC insert your small test program into the skeleton SEEPIC code and program the resulting compiled code into a PIC16C54. A MAX233 allows a connection to be made to your PC's serial port. Run whatever communication software you are comfortable with, and you should get a binary display of all of the PIC16C54 registers including the W register on screen. SEEPIC runs your test program only once, so you must remove and apply power to the programmed test PIC to run the program again. SEEPIC is designed as a learning tool. Writing code and seeing a result is the best way to learn how any microcontroller works. SEEPIC provides examples of a 9600 bps serial routine and many common functions you will use when you apply the PIC in your projects.

The author has also written a PIC cross-assembler that is included with the PIC programmer PICPROG software package. You can obtain all the batch files, PICPROG, SEEPIC, and the PIC cross-assembler from the Electronics Now BBS as the file called PICPROG.ZIP.

PARTS LIST FOR SEEPIC

IC1—PIC16C54
IC2—MAX233
C1, C2—0.1 µF bypass
8-MHz ceramic oscillator, DB-25 shell connector, perforated construction board, serial cable, wire, solder, etc.



SEEPIC SCHEMATIC. This simple hardware/software combination for the PIC16C5X Microcontroller Programmer will execute a PIC instruction or set of PIC instructions, and display the resulting PIC register file contents on your terminal or PC with a 9600 BPS serial link.

PIC17C42 PROGRAMMER PARTS LIST

Resistors
R1, R4—237 ohms, 1%
R2—866 ohms, 1%
R3—3090 ohms, 1%
R5—2320 ohms, 1%
R6, R7, R9—10,000 ohms, 5%
R8—10,000 ohms × 8, 9-pin SIP
Capacitors
C1–C5, C7–C9, C13—0.1 µF, bypass
C6—1000 µF, electrolytic
C10, C11—27 pF, ceramic
C12—1 µF, Tantalum
Semiconductors
IC1—CD4053B CMOS multiplexer
IC2—8749H microcontroller
IC3—82C55 programmable peripheral interface
IC4—7407 TTL hex buffer
IC5, IC7—LM317LZ adjustable regulator
IC6—LM7805 5-volt regulator
D1–D4—1N4002 diode
Q1, Q2—PN2222A NPN transistor
Other components
XTAL1—10 MHz crystal
XTAL2—4 MHz oscillator
S1—8-position DIP switch
ZIF1—40-pin zero-insertion-force socket for PIC17C42 target microcontroller



FIG. 7—PROTOTYPE PIC17C42 PROGRAMMER. The circuit is point-to-point wired.

XTAL2, a 4 MHz oscillator, is provided for this purpose. For a detailed bit-by-bit account of how the PIC17C42 programmer works, study the fully commented source code.

Using the PIC17C42 programmer should be a snap. There is only one caution to observe: never apply or remove power to the programmer module with a target PIC17C42 socketed. It could damage the target device. With that in mind, apply power to the programmer module and start the terminal program (17C42.EXE). A "READY FOR COMMAND" should be displayed as a flashing message indicating that the terminal program has made contact with the programmer module. Load the binary image of what is to be programmed (PICPRGR.BIN if you want to build the PIC16C5X project), insert a blank target PIC17C42, and press P to program. The programming algorithm will execute and end successfully with a "VERIFY OK" message. The PIC17C42 is then ready for service.

Conclusion

We hope you have "PICed" up enough information to realize what fantastic devices PIC microcontrollers really are, and how easy they are to use. For more PIC details, get your hands on the Microchip Data Book and the Microchip Embedded Control Handbook (Microchip Technology, Inc., 2355 W. Chandler Blvd., Chandler, AZ 85224-6199, 602-963-7373).

The author is always happy to offer readers any assistance he can, so you should feel free to PIC up the phone and direct your PIC-related questions to the HELPLINE at 407-454-9905. Ω

A stepper motor, believe it or not, makes a pretty good shaft encoder!

STEPPER MOTORS AS SHAFT ENCODERS

NEIL W. HECKT

SHAFT ENCODERS ARE USUALLY OPtoelectronic devices that produce quadrature (90-degree) signals in response to the rotation of a shaft. The phase relationship of the signals depends on the direction of rotation, and the pulse rate depends on the speed of rotation.

Shaft encoders are difficult to build, because they require mechanical construction. They are also somewhat expensive, starting at about $30, and rarely seen on the surplus market. This article describes how to use stepper motors as replacements for optical shaft encoders. Stepper motors are commonly found on the surplus market. The small permanent-magnet (PM) motors used in floppy-disk head positioning can be purchased for as little as $2 each.

Stepper motors are also quadrature devices. This means quadrature-related drive signals cause the shaft to rotate a precise amount. As in a shaft encoder, the phase relationship of a stepper motor's drive pulses determines its direction of rotation, and the rate of pulses determines its speed of rotation. Just as a standard electric motor can also be used as a generator, a stepper motor can generate quadrature phased output pulses in response to mechanical rotation of its shaft.

Figure 1 is a simplified diagram of stepper motors construction. The PM stepper motor consists of a rotor and a stator. The rotor is fabricated from a cylindrical permanent magnet, or more precisely, a spool-shaped permanent magnet. Teeth, like those found on gears, are ground into the north pole of the magnet, and an identical set of teeth, offset by ½ the tooth pitch, are ground into the south pole of the magnet. This can be seen in Fig. 1. Since the rotor in Fig. 1 has 5 teeth, the tooth pitch is $^{360}/_{5}$, or 72 degrees. In actual stepper motors, there are usually a lot more than five teeth used. Figure 2 is a photo of a disassembled 200 step/revolution stepper motor that has 50 teeth in each row.

The stator consists of an iron-core electromagnet whose poles have the same spacing as the teeth on the gears less one tooth. Figure 1 shows that there are four poles. In a practical stepper motor there are several windings for each phase, and each winding has teeth ground on its surface to provide the effect of many more stator poles.

Stepper motor operation

Operation of the stepper motor (as a motor, and not a shaft encoder) is shown in Figs. 3 to 7. Currents are induced in the stator windings to produce magnetic poles, north (N) and south (S), as indicated on the stator pole pieces. The flux polarity of the rotor's magnetic poles are fixed by the permanent-magnet core, and each tooth possesses that flux density. The teeth are numbered to help the reader keep track of each tooth during rotation.

Figure 3 shows an arbitrary initial position (called state 0), in which the stator has a north pole at the top and a south pole



FIG. 1—A SIMPLIFIED DIAGRAM shows how stepper motors are built.

phase-2 is reversed, the top pole of the stator will become a south pole and the bottom pole will become north. That relationship repels the rotor flux, freeing the rotor to seek a new stable position. The nearest stable position is determined by the left and right stator poles. Because the left pole is south and the right pole is north, the nearest stable position can be reached if a rotor's north pole (N2) aligns with the stator's left south pole,



FIG. 2—THIS DISASSEMBLED 200 step/revolution stepper motor has 50 teeth in each row.



FIG. 3—THE INITIAL POSITION (state 0) results from the stator with a north pole at the top and a south pole at the bottom. They are opposite a rotor south pole (S1) at the top and north pole (N4) at the bottom.



FIG. 4—STATE 1. The rotor has moved clockwise one quarter of the tooth pitch (72/4), or 18°.



FIG. 5—STATE 2. Here the polarity of phase 1 is reversed, causing the left stator pole to become north and the right pole to become south. The motor then finds a new stable position clockwise an additional 18°, for a total of 36°.

at the bottom, and the rotor has a south pole at the top (S1) and a north pole at the bottom (N4). Because opposite magnetic poles attract, the rotor is held in this position. The left and right poles of the stator are half way between rotor teeth, so the net force is nearly neutral.

If the polarity of the current in

and a rotor's south pole (S5) aligns with the stator's right north pole. This position is one-quarter tooth pitch clockwise of the initial position as shown in Fig. 4.

In Fig. 4 (the position for state 1), the rotor has moved clockwise one quarter of the tooth pitch (72/4), or 18°. The top and bottom stator poles are now half way between rotor poles and have a neutral force. The motor has now found a new stable position.

In Fig. 5 (state 2), the polarity of phase 1 is reversed, causing the left stator pole to become north and the right pole to become south. The motor then finds a new stable position an additional 18° clockwise, and has now rotated a total of 36°. In Fig. 6 (state 3), the polarity of phase 2 is reversed, causing the top stator pole to become north and the bottom pole to become south. Again the motor finds a new stable position at an additional 18° clockwise, and has now rotated a total of 54°.

In Fig. 7 (state 4), the polarity of phase 1 is reversed, causing the left stator pole to become north and the right pole to become south. Again the motor finds a new stable position an additional 18° clockwise, and has now rotated a total of 72°. Because 72° is equal to one tooth pitch, the motor is again in state 0 but it is replaced one tooth clockwise. By repeating the sequence of phase reversals in the stator, the motor will continue to rotate clockwise.

By reversing the order of phase reversals, the motor will rotate counterclockwise. The effective currents in the stator are shown in Fig. 8 for both clockwise and counter-clockwise rotations. The current



FIG. 6—STATE 3. Here the polarity of phase 2 is reversed, causing the top stator pole to become north and the bottom pole to become south. The motor has now rotated a total of 54°.



FIG. 7—STATE 4. Here the polarity of phase 1 is reversed causing the left stator pole to become north and the right pole to become south. It has now rotated a total of 72°, which is equal to one tooth pitch so the motor is again in state 0 but one tooth clockwise.

waveforms for the stepper motor are essentially square waves as shown.

Stepper generator

When a stepper motor functions as a generator, the voltage waveforms will essentially be sinewaves as shown in Fig. 9. The sinewaves constitute a "step" signal derived from phase 2 and a phase-leading (clockwise) or phase-lagging (counter clockwise) "direction" signal derived from phase 1. This permits continuous rapid rotation of the shaft.

When a stepper motor is at rest, it has a "magnetic detent" resulting from residual magnetism in the core of the stator reacting to the flux of the rotor's permanent magnet. In single-step operation, the rotor is moved from one magnetic detent to the next. The voltage waveforms for single-step rotation are similar to those in Fig. 10.

When single stepping, the maximum output amplitude is typically 30 to 500 millivolts, and for rapid rotation it can be several volts peak-peak, although it varies with the type of motor used. As with all generators, the output voltage is a function of the strength of the magnetic flux, the rate of rotation, and the number of turns of wire on the stator. Larger motors and/or higher-voltage motors will produce greater output voltages.



FIG. 8—STATOR CURRENTS for both clockwise and counter-clockwise rotations.



FIG. 9—WHEN A STEPPER MOTOR functions as a generator, the voltage waveforms will essentially be sinewaves with continuous rapid rotation of the shaft.



FIG. 10—THE VOLTAGE WAVEFORMS for single-step rotation are similar to these.

Stepper shaft encoder

For stepper shaft-encoder operation only the timing relationships between the pulses are important. The voltages are of interest only as a means for detecting their timing relationships and protecting the detector from excessive input voltage.

To obtain a complete set of pulses describing both rate and direction, the stepper shaft must be rotated through four of its motor positions. That is typically the distance from one magnetic detent to the next. Unfortunately the number of output-pulse sets per revolution of the shaft is one quarter the specified number of positions of the motor. A 200-step per revolution motor will therefore produce only 50 encoder output pulse sets per revolution.

To use the stepper shaft encoder, the output signals must be converted to square waves to drive logic circuits. A pair of voltage comparators, with hysteresis, convert the sinewaves to square waves (see Fig. 11). If



FIG. 11—TO USE A STEPPER as a shaft encoder, the output signals must be converted to square waves with a pair of voltage comparators.



FIG. 12—COMPARATOR WAVEFORMS. The hysteresis trip points are set to less than the peak amplitude of the main cycle of the sinewave, but greater than the peak value of the residual cycle.



FIG. 13—BIPOLAR STEPPER MOTORS have a single winding for each phase. Unipolar units provide the bidirectional current flow when the winding is center-topped. Shown in *a* is a bipolar drive and in *b* is a unipolar drive.



FIG. 14—THIS STEPPER provides 50 pulses per revolution.

the hysteresis is properly set, one can obtain reliable pulses even under single-step conditions.

Figure 12 shows the voltage-comparator waveforms. The hysteresis trip points are set to less than the peak amplitude of the "main" cycle of the sinewave but greater than the peak value of the "residual" cycle. The main cycle is generated by rotating the shaft from one magnetic detent to the next. The residual cycle is obtained from the overshoot past the detent and the rocking of the shaft as it settles into the detent. The residual cycles are much lower in amplitude because the rate of rotation is much slower.

Types of stepper motors

There are basically two kinds of stepper motors: unipolar and bipolar. Bipolar motors have a single winding for each phase. Because current must flow in both directions, the bipolar motor requires a double-pole, double-throw driver such as four transistors connected in a bridge. Unipolar motors are center-tapped to provide the bidirectional current flow as shown in Fig. 13.



FIG. 15—THIS UNIT has a step angle of 3.6°.

Most of the author's experiments were performed on four-wire bipolar stepper motors. However the unipolar motors should also work if one end and the center tap or both ends are used. The 5-wire stepper motors have a common wire for power. With those motors it is necessary to use the common wire as neutral and one end of each winding for the signal. For the 6-wire stepper motors, the power is not common, and the two ends of the windings can be used to double the output voltage.



FIG. 16—THIS STEPPER WORKS WELL and provides 25 pulses per revolution. It seems to have more magnetic detent positions than output pulses.

Stepper motors are available with operating voltages from about 1.5 to 24 volts. For shaft-encoder use, the operating voltage is not important except that the output voltages will be higher for the higher-voltage motors. The most important specification is the step angle, or steps per revolution. Typical motors range from 15° (24 steps/revolution) to 0.9° (400 steps/revolution) with 1.8 degrees (200 steps/revolution) ratings quite common. As mentioned earlier, the number of output pulses is one quarter of the number of steps per revolution. The 200- and 400-step units that produce 50 or 100 pulses per revolution are those most suitable for shaft-encoder applications.

Figures 14–16 show several examples of stepper motors that were obtained from the list of suppliers contained in this arti-

TABLE 1—STEPPER MOTOR SPECIFICATIONS

Motor	Manufacturer	Part Number	Degrees Step	Rated Voltage	Type	Single-Step Output	Rapid-Spin Output
Fig. 14	Astrosyn	14PM-K203-01	1.8	-	Bipolar	0.5Vp-p	4.0Vp-p
Fig. 15	Airpax	LA82702-C	7.5	12	Unipolar	2.0Vp-p	12Vp-p
Fig. 16	Howard	1-9-4201	3.6	24	Unipolar	2.0Vp-p	6.0Vp-p

cle. Their specifications are listed in Table 1. Two are of particular interest. The one shown in Fig. 14 provides 50 pulses per revolution. The motor in Fig. 16 works well and provides 25 pulses per revolution, although it has more magnetic detent positions than output pulses. The magnetic detent is very light and might be ignored.

Designing an interface

Designing an interface to permit a stepper motor to act as a shaft encoder consists mainly of selecting a value for R3 in the circuit of Fig. 17. Two of those circuits are required for each encoder. An LM339, LM2901, or MC3302 quad voltage comparator or LM393 or LM2903 dual-voltage comparator can be used. To operate it from a single 5-volt supply biasing the comparators at one half the supply voltage is required. That can be accomplished with the voltage divider consisting of two 1K resistors (R5 and R6) and a fairly large bypass capacitor (C1) at the node; this network can be shared by both comparators. The input resistance is split in half between R1 and R2 with back-to-back diodes clipping the peak levels to protect the voltage comparators from high-voltage inputs during rapid rotation of the shaft. For lower-voltage motors, the diodes can be eliminated and R1/R2 replaced by a single 10K resistor.

The value of R3 sets the hysteresis trip points. Assuming that R3 is much greater than R1+R2, the trip points are approximately:

$V_{p\text{-}p} = (V_{CAP}R3)/(R1+R2)$

R3 should be between 100K and 1 megohm, with 1 megohm producing the highest sensitivity. A typical value is 470 kilohms.

BEcause it is difficult to evaluate the performance of a stepper shaft encoder with just an oscilloscope, the author built the test circuit of Fig. 18. It incorporates an ICM7217IJI four-digit up/down counter display-driver chip and a 4-digit common-anode LED display. The voltage comparators have 100K fixed resistors in series with 1 megohm potentiometers to set the hysteresis levels. The goal is to find a value of hysteresis that provides adequate sensitivity for single-step operation without being too sensitive and producing extra pulses. Adjustment is not critical, and steps of about 100K will lead to the correct value.

The test circuit allows a complete evaluation of the performance of the interface circuit.



FIG. 17—TWO OF THESE CIRCUITS are required for each encoder.

For the two most applicable motors, the test results were excellent. It was very easy to set the count to any desired value and very easy to increment or decrement the count by one pulse. It is important that the frame of the motor be grounded to prevent noise pickup from your body. Figure 19 shows a photo of the test fixture.

Interesting results were discovered when the author inadvertently connected two motors in parallel. The circuit continued to perform well and either motor could be used to tune it. This suggests that two motors with different numbers of steps per revolution could be connected in parallel to provide course and fine tuning. One might use a 0.9° (400 steps/rev-



FIG. 18—THIS TEST CIRCUIT incorporates an ICM7217IJI four-digit up/down counter display-driver chip and a 4-digit common-anode LED display.

EN Engineering Admart

Rates: Ads are 2¼" × 2⅛". **One** insertion **$995 each. Six** insertions **$950** each. **Twelve** insertions **$925** each. Closing date same as regular rate card. Send order with remittance to **Engineering Admart,** Electronics Now Magazine, 500-B Bi-County Blvd., Farmingdale, NY 11735. Direct telephone inquiries to Arline Fishman, area code-**1-516-293-3000. FAX 1-516-293-3115.** ***Only 100% Engineering ads are accepted for this Admart.***

Radiotelephone - Radiotelegraph
FCC Commercial License

Why Take Chances?

Discover how easy it is to pass the exams. Study with the most current materials available. Our **Homestudy** Guides, Audio, Video or PC "Q&A" pools make it so fast, easy and inexpensive. No college or experience needed. The new commercial FCC exams have been revised, covering updated Aviation, Marine, Radar, Microwave, New Rules & Regs, Digital Circuitry & more.We feature the Popular "Complete Electronic Career Guide". 1000's of satisfied customers **Guarantee** to pass or money back.

Send for **FREE DETAILS** or call
WPT Publications
7015 N.E. 61st Ave Dept. 10
Vancouver, WA 98661
1-800-800-7588

CIRCLE 105 ON FREE INFORMATION CARD

NEW

68HC11 PROGRAMMER



P11 PROGRAMMER

Connects to an IBM PC serial port and provides the fastest, easiest way to read, modify, program & verify the eeprom/eprom memory and config. register of 68HCx11xx microcontrollers. Prices from $349.00 for Programmer & host PC S/W.

TECI **Tel:(802) 525-3458**
Fax:(802) 525-3451
The Engineers Collaborative, Inc.
Route 3, Box 8C, Barton, VT 05822 USA

CIRCLE 178 ON FREE INFORMATION CARD

HIGH POWER AUDIO AMPLIFIER CONSTRUCTION



BP277—Here's background and practical design information on high power audio amplifiers capable of 300 ± 400 watts r.m.s. You'll find MOSFET and bipolar output transistors in inverting and non-inverting circuits. To order your copy **send $6.25 plus $2.50 for shipping** in the U.S. to **Electronic Technology Today Inc., P.O. Box 240, Massapequa Park, NY 11762-0240.**



FIG. 19—PROTOTYPE TEST FIXTURE. It is important that the frame of the motor be grounded to prevent noise pickup.

olution) motor to provide 100 pulses per revolution course tuning and a 3.6° (100 steps/revolution) motor to provide 25 pulses per revolution fine tuning by connecting them in parallel.

The polarity of the two phases and their timing relationship depends on the application. Because there are two phases, there are four possible ways to connect the windings, one of which will meet any requirement. Most of the stepper motors have 3/16-inch diameter shafts. These cause a minor problem when fitting a knob. A piece of ¼-inch copper or brass tubing can be used as a bushing for a better fit. Holes opposite the set screws must be made in the bushing. Insert the tubing into the knob, tighten the set screws to mark their location, and scribe the tubing to mark the depth of the knob insert. The tubing is then removed, the holes made, and the piece cut to length.

At this point it's up to you to come up with interesting applications for using stepper motors as shaft encoders. Availability of low-cost stepper motors on the surplus market and the simplicity of the interface circuits makes their use as shaft encoders very attractive to the hobbyist. Ω

STEPPER MOTOR RESOURCE LIST

All Electronics
P.O. Box 567
Van Nuys, CA. 91408
800-826-5432

American Design Components
400 Country Ave.
Secaucus, NJ 07094
800-776-3700

American Science and Surplus
601 Lindon Pl.
Evanston, IL 60202
708-475-8440

C&H Sales
P.O. Box 5356
Pasadena, CA 91117-9988
800-325-9465

Fort Apache
31902 Hayman St.
Hayward, CA 94544
510-429-1060

Herbach & Rademan
P.O. Box 122
Bristol, PA 19007-0122
800-848-8001

MECI
340 East First St.
Dayton, OH 45402-1257
800-344-1165

Marlin P. Jones & Assoc.
P.O. Box 12685
Lake Park, FL 33403-0685
407-848-8236

R&D Electronics
1224 Prospect
Cleveland, OH 44115
216-621-1121

Digi-Key
(for the ICM7217IJI)
701 Brooks Ave. S.
P.O. Box 677
Thief River Falls, MN 56701-0677
800-344-4539



68705-BASED



EXPERIMENTER'S CLOCK

Now that you know how to program 68705 microcontrollers, and have built the equipment to do so, you can put one to use in a clock circuit.

BRIAN BEARD

LAST MONTH THE DESIGN OF A PROgrammer for Motorola's HMOS 68705 family of microcontrollers was presented. This month a digital alarm clock based on one of those parts, the 68705P will be described. Motorola has published a power-line interrupt circuit and interrupt software for clocks in its M6805 Family User's Manual. Motorola also has a Freeware BBS (512-891-3733, 300/2400, 8N1) that wil permit you to download assemblers



FIG. 1—CLOCK CIRCUIT BLOCK DIAGRAM. You can build the clock with an LED (light-emitting diode) or LCD (liquid-crystal) display.



FIG. 2—POWER SUPPLY. The alarm circuitry uses an unregulated +9 volts while the rest of the clock needs a regulated +5 volts provided by 7805 regulator.



FIG. 3—68705 CIRCUITRY. With the crystal inputs tied together, the oscillator circuit can free-run, providing an internal clock cycle of approximately 1.25 microseconds.

and user libraries, at no cost, for all of its 8-bit microcontrollers. The code for this project was compiled with a free assembler from the BBS.

Hardware design

The clock contains the basic features found in most digital alarm clocks, but it can be customized to suit your needs. Figure 1 is a block diagram of the clock circuit. There are only four parts to the clock: power supply, alarm, microcontroller, and display. As the figure shows, you can display the clock output with an LED (light emitting diode) or LCD (liquid crystal) display. The prototype shown here includes both.

Figure 2 shows the power supply. The alarm circuitry needs an unregulated +9 volts while the rest of the clock is powered by a regulated +5 volts provided by 7805 regulator IC1. One side of the transformer secondary provides a 60-hertz timebase. The 60-hertz line frequency is constantly monitored and corrected by the power company, and its average frequency is maintained as close to 60 hertz as possible. By using the 60-hertz timebase, the need for a crystal timebase is eliminated. The AC voltage is clipped by resistor R1 and diodes D1–D4, filtered by C9, and capacitively coupled by C4 to the external interrupt pin of the 68705. Interrupts are triggered on every negative-going zero crossing of the AC signal.

The 68705 is shown in Fig. 3. Notice that the crystal inputs (pins 4 and 5 of IC2) are tied together. That allows the oscillator circuit to free-run, providing an internal clock cycle of approximately 1.25 microseconds. Port-A lines PA0–PA7 are output to the display, which will be discussed shortly. Port-B lines PB4 and PB5 control the AM and PM indicators, PB6 controls the alarm, and PB7 controls the colon display. Ports PB2 and PB3 are not used. The remainder of port-B and all of port-C accept inputs from the circuit control switches.

The switch connections are very simple. The port lines are pulled high (logic 1) by a resistor until a switch is closed which grounds the port line (logic 0). All of the switches are normally-open momentary pushbuttons. The TIME SET button allows you to set the time of day. Pressing it together with the HOUR SET button will increment the hours digit until one of the buttons is released. Similarly, the TIME SET and MIN SET buttons will increment the minutes digit. When you press and hold the ALARM SET button, the display will show the alarm time. While the alarm time is displayed, it can be changed with the HOUR SET and MIN SET buttons.

The ALARM STOP button and



FIG. 4—LED DISPLAY CIRCUIT. The 7212A can drive four 7-segment common-anode digits.

ALARM ENABLE switch both connect to PB1. When the alarm is enabled, the ALARM ENABLE LED will be lit and PB1 will be high. When the time of day first equals the alarm time, the 68705 checks the state of PB1. If PB1 is high, the alarm is turned on; then, as soon as PB1 goes low, the alarm is turned off.

If there were only a pushbutton in the circuit, the alarm would turn on *every* morning at the set time. Conversely if there were only a switch, you would have to remember to enable the alarm every night.

The final input (PC3) selects a 12- or 24-hour display. Grounding PC3 (closing jumper JU1) will give you the 12-hour display. The function is controlled by a jumper, because most people have a definite preference, but a switch can be used if you want to be able to switch between display modes. If you hardwire the 24-hour display, the AM/PM indicators (LED2 and LED3) will never come on, so you need not even install them.

The display is the part of the clock you'll see most often, so it should have the display style you like. That's why the clock was designed for either LCD or LED displays. In fact, the prototype clock pictured here has both! This is made possible by the use of display controller chips. A 7211A (an LCD controller) and a 7212A (an LED controller) can both accept multiplexed BCD inputs. The 68705 program simply sends out hour and minute data as multiplexed BCD. The type of display that is connected to the circuit makes no difference.

The LED display circuit is shown in Fig. 4. The 7212A (IC4) will drive four 7-segment common-anode digits. The brightness control input to IC4 (pin 5) can be tied to +5 volts for maximum brightness, or potentiometer R11 can be connected as shown in Fig. 4 for adjustable brightness. With the colon indicator (LED4 and LED5) connected to PB7, it will flash at 1 hertz. If you want the colon to stay on constantly, connect it to ground instead of PB7.

The LCD circuit is shown in Fig. 5. The 7211A (IC4) generates the required AC drive signals for a 4-digit 7-segment liquid-crystal display. The oscillator input (pin 36) can be left open, which results in a backplane frequency of approximately 125 hertz. The colon will flash at 1 hertz as long as IC5-a pin 2 is connected to PB7. If you want the colon to remain on, connect IC5-a pin 2 to ground instead of PB7. On the other hand, if you don't want the colon to appear at all, tie the LCD's colon pin directly to the backplane and omit IC5-a.

Figure 6 shows the alarm circuit of the prototype. The circuit is basically two gated oscillators and an output transistor. The first oscillator (IC3-a and -b) runs at about 1.6 hertz, gating the second oscillator (IC3-c and -d), which runs at about 720 hertz. The resulting tone bursts are shrill enough to wake almost anyone. The alarm is controlled by the state of PB6; a high turns the alarm on and a low turns it off.

Software

There isn't enough space to print the entire assembly language source code in this arti-



FIG. 5—LCD CIRCUIT. The 7211A generates the required AC drive signals for a 4-digit, 7-segment liquid-crystal display.

MAIN CLOCK PARTS

All resistors are ¼-watt, 5%, unless otherwise noted.
R1—27,000 ohms
R2–R4—470 ohms
R5—270 ohms, ½-watt
R6—100,000 ohms
R7—220,000 ohms
R8—820 ohms
R9—4700 ohms ×9, 10-pin SIP (pin 1 common)
Capacitors
C1—1000 µF, 25 volts, electrolytic
C2, C7, C9—0.01 µF
C3—47 µF, 15 volts, electrolytic
C4—0.1 µF, ceramic
C5—1 µF, 15 volts, electrolytic
C6—10 µF, 15 volts, electrolytic
C8—47 µF, 35 volts, electrolytic
Semiconductors
IC1—7805 5-volt regulator
IC2—68705P3 microcontroller
IC3—74HC132 CMOS Schmitt-trigger quad NAND gate
D1–D4—1N4148 diode
D5–D8—1N4001 diode
Q1—2N2222 NPN transistor
LED1–LED3—light-emitting diode, any color
Other components
SPKR1—8-ohm speaker
T1—6.3-volt AC, 1-amp transformer
S1–S5—Normally-open pushbutton switch
S6—SPDT switch
Miscellaneous: Heatsink for 7805 regulator, IC sockets, perforated construction board, wire, solder.

LCD DISPLAY PARTS

IC4—7211A LCD driver (ICM7211AIPL or TC7211AIPL)
IC5—4077 CMOS quad exclusive-NOR gate
DISP1—4-digit 7-segment liquid crystal display module
C10—22 pF, ceramic
40-pin socket—for the 7211A
14-pin socket—for the 4077

cle. However, it is available on the *Electronics Now BBS* (516-293-2283, 1200/2400, 8N1) as a file called 687CLK.ZIP. The source code is well-commented and highly modular, so it should be easy to understand.

The code begins with a large block of comments that explain the memory map and functioning of all the ports. Next, understandable names are assigned to the various registers and memory locations that will store variables by the use of equate definitions. These definitions make the difference between readable code and indecipherable hieroglyphics.

The subroutines come next in the program. One of the subroutines converts the time to 12-hour format, another converts binary values to BCD, and another sends the BCD to the display. Internally, all times are kept in a 24-hour format, so the alarm will go off only once a day, even if you select the 12-hour display format.

Two other subroutines are responsible for setting the time of day and alarm time. Both of these subroutines call a delay subroutine that monitors how long you hold the "set" pushbuttons depressed. For example, if you press the TIME SET and MIN SET pushbuttons, the minutes will increase by one immediately. If you keep both buttons depressed, the next increment will occur after 0.8 seconds; the interval between increments will then get smaller and small-



FIG. 6—ALARM CIRCUIT. The first oscillator (IC3-a and -b) runs at about 1.6 hertz, gating the second oscillator (IC3-c and -d) which runs at about 720 hertz.

er until it reaches a rate of five per second. This way you can rapidly change a value by holding both buttons. Note that when the TIME SET button is released, the seconds counter is cleared so that timekeeping resumes from the start of the displayed minute.

At power-up, control is transferred to the address stored in the reset vector. In this case, it is the label "RESET." This portion of code initializes all the variables and control registers. It then starts flashing the message "HELP" on the display and it sounds the alarm until the TIME SET button is depressed. If there is a power outage you won't know with most alarm clocks until you are already late for work. This clock will wake you up so you can reset the time and alarm. If you don't want to hear the alarm every time the power is interrupted, one line from the source code will delete that feature.

The main program is a continuous loop beginning at the label "LOOP." It checks the TIME SET and ALARM SET switches, flashes the colon every second, updates the display every minute, and starts the alarm when necessary. If the alarm is sounding and you don't turn it off, it will automatically shut off after 30 minutes.

Finally we come to the external interrupt service routine. Program control is transferred here, to the label "TICK," with every tick of the 60-hertz interrupt. The time-of-day counters are increased by 1/60th of a second and control returns to the routine that was interrupted.

Construction and checkout

First decide on the type of display you want for the clock. Remember, LCDs cannot be read in the dark because they do not emit any light. However, a small incandescent bulb, mounted in front of and to the side the LCD, will make it readable at night. Backlighting is also possible if you install a transmissive or transflective LCD module with a built-in light source.

Collect the required parts for the clock and display of your choice. The parts are available from many mail-order companies including ones that advertise in this magazine. Burn the program into the 68705P's internal EPROM; you can use the programmer discussed last month or buy a preprogrammed 68705P from Lucid Technologies (see the Parts List).

The prototype was built using a combination of wirewrap and point-to-point construction. Be sure to install sockets for all the ICs. After everything is assembled, check for wiring errors, shorts, opens, and loose connections. Before installing the ICs in their sockets, apply power and check for +5 and +9 volts. Also check the IC sockets to be sure that +5 volts and ground are on the correct pins. If everything is okay, remove AC power, install the ICs, and reapply power. The "HELP" message should now be flashing on the display, and the alarm should be beeping. Press and release the TIME SET button; the alarm should shut off and the display should now show 1:00 AM (0100 when displayed in the 24-hour format).

LED DISPLAY PARTS

IC4—7212A LED display driver (ICM7212AIPL or TC7212AIPL)
DISP1–DISP4—Common-anode 7-segment LED display
R10—270 ohms
R11—100,000 ohms, trimmer potentiometer
LED4, LED5—Colon-indicator LEDs
40-pin socket—for 7212A
Note: The following items are available from Lucid Technologies, 7439 Highway 70 South, Unit 297, Nashville, TN 37221:
- **EP705N programmer kit (includes PC board, programmed 2764 EPROM, MC145411 bit-rate generator, UA78S40 switching regulator, 5.25-inch 360K documentation disk, and schematics)—$48**
- **EP705N programmer kit (same kit as above, less PC board)—$28**
- **Clock kit (includes 68705P3 programmed with the clock software for 60-hertz power, documentation, source code and S19 file on a 5.25-inch 360K disk, and schematics)—$25**

Other options

The options included in the digital alarm clock design should satisfy most hobbyists. However, there are some additional things you could try.

The LED brightness control (pin 5 of the 7212A) can be driven by a digital signal. It is possible to build a light-sensing circuit that varies the duty cycle of a pulse train applied to that pin. Then, as the room becomes darker, the display will dim.

The alarm circuit shown is only one of many that are possible. You can change the time constants of the oscillators to get different effects. Actually you can use any noise-generating circuit that can be digitally controlled (PB6 = 1 for alarm on, 0 for alarm off). Try experimenting with a sound-generator chip. Ω

RADON MONITOR

Build this radon monitor to detect a possible health threat in your home and, while doing it, learn more about radioactivity.

PAUL NEHER

THIS IS THE SECOND PART OF A TWO-part article on the design, construction and use of a simple, inexpensive environmental radon gas monitor that you can build. It is called the beverage can environmental radon monitor or BERM because the ionization chamber sensor is made from a readily available aluminum beverage can. The first part of this article explained radon and described the construction of BERM's ionization chamber and amplifier circuitry.

As was explained in the first part of this article, most people are exposed to environmental radon in excess of the natural rate because of the time they spend indoors. The article explained what radon is, why it is a health hazard, and the importance of knowing the level of radon in the rooms of your house where you spend most of your time while indoors. It also included the information needed to build the ionization chamber and its amplifier circuitry, and alternative circuits for charging an internal high-voltage capacitor to 500 volts.

The second part of this article covers such subjects as calibration and the measurement of events or rates. It offers alternative methods and circuitry for performing these functions.

Counting techniques

To determine picoCuries per liter of activity, it is necessary to count the number of pulses over a period of time, say an hour, and determine the average count per minute. It will be necessary to divide this count by the effective volume of the chamber and factor in the effect of radon daughters, which also produce alpha ionizations, to come up with an estimate of the radon concentration.

Because this count is a random process, any estimate is meaningful only when accompanied with some indication of probable error. This indication of error includes the statistical uncertainty of the count as well as uncertainty in the volume of the chamber and other factors. Later in this article, formulas will be given for the conversion

of BERM's pulse counts to specific activity units.

Rate meter

A count-rate meter will meet your requirements for counting and averaging. The circuit schematic for a count-rate meter is shown in Fig. 6. The components on the left side of the schematic function as the basic pulse-rate count circuit, while those on the right side condition the output of the analog voltmeter M1.

When the amplifier comparator IC1 (IC1-b) pulls the input to ground, capacitor C5 in the rate meter discharges through emitter-base diode D2 (Q2). Then, when the comparator goes high, resistor R8 charges C5 through emitter-base diode D3 (Q3) and accumulation capacitor C6. These components form a simple "charge pump" which charges accumulation capacitor C6 at a rate determined by the pulse rate.

The current flowing out of C6 through R9 is proportional to the accumulated charge and, at equilibrium, equals the current flowing in. In other words, the pulse rate determines voltage V_R across 100-megohm resistor R9. The equation for this response is :

$V_S = r \times R9 \times C5 \times (V_S - 2V_D)/(1 + r \times R9 \times C5)$

Where r = the pulse rate in counts per second, V_S = the supply voltage, and V_D = the diode forward voltage drop (0.5 volt).

This function is approximately linear as long as the product $r \times R9 \times C5$ is small compared to unity. If, for example, the circuit is designed so that the maximum count rate develops a voltage across R9 that approaches 10 % of the supply voltage, the maximum nonlinearity error will be 2 %.

With a regulated 9-volt supply, this circuit develops about 120 millivolts (V_R) with an input rate of 20 counts per minute where (r = 20/60 counts per second).

The value of accumulation capacitor C6 doesn't enter into the previous equation. Time constant ($C6 \times R9$) must be sufficiently long with respect to the pulse interval to produce a reasonable average. The uncertainty of the count rate, as a function of this time constant, is given by:

$U_r = \sqrt{(r/2RC)}$

This circuit has an RC time constant of 1000 seconds. This means that it will take about an hour to settle to within 3% of its final value. It has a half-scale uncertainty (10 counts per minute) of ± 5 %.



FIG. 6—THIS PULSE-COUNT RATE circuit for the BERM is coupled by to the ionization chamber with a three-wide cable.

Voltmeter

The right half of the Fig. 6 schematic is an analog panel voltmeter with a very high input resistance so that it does not load the rate circuit. Figure 6 shows a 20-microampere meter, but if you want to save money, the lower cost 50-microampere meter will work as well.

Alternatively, if you do not want a permanent system, you can substitute a bench volt-ohm milliammeter (VOM) in place of resistor R11 and the microammeter, and modify the circuit accordingly to match your meter's lowest scale. With this approach, the meter need only be connected when you want a reading.

Meter zero-adjustment resistor R12 can compensate for ± 6 millivolts of differential offset voltage in dual FET Q2. With that compensation in addition to the mechanical adjustment on the meter movement, you should be able to zero the meter with accumulation capacitor C6 discharged. If this does not happen, recheck the circuitry for possible errors.

Component selection

The leakage of diodes D2 and D3 of Fig. 6 (formed with the emitters and bases of 2N2222 transistors) as well as capacitor C6 must be low if this rate meter circuit is to work properly. The emitter-to-base junctions of a 2N2222 transistor has three orders of magnitude lower reverse current than a 1N914 switching diode.

Test electrolytic capacitor C6 for leakage before using it in the circuit. Select one that has an internal leakage resistance that is at least ten times greater than resistor R9. An effective capacitor will have a self-discharge time constant greater than three hours. Most capacitors tested by the author held at least 1 volt for 24 hours.

Don't forget the memory effect of electrolytic capacitors, especially if they have been recently operated at a voltage higher voltage than a few hundred millivolts. Some electrolytic capacitors recharge themselves to a small fraction of their operating voltage after being temporarily discharged.

Another alternative

You can also use a digital voltmeter with a constant 10-megohm input resistance and the pulse-rate circuit shown in Fig. 7. The five components of the rate circuit in Fig. 7 will fit on the amplifier circuit board with careful layout.

Typically, a full-scale count

rate of 20 counts per minute will be suitable for most indoor air environments, so the values shown in Fig. 7 were selected to produce 200 millivolts into a 10-megohm resistance. Select the value of capacitor C5 to calibrate the circuit. In contrast to the previous approach, however, the DVM must remain connected at all times.

Rate meter calibration

To calibrate any of the rate meters, you will need a data point to adjust the gain or scale factor. You can build a pulse circuit based on the 555 silicon monolithic timer IC (e.g., NE555N or MC1455N) as shown in Fig. 8. It produces about 10 pulses per minute to establish the slope of the rate meter's response when input counts per minute are plotted against the rate meter output scale.

Calibrate the pulser's rate by counting oscillations for 10 minutes so it will be within 1% accurate. Connect this auxiliary pulse circuit to the rate meter and let it settle for at least an hour before adjusting gain potentiometer R11. It might be necessary to substitute an alternative value for capacitor C5, depending on which version of the rate meter you build. You should be able to calibrate the meter to within a few percent in this way.

Combine the two

The rate meter shown in Fig. 6 and the amplifier together draw a supply current of about 3 milliamperes. They will both work from a standard 9-volt transistor battery. If you want a portable radon monitor, you can put both circuits together in a common enclosure.

Reset pushbutton switch S1 across capacitor C6 will be useful if you should accidentally bump the ionization chamber against a solid object. The large number of false readings will overload the meter which will take a long time to settle unless switch S1 is pressed.

Periodically check the rate meter zero setting by resetting capacitor C6. Do not apply any input pulses to the rate meter circuit for about an hour to check capacitor C6 for memory effects.

Alternative counters

An electromechanical counter is capable of accumulating a raw count. The LM392 (IC1) cannot drive the solenoid directly, but it can trigger a 555 timer IC that provides both a sufficiently wide pulse and enough current to drive a low-voltage counter.



FIG. 7—AN ALTERNATIVE CIRCUIT for pulse-count determination if an an external voltmeter is be used in place of the meter.



FIG. 8—THIS PULSE COUNT reference circuit can be used to calibrate the pulse-count rate circuit.

Some benchtop frequency counters include a scaler setting that will allow you to make a direct connection to the ionization chamber so you can accumulate counts. Alternatively, you can build a digital counter with an LSI counter/display driver IC.

Computer interface

If you are a computer enthusiast you might want to use your PC to count the pulses, compute a running-time average, and display the results graphically. The interface to your computer probably makes use of a latched interrupt request. A separate RS flip-flop board, set by the active-low, open-collector output, can provide the latch that is reset by the interrupt handling routine. The count rate will typically be less than 10 counts per minute, so processing speed is not critical.

An advantage of the open-collector output from the ionization chamber is that it can be pulled up by the computer logic supply (5-volts, 10 kilohms) without the requirement that the noise-sensitive amplifier circuitry share a common (electrically noisy) positive supply voltage. The chamber ground should be connected to the computer ground.

The largest calibration error relates to the proper determination of the ionization chamber's effective volume. Compared with that uncertainty, most of the other contributing sources of error in the BERM are small—approximately 10%.

Gain equation

The specific activity of radon, a(Rn), as a function of system variables is given by the following equation:

$a(Rn) = r \times k/(n \times VE)$

where a(Rn) is in units of picoCuries per liter

r = the count rate in counts per minute

k = a conversion factor from disintegrations per minute to picoCuries

n = the number of alpha counts per radon atom

VE = the effective volume in liters = physical volume × efficiency.

The constants $k/(n \times VE)$ equal 1.9 for a chamber equipped with a radon progeny filter. At 5 counts per minute, the radon concentration is 9.5 pCi/l.

If the construction instructions given in part 1 of this article were followed, the result should be a BERM that will have the same calibration factor as the author's prototype. The basic accuracy of your instrument will be ± 25%, which accounts for the probable mechanical variations, the statistical uncertainty in the author's calibration, and any rate meter error.

Radon progeny error

Refer to Fig. 9. The conversion factor n, number of alpha emissions per radon atom, has a theoretical value of 3 because, for every radon disintegration, two more alpha particles are emitted from polonium 218 and polonium 214 (See Table 1) under equilibrium conditions.

As radon decays, the number of progeny atoms increases until their radioactive decay balances their rate of production. After radon is introduced into the chamber, the alpha production rate will stabilize in about two hours.

If the ionization chamber is open to the air so that radon and radon progeny can enter the chamber freely, there is a reading uncertainty caused by their unknown equilibrium state. Researchers have found wide variations in the ratio of short-lived daughter products compared to radon in indoor air.

This factor has been estimated to average 20 ± 14 %. A simple progeny filter made from a plastic or paper bag eliminates this source of error. However, even with a filter in place, radon diffuses slowly through the paper or plastic, and it might take up to eight hours for the reading to stabilize. The installation of a simple BERM filter is described later.

Rate meter error

Because rate meter gain is directly proportional to the power supply voltage, you should know that the calibration shifts with decreasing battery voltage. The voltage of a typical 9-volt battery will fall approximately 20% over its useful lifetime. This has been found to permit about three days of continuous operation.

The rate meter, with a time constant (RC) of 1000 seconds, has an uncertainty that depends on the rate r, assuming the background rate is negligible, and as stated earlier, has a ± half-scale error. If the count is accumulated by other means, the statistical uncertainty in N counts is $\sqrt{N}$.

Summary of errors

The BERM has a total probable error of ± 25% plus a calibration drift caused by the battery. However, the total probable error can be reduced to about ± 13% under the following conditions:

- A progeny filter is installed.
- A highly stable power supply is in use.
- The BERM is calibrated against a standard instrument with a ± 10% error.
- Background rate adjustments have been made.

Application

The discussion on errors assumes that the BERM is in equilibrium with the surrounding air. A number of factors affect the time required for the BERM to reach this equilibrium.

Filters

As discussed earlier, the installation of a simple radon progeny filter will limit the particles entering the ionization chamber to radon. Find a polyethylene plastic bag sealed on three sides that is large enough to hold the ionization chamber. Inflate it with air and tie it off at the neck with several turns of a wire tie. Observe the inflated bag over a period of about an hour to make sure that it has no pinhole leaks.

After you are satisfied that the bag is free of pinholes, open it and place the ionization chamber inside. Then inflate the bag again and again tie it off with several turns of the wire tie around cable this time. Attempt to hold as much air as possible inside the bag while you tie it off.

PARTS LIST

Figure 6 ratemeter circuit.
All resistors are ¼-watt, 5%.
R8—100,000 ohms, carbon composition
R9—100,000,000 ohms, carbon composition
R10, R13—2,200 ohms, carbon composition
R11—5000 to 10,000, 15-turn trimmer
R12—100 ohms, 15-turn trimmer
Capacitors
C5—470 pF silvered mica, selected (see text)
C6—10 µF, 15 volts, aluminum electrolytic, radial-leaded, value tested (see text)
Semiconductors
Q2—2N5566 dual JFET
D2, D3—diodes formed from 2N2222 transistors
Other components
M1—0 to 20µA analog moving-coil panel meter (see text)

Response time

Theoretically, if a constant concentration of radon could be introduced into the chamber, the alpha count rate would increase over a few hours before reaching a stable rate. Figure 9 is a plot of short-lived radon progeny dynamics, which affect alpha count ratio until equilibrium conditions are reached. The BERM's ionization chamber will typically stabilize in a few hours. The shortest time constant of the rate meter is 17 minutes.

Background rate

Even when BERM is taken outdoors where radon concentration is very low, it is likely that there will be some alpha activity in the chamber. It will be caused by the materials in the chamber itself as well by residual isotopes from the surrounding air which have attached themselves to the chamber walls.

Because this background activity is variable, it is advisable to check the background rate after cleaning the chamber. This is done by discharging high-voltage capacitor C1 and flushing the chamber with clean outside air. If possible, allow the chamber to remain outdoors for a day before performing the indoor measurement.

The background rate of the chamber is typically 20 to 60 counts per hour. Use the net counting rate—gross indoor rate minus outdoor rate—to calculate radon concentration, especially if the rates are similar.

Making a measurement

Although the BERM has an assumed large scale factor or

calibration error, the instrument is still sensitive enough to detect even small amounts of radon, perhaps only a few times greater than that in outdoor air. It has sufficient dynamic range to remain linear up to several hundred counts per minute. Without a filter which improves accuracy but slows down its measurement, the BERM can be used anywhere in a house to identify the highest levels of radon concentration and the conditions that cause that level.

Vibration effects

As stated in Part 1 of this article, the BERM's ionization chamber is a very sensitive vibration sensor that will also respond to loud, low-frequency noises. Be suspicious of any unusually high readings if the chamber had just been inadvertently bumped against a solid object. After you have gained experience with BERM while it is connected to an oscilloscope, you will be able to see for yourself what level of vibration causes false detections.

Natural background

You can modify the BERM so that it will be capable of measuring radon concentration in the soil. To do this the radon monitor must be capable of measuring up to 200 counts per minute. This is done by replacing resistor R9 with one having a value that is only 10 % of the specified R9 value. Then:

- Place the ionization chamber in the plastic filter bag as previously described. (In this test the filter will act as a moisture barrier. The BERM is insensitive to changes in relative humidity, but condensation can provide a leakage path between the cathode lining and ground.)
- Dig a hole about 15 inches deep in dry ground.
- Place the bag-covered ionization chamber at the bottom of this hole to collect radon gas emitted from the soil and cover it with an inverted bucket. Then backfill the soil around the bucket to act as a seal.

This test should show that radon concentration in the ground is at least 100 times greater than that found in outdoor air. Compare the outdoor readings with those measured indoors with the same rate meter. If you have been unable to calibrate your BERM against a professional instrument, the readings taken in the ground will act as a useful reference. *If the amount of radon collected indoors is as much as 10 % of the level determined from the soil test, it is probable that a radon hazard exists.*



FIG. 9—PLOT OF RADON 222 PROGENY EMISSION OVER TIME VS. number of atoms.



FIG. 10—THIS FILTERED POWER SUPPLY can replace a 9-volt transistor battery for powering the radon monitor.

Line power circuit

If you want to experiment with your BERM indoors or perform long-term testing, you might want to power it from the AC line rather than depend on disposable 9-volt batteries. An off-the-shelf AC-to-DC adaptor is not suitable for this application because it lacks the necessary filtering to eliminate noise interference. The circuit shown in Fig. 10 includes the necessary filtering. Ω

References

1. Brookins, Douglas G.: "The Indoor Radon Problem," Columbia University Press, New York, NY, 1990.
2. Lao, Kenneth: "Controlling Indoor Radon," Van Nostrand Reinhold, New York, NY, 1990.

Electronic Paperbacks at Special Prices

☐ **BP325—A CONCISE USER'S GUIDE TO WINDOWS 3.1 . . . . $7.95.** Come to grips with Windows 3.1 in the shortest and most effective way. Learn how to manipulate Windows screens and DOS by Windows graphics interface. Master its word processor, Paintbrush and data base along with Notepad, Macro Recorder, PIF Editor, and Calculator.



☐ **BP311—AN INTRODUCTION TO SCANNERS AND SCANNING . . . . $7.95.** Radio scanners have opened a realm of exciting radio listening. Understand radio wave propagation, types of transmissions, antennas, band assignments—the straight dope on what to hear and where to hear it! Comes complete with index, glossary of important terminology.



☐ **BP287—A REFERENCE GUIDE TO PRACTICAL ELECTRONICS TERMS . . . . $8.95.** More than just a dictionary of practical electronics terms, the book goes a step further in getting down to fundamentals. A reference volume that can be read casually by a reader seeking knowledge.



☐ **BP248—TEST EQUIPMENT CONSTRUCTION ..... $5.95.** Details construction of simple, inexpensive, but extremely useful test equipment. AF Gen, Test Bench Ampl, Audio Millivoltmeter, Transistor Tester and six more.

☐ **BP267—HOW TO USE OSCILLOSCOPES AND OTHER TEST EQUIPMENT ..... $6.95.** Mastering the oscilloscope is not really too difficult. This book explains all the standard controls and functions. Other equipment is also described.



☐ **BP265—MORE ADVANCED USES OF THE MULTIMETER . . . . $5.95.** Use these techniques to test and analyze the performance of a variety of components. Also see how to build add-ons to extend multi-meter capabilities.



☐ **BP256—INTRO TO LOUDSPEAKERS AND ENCLOSURE DESIGN ..... $5.95.** We explore the variety of enclosure and speaker designs in use today so the reader can understand the principles involved.

☐ **BP298—A CONCISE INTRODUCTION TO THE MACINTOSH SYSTEM AND FINDER. . . .$6.25.** If you have one of the popular Macintosh range of computers, this book is designed to help you get the most from it. Although the Mac's WIMP user interface is designed to be easy to use, much of it only becomes clear when it is explained in simple terms. All Macintosh computers are covered including the new "Classic" range.

☐ **BP299—PRACTICAL ELECTRONIC FILTERS ..... $6.95.** Presents a dozen filter-based practical projects with applications in and around the home or in the constructor's workshop. Complete construction details are included.

☐ **BP249—MORE ADVANCED TEST EQUIPMENT CONSTRUCTION . . . . $6.95.** Eleven more test equipment construction projects. They include a digital voltmeter, capacitance meter, current tracer, etc.





☐ **BP245—DIGITAL AUDIO PROJECTS ..... $5.95.** Practical circuits to build and experiment with. Includes A/D converter, input amplifier, digital delay line, compander, echo effect and more.

☐ **BP247—MORE ADVANCED MIDI PROJECTS ..... $5.95.** Circuits included are a MIDI indicator, THRU box, merge unit, code generator, pedal, programmer, channelizer, and analyzer.

☐ **BP257—INTRO TO AMATEUR RADIO . . . . $6.95.** Amateur Radio is a unique and fascinating hobby. This book gives the newcomer a comprehensive and easy to understand guide to the subject.



☐ **BP309—PREAMPLIFIER AND FILTER CIRCUITS ..... $6.95.** Provides circuits and background info for a range of preamplifiers, plus tone controls, filters, mixers and more. All are high-performance circuits that can be built at a reasonable cost.

☐ **BP303—UNDERSTANDING PC SOFTWARE ..... $6.95.** This book will help you understand the basics of various types of business software in common use. Types of software covered include word processors, spelling checkers, graphics programs, desktop publishing, databases, spreadsheets and utilities.

☐ **BP251—COMPUTER HOBBYISTS HANDBOOK . . . . $8.95.** A wrapup of everything the computer hobbyist needs to know in one easy to use volume. Provides a range of useful reference material in a single source.



☐ **PCP115—ELECTRONIC PROJECTS FOR HOME SECURITY . . . . $10.00.** 25 projects ranging from a single-door protection circuit that can be completed in an hour or two, to a sophisticated multi-channel security system. Each project is described in detail with circuit diagrams, explanations of how it works, instructions for building and testing, and how to adapt circuits to meet special requirements.

☐ **BP190—ADVANCED ELECTRONIC SECURITY PROJECTS.....$5.95.** Includes a passive infra-red detector, a fiber-optic loop alarm, computer-based alarms and an unusual form of ultrasonic intruder detector.

☐ **BP235—POWER SELECTOR GUIDE . . . . $10.00** Complete guide to semiconductor power devices. More than 1000 power handling devices are included. They are tabulated in alpha-numeric sequence, by technical specs Includes power diodes, Thyristors, Triacs, Power Transistors and FET's.

☐ **BP234—TRANSISTOR SELECTOR GUIDE.....$10.00.** Companion volume to BP235. Book covers more than 1400 JEDEC, JIS, and brand-specific devices. Also contains listing by case type, and electronic parameters. Includes Darlington transistors, high-voltage devices, high-current devices, high power devices.

☐ **BP117—PRACTICAL ELECTRONIC BUILDING BLOCKS—Book 1.....$5.75.** Oscillators, Timers, Noise Generators, Rectifiers, Comparators, Triggers and more.

☐ **BP195—INTRODUCTION TO SATELLITE TV..... $9.95. A** definitive introduction to the subject written for the professional engineer, electronics enthusiast, or others who want to know more before they buy. 8 × 10 in.

☐ **BP179—ELECTRONIC CIRCUITS FOR THE COMPUTER CONTROL OF ROBOTS ..... $7.50.** Data and circuits for interfacing the computer to the robot's motors and sensors.

☐ **BP239—GETTING THE MOST FROM YOUR MULTIMETER..... $5.95.** Covers basics of analog and digital meters. Methods of component testing includes transistors, thyristors, resistors, capacitors and other active and passive devices.

☐ **BP97—IC PROJECTS FOR BEGINNERS.....$5.50.** Power supplies, radio and audio circuits, oscillators, timers, switches, and more. If you can use a soldering iron you can build these devices.

☐ **RADIO—100 RADIO HOOKUPS.....$3.00.** Reprint of 1924 booklet presents radio circuits of the era including regenerative, neutrodyne, reflex & more.

☐ **BP42—SIMPLE LED CIRCUITS..... $5.50.** A large selection of simple applications for this simple electronic component.

☐ **BP122—AUDIO AMPLIFIER CONSTRUCTION . . . . $5.75.** Construction details for preamps and power amplifiers up through a 100-watt DC-coupled FET amplifier.

☐ **BP92—CRYSTAL SET CONSTRUCTION..... $5.50.** Everything you need to know about building crystal radio receivers.

☐ **BP255—INTERNATIONAL RADIO STATIONS GUIDE . . . . $7.95.** Provides the casual listened, amateur radio DXer and the professional radio monitor with an essential reference work designed to guide him or her around the more than ever complex radio bands.

CHECK OFF THE BOOKS YOU WANT

ELECTRONIC TECHNOLOGY TODAY INC.
P.O. Box 240, Massapequa Park, NY 11762-0240

Name _____

Address _____

City _____ State _____ Zip _____

EN294

SHIPPING CHARGES IN USA AND CANADA

$0.01 to $5.00	$1.50
$5.01 to $10.00	$2.50
$10.01 to 20.00	$3.50
$20.01 to 30.00	$4.50
$30.01 to 40.00	$5.50
$40.01 to 50.00	$6.50
$50.01 and above	$8.00

SORRY No orders accepted outside of USA & Canada

Number of books ordered ☐

Total price of merchandise . . . . $ _____
Shipping (see chart at left) . . . . $ _____
Subtotal . . . . . $ _____
Sales Tax (NY State only) . . . . . $ _____
Total Enclosed . . . . . $ _____

All payments must be in U.S. funds

Why just give a present, when someone special to you celebrates a birthday, wedding, the birth of a child, the holidays or any other special day? Instead, give a gift that's as special as the day itself — a U.S. Savings Bond. After all, **when you can give** someone a piece of the future, you show you care today — and tomorrow. Get U.S. Savings Bonds at your bank, and be sure to ask for a U.S. Savings Bond gift certificate. Then, when someone special to you celebrates a special day, give U.S. Savings Bonds. You'll give **a piece of the future.**

Take Stock in America

U.S. SAVINGS BONDS

A public service of this magazine



HARDWARE HACKER

Hacker's data exchange, the Adobe Acrobat system, a new pseudoscience magazine, voice messaging circuits, and special-effects resources.

DON LANCASTER

Let's start with an announcement that a superb video on the use of car alternators as low-cost, high-power stepper motors for such tasks as CAD/CAM is now available from *John Rees*. Included is a demo of his sign routing system and step-by-step rewinding details. The cost of the video is $19.50.

One hardware hacking topic that has generated more than its share of helpline calls lately is...

Voice messaging

At one time, analog tape recorders were the only reasonable way to record and play back voice messages. But these days, we've got compact, low-power, reliable electronic solutions—solutions that require no mechanical parts or moving media. Uses? Everything from voice E-mail systems to robotics and talking cards.

There are a lot of different options here. They trade quality and message time against costs, ease of recording, and compressibility.

Many older systems are based on *Toshiba* or OKI speech chips. Those systems basically include an A/D converter for recording, some digital storage, and D/A circuits for playback. The digital storage can be permanent (ROM) or else easily changeable (RAM). Otherwise a large EPROM can store messages that are to be changed only every now and then.

Typical low-cost hacker systems include the *Quik Voice* from *Eletech Electronics* and various offerings from *Ming Engineering*. Pricing is in the $20 to $40 range. These systems are usually a small circuit board holding a speech chip, a message EPROM, some analog circuits, and an output amplifier.

Everything from telephone- to CD-quality audio is available simply by changing the sampling rates. But memory requirements tend to get out of hand when recording messages longer than a minute or so.

Two good starting points for this approach are the *Voice Synthesis LSI* data book from *OKI* and various data books and application-notes from *Toshiba*.

But there is a new kid on the block that offers a true single-chip solution to electronic messaging. This one is called DAST, short for *direct analog storage technology*. Instead of going the A/D-D/A route, this new technique uses special circuitry that *directly* stores *analog* samples in a nonvolatile array.

The pioneer here is an outfit called ISD, which is short for *Information Storage Devices*. Its current offerings are the ISD2500 family that give up to 90-second playback at selected quality levels. As many as several hundred different messages can be stored. You could easily record a vocabulary of words and combine them as needed under external computer control.

Its analog storage capability is 480K bytes, or just under a half megabyte. But note that this is equivalent to many megabytes of pure digital storage.

ISD has also released a simpler and older ISD1000A chip for sale through *Radio Shack* (No. 276-1325 voice recorder chip). This one costs around $20 for the chip alone and holds 128,000 analog speech samples. Figure 1 shows the chip in an ultra-simple playback-only circuit, while Fig. 2 shows what's needed to record and play back messages.

While there's no reason why you can't also use this for recording tones, sound effects, or music, the lower sampling rates of the DAST system generally limit you to telephone-quality audio.

NEED HELP?

Phone or write your **Hardware Hacker** questions to:

Don Lancaster
Synergetics
Box 809-EN
Thatcher, AZ 85552

(602) 428-4073

For fast **PSRT** access, modem (800) 638-8369, then an HHH. Then XTX99005,SCRIPT.

A hacker data format

Wouldn't it be nice if there were some sort of data standard for getting *exact size* printed-circuit artwork for construction projects, as well as ready-to-use panel art and dial plates? Well, I've been doing this for years with all of my more recent *Hardware Hacker*, *Ask the Guru*, *Resource Bin*, and *Blatant Opportunist* columns by way of my *GEnie* PSRT. But that's just me. The key question is which data format could be used so that *all* authors for *all* technical publications could provide the same service?

There are several obvious goals for such a data format. The files should be totally device independent. The same file should run identically on *any* computer—a PC, Mac, IBM, C-64, Amiga, Sun, or Cray. The files should consist of ordinary printable ASCII characters that can be sent over a non-transparent 7-bit data channel. There should be absolutely *no* need for any special end-user hardware or software. Files should be printable on all popular printers.

The files should be more or less readable by humans and easy to edit. No royalties, costly software, limits, use licenses, or other restrictions should be involved. No trace

should remain of any of the proprietary code used to generate the actual text and graphic images. All the files should also lend themselves to full *book-on-demand* publishing.

And, of course, the files should all be super compact, run quite fastand be self-collating at the maximum possible mechanical feed speed of the printer with *zero* setup time. A reasonable goal is a file size o 10 kilobytes per camera-ready page, uncompressed.

After working on this problem for several years, I've concluded there are three routes to the hacker data format that seem reasonable. These are fax, *PostScript*, or Adobe's new *Acrobat* document system.

I don't like fax. I never use it. Special costly equipment is often needed. Compared with camera-ready PostScript, fax quality is putrid. The exact size is never guaranteed. And most fax files end up much longer than PostScript files and transmit much more slowly.

It turns out that fax compression is just about the worst possible way to squash photos or fancy technical illustrations. See Adobe's note No. 5115 for unbiased comparisons. And it is still fairly tricky to store, edit, and reuse fax code. And they are usually black-and-white only. Yet there are lots of sources now offering automatic fax services. For instance, Dan Poynter has some outstanding free resource information on self-publishing available by way of his auto fax. And most of the electronic trade journals now have lots of auto fax ads showing up.


play
8Ω speaker
+5vdc
nc nc nc nc nc nc nc
28 27 26 25 24 23 22 21 20 19 18 17 16 15
+5D REC CLK EOM PD CE NC OUT IN AGC MIC MIC +5A SP-
ISD1000A
A0 A1 A2 A3 A4 A5 NC NC A6 A7 AUX GND GND SP+
1 2 3 4 5 6 7 8 9 10 11 12 13 14
nc nc nc
10Ω

FIG. 1—PLAYBACK-ONLY CIRCUIT for the ISD1000A. The ISD chip has an innovative on-chip analog data-storage system.

On the other hand, PostScript can meet all hacker data goals. As I have mentioned before, I use PostScript as a totally *general purpose* computer language. I use it for everything from formal engineering design to stock-market analysis. Plus, of course, dirtying up otherwise clean sheets of paper.

More and more hackers have easy access to a PostScript laser printer. If you do not, the *GhostScript* shareware is widely available for downloading. This lets you run a fake PostScript over any popular printer, plotter, or phototypesetter. And yes, the full GhostScript source code is included so you can work from any recent host computer system.

One subtle but super important feature of PostScript: You can easily do *microsizing*. That let's you adjust precisely the final size on printed-circuit art and compensate for paper stretch or mechanical feeding errors. PostScript, of course, works beautifully with the new direct-toner printed-circuit processes offered by *DynaArt Designs* and *Techniks*. And, yes, PostScript can be converted back into older and more klutzy *Gerber* or HPGL vector formats.

Adobe Acrobat is brand new. This is intended to let Fortune-500 firms achieve "paperless offices," whatever those are. Their fancy document files include global searching, nonlinear Hypercard access, and thumbnail sketches for each page. The system is quite expensive.

Sadly, Acrobat document files can *not* be printed without special viewer software. Acrobat files generally demand the use of genuine PostScript level 2. The final files are also much larger and run much more slowly than I believe is really necessary.

Because nearly all of those more powerful PostScript commands are disallowed in the files, some simple graphic constructs will often generate unbearably long code. For instance, a circle needs hundreds of bytes.

Something vastly better is clearly needed for a hacker file-interchange standard.

The solution

Why not combine the best features of PostScript and Acrobat? Acrobat contains a useful but grievously flawed *distillery* that can take any PostScript input from any source and reduce it to essential core commands only, usually in a fairly efficient manner.

Sadly, the new distillery does all of its work in the host, rather than the printer. Any selected fonts must be available in host format. The file must be in one continuous piece, since persistent downloads and *run* support are appallingly absent.

Nonetheless, the distillery is the key to converting any code that was generated on a proprietary CAD/CAM, page-making, or illustration program into license-free and royalty-free distribution format.

Each page appears in the Acrobat document as an *object*. It is very

NEW FROM
DON LANCASTER

HARDWARE HACKING

Incredible Secret Money Machine II	18.50
Hardware Hacker Reprints II or III	24.50
Blatant Opportunist Reprints	24.50
Resource Bin Reprints	24.50
The Case Against Patents	24.50
Ask The Guru Reprints I, II or III	24.50
CMOS Cookbook	24.50
TTL Cookbook	24.50
Active Filter Cookbook	24.50
Micro Cookbook I	19.50
Lancaster Classics Library	119.50

POSTSCRIPT STUFF

PostScript Secrets (IIe/Mac/PC)	39.50
Book-on-demand resource kit	39.50
Intro to PostScript VHS Video	39.50
PostScript Beginner Stuff	39.50
PostScript Show & Tell	39.50
PostScript Cookbook (Adobe)	18.50
PostScript Ref. Manual II (Adobe)	29.50
PostScript Program Design (Adobe)	24.50
Type I Font Format (Adobe)	15.50
Acrobat Reference (Adobe)	24.50
LaserWriter Reference (Apple)	19.50
PostScript by Example (McGilton)	29.50
Pgm Display PostScript with X	29.50
PostScript Visual Approach (Smith)	22.50
Thinking in PostScript (Reid)	22.50
Undst PS Pgrmmg (Holtzgang)	29.50
The Whole Works (all PostScript)	349.50

FREE VOICE HELPLINE VISA/MC

SYNERGETICS
Box 809-RE
Thatcher, AZ 85552
(602) 428-4073

CIRCLE 219 ON FREE INFORMATION CARD



FIG. 2—A MULTI-MESSAGE COMBINATION playback and record circuit based on the ISD1000A. An electret microphone is shown.

easy to extract each page object, add some simple header code, and make it into a stand-alone PostScript file.

But I believe that raw Acrobat page output is much too long and runs far too slowly. It is also hard to read and harder yet to edit.

So, I have come up with a *triple distilling* process that dramatically improves extracted Acrobat files. The files are first split into their graphics and text portions. Then the graphic portions are shortened and simplified by permitting additional PostScript commands. The tricks used here will depend largely on how the original code was first generated. But such operators as *arcto*, *translate*, and *repeat* can play a big role here.

The text is sorted so that *each font size only is used once* and it is defined so that *each text line stands on its own*. Unneeded characters (such as leading zeros, trailing spaces, and extra precision) are also eliminated to further shorten the files. The speed and size gain here can be very impressive to the extent that an *uncompressed* triple-distilled file is often shorter than a compressed Acrobat file!

With some care, triple distilling can leave you with level 1 commands only, so that older PostScript printers can still be used. This will continue to be an important hacker feature for the next several years or so.

Figure 3 shows a fragment of Acrobat text output, while Fig. 4 shows the double-distilled results. The Acrobat code is typically 65% longer and 43% slower. In addition, it is harder to read and edit. Since many casual PostScript users end up baud-rate limiting themselves, a 65% length penalty can also become a 65% speed penalty. More details appear in SPEEDUP.PS.

The triple-distilling process can be fully reversible. The end user could always use the Acrobat distillery to get himself right back where it all started, or to import into packages that accept only limited PostScript commands. This use would normally be very rare.

Custom or exotic fonts could be

Earn Your B.S. Degree in ELECTRONICS or COMPUTERS



By Studying at Home

Grantham College of Engineering, now in our 43rd year, is highly experienced in "distance education"—teaching by correspondence—through printed materials, computer materials, fax, and phone.

No commuting to class. Study at your own pace, while continuing on your present job. Learn from easy-to-understand but complete and thorough lesson materials, with additional help from our instructors.

Our Computer B.S. Degree Program includes courses in BASIC, PASCAL and C languages — as well as Assembly Language, MS DOS, CADD, Robotics, and much more.

Our Electronics B.S. Degree Program includes courses in Solid-State Circuit Analysis and Design, Control Systems, Analog/Digital Communications, Microwave Engr, and much more.

An important part of being prepared to *move up* is holding the right college degree, and the absolutely necessary part is knowing your field. Grantham can help you both ways—to learn more and to earn your degree in the process.

Write or phone for our free catalog. Toll free, 1-800-955-2527, or see mailing address below.

•

Accredited by the Accrediting Commission of the National Home Study Council

•

GRANTHAM College of Engineering

Grantham College Road
Slidell, LA 70460

SPECIAL EFFECTS RESOURCES

Alcone Company
5-49 49th Avenue
Long Island City, NY 11101
(718) 361-8373
CIRCLE 316 ON FREE INFORMATION CARD

Burman Industries
14141 Covello Street Suite 6A
Van Nuys, CA 91405
(818) 782-9833
CIRCLE 317 ON FREE INFORMATION CARD

Cinefex
Box 20027
Riverside, CA 92516
(909) 781-1917
CIRCLE 318 ON FREE INFORMATION CARD

Cinema FX
13120-B Saticoy Street
North Hollywood, CA 91605
(818) 765-4995
CIRCLE 319 ON FREE INFORMATION CARD

Du-Bro Products
Box 815
Wauconda, IL 60084
(708) 526-2136
CIRCLE 320 ON FREE INFORMATION CARD

Electropea
24307 Magic Mtn Pkwy #272
Valencia, CA 91355
CIRCLE 321 ON FREE INFORMATION CARD

Film & Video
8455 Beverly Blvd Suite 508
Los Angeles, CA 90048
(213) 653-8053
CIRCLE 322 ON FREE INFORMATION CARD

Kryolan
132 Ninth Street
San Francisco, CA 94103
(415) 863-9684
CIRCLE 323 ON FREE INFORMATION CARD

Kuper Controls
11200 Montgomery, Suite 8
Albuquerque, NM 87111
(505) 263-5949
CIRCLE 324 ON FREE INFORMATION CARD

Makeup & Effects Lab
7110 Laurel Canyon Blvd Bldg E
North Hollywood, CA 91605
(818) 982-1483
CIRCLE 325 ON FREE INFORMATION CARD

Mannetron
74 Leonard Wood Drive
Battle Creek, MI 49015
(800) 357-2777
CIRCLE 326 ON FREE INFORMATION CARD

National Hair Technologies
300 Canal Street
Lawrence, MA 01840
(508) 686-2964
CIRCLE 327 ON FREE INFORMATION CARD

Polytek Development
Box 384
Lebanon, NJ 08833
(908) 534-5990
CIRCLE 328 ON FREE INFORMATION CARD

Quantel, Inc.
85 Old Kings Hwy North
Darien, CT 06820
(203) 656-3100
CIRCLE 329 ON FREE INFORMATION CARD

Smooth-On
1000 Valley Road
Gillette, NJ 07933
(908) 647-5800
CIRCLE 330 ON FREE INFORMATION CARD

Special Effects Supply Co
543 W. 100 North, Suite 3
Bountiful, UT 84010
(801) 298-9762
CIRCLE 331 ON FREE INFORMATION CARD

Mat Sweeney
14201 Bessemer Street
Van Nuys, CA 94101
(818) 902-9354
CIRCLE 332 ON FREE INFORMATION CARD

Sword & Stone
723 N Victory Blvd
Burbank, CA 91502
(818) 562-6548
CIRCLE 333 ON FREE INFORMATION CARD

handled one of five ways: (1) Ignore them and default to *Courier*. (2) Ask your end user to get all of his own fonts. (3) If only a few characters are involved, you can use a *font eliminator* that substitutes the actual font paths (this is great for logos—see FONTELIM.PS). (4) Use *multiple master* fonts for a lookalike approximation. Or, (5) You can internally tow along a copy of the needed font. Yes, much of the triple-distilling process can be fully automated.

If you do not have any access to Acrobat, there's an older DISTILL.PS file available for downloading. This older program has lots of bugs that eliminate clipping, scaling, and subscripting. But it can be run in any PostScript printer or emulator. It also supports persistent downloads, allows run commands, and has no host font restrictions.

I strongly believe that triple-distilled PostScript is the ultimate solution for a compact and low-cost hacker file interchange. I've got scads more on this on *GEnie* PSRT, including lots of source code and examples.

Naturally, I'd be most happy to help you create your own distribution files in hacker data format. You can call or write for help on this.

Two contests

As the first of two contests this month, just tell me your thoughts for a new hacker data-format standard. There will be the usual *Incredible Secret Money Machine II* prize going to the best dozen or so entries, with an all expense paid (FOB Thatcher, AZ) *tinaja quest* for two going to the very best of all. As usual, send your written entries directly to me here at *Synergetics* and not to **Electronics Now** editorial.

Special effects

How would you like to build your own T-Rex? or shoot a custom version of *Godzilla versus the Night Nurses* as a home video? What you'll require here, of course, are *special effects*. As you might guess, there is a low-profile and little-known special-effects industry that can supply all of your needed bits and pieces, either off-the-shelf or custom.

The special-effects supply sources can be a treasure trove for hardware hacking. Included are materials for plastic, rubber, and resin molding. There's special hardware, unusual materials, "claymation" supplies, fur and hair, armatures, control cables, remote controls, unusual lighting, fog and smoke machines, and lots more.

As a sidebar for this month, I thought we'd gather together a few of the better special-effects resources. The center of the industry appears to be a great quarterly magazine called *Cinefex*. A recent issue showed the insider secret plans to all the Jurassic dinosaurs, as well as the Andean plane crash. A second useful magazine on this subject is *Film & Video*.

Two of the more intriguing entries on our list are the *Sword & Stone*

```
/F8 1 Tf
9.75 0 0 9.75 60 427.5 Tm
0.029 Tc
0.032 Tw
(The tone frequencies are)Tj
/F9 1 Tf
10.9 0 Td
(subaural)Tj
/F8 1 Tf
3.7 0 Td
( in)Tj
-14.7 Te
0.021 Tc
-0.013 Tw
(that most phone or mobile comm gear)Tj
0 Te
0.043 Tc
0.115 Tw
(sharply attenuates audio below)Tj
9 0 0 9 200.4 406.5 Tm
0.046 Tc
0.124 Tw
(300)Tj
9.75 0 0 9.75 215.2 406.5 Tm
-15.9 Te
0.026 Tc
0.016 Tw
(Hertz or so.)Tj
1.025 Te
0.030 Tc
0.038 Tw
(The)Tj
9 0 0 9 89.1 385.5 Tm
0.032 Tc
0.041 Tw
(MX365A)Tj
9.75 0 0 9.75 125.4 385.5 Tm
0.030 Tc
0.038 Tw
( is a typical chip that)Tj
-6.7 Te
0.032 Tc
0.053 Tw
(can be be used either as the encoder)Tj
0 Te
0.032 Tc
0.053 Tw
(of Figure 2 or the decoder of Figure)Tj
0 Te
0.035 Tc
0.068 Tw
(3. This circuit offers your choice of)Tj
0 Te
0.048 Tc
0.148 Tw
(hardwire programmable tones or a)Tj
0 Te
0.038 Tc
0.084 Tw
(serial computer control. I've shown)Tj
```

FIG. 3—TYPICAL ADOBE ACROBAT OUTPUT used to distribute high-quality text and graphic documents. A special reader is required before the file can be printed.

and *National Hair Technologies*. The first for medieval armor, and the second for fake fur and strange wigs.

There are a lot more where those came from, so be sure to let me know your favorites or anyone I missed. In fact, let's make a second contest out of it.

New tech lit

Untapped Technology in Review is a new labor-of-love pseudoscience journal. Uh, this one seems midway between the *Skeptical Inquirer* and the *Borderlands Quarterly*. Included are commented critical reviews of some popular free-energy and antigravity schemes, the current contents for the other pseudoscience magazines, and off-the-wall patent listings.

A brand new book on buying and using older *Tektronix* oscilloscopes is titled *Oscilloscopes: Selecting and Restoring a Classic*. This one costs $19.95 from *Stan Griffith*.

Olympus has just introduced its *Videoimagescope* system. This is a full-color video camera, a *quarter inch* in diameter, at the end of a 70-foot (!) strobe-illuminated and fully steerable snake-like probe. While this dude looks outrageously expensive, it just might make a really dandy cave-survey and exploration tool, especially if it could be made self-cleaning and waterproof to a depth of twenty feet.

The horse's mouth source information on SCSII disk communication is known as ANSI X3.131-1986. It is available for $50 directly from the *American National Standards Institute*.

Sound Practices is a hands-on magazine that concentrates on vacuum tube audio circuits with only high-voltage linear triodes. The preferred tube these days seems to be the 211. To me, that mythical "tube sound" is simply so much hum, noise, and distortion added to an otherwise clean audio channel. You

```
/Times-Roman 9.75 ss
.31 .29(The tone frequencies are)60 427.5 hH
( in)203.9 427.5 H
-.13 .21(that most phone or mobile comm gear)60 417 h
1.12 .42(sharply attenuates audio below)60 406.5 h
.16 .26(Hertz or so.)60 396 h
.38 .3(The)70 385.5 hH
( is a typical chip that)125.4 385.5 H
.52 .32(can be be used either as the encoder)60 375 hH
(of Figure 2 or the decoder of Figure)60 364.5 H
.67 .35(3. This circuit offers your choice of)60 354 h
1.45 .47(hardwire programmable tones or a)60 343.5 h
.82 .37(serial computer control. I've shown)60 333 h
/Times-Italic 9.75 ss
.31 .29(subaural)166.9 427.5 h
/Times-Roman 9 ss
1.12 .42(300)200.5 406.5 h
.38 .3(MX365A)89.2 385.5 h
```

FIG. 4—TRIPLE DISTILLING can make the Acrobat output faster, shorter, and far more hacker friendly. No expensive software or special printer is required.

43,216
ELECTRONIC COMPONENTS
Whether you order 1 part or all 43,216...MOUSER stocks and...*ships same day!!*
CALL...
(800) 992-9943
for your FREE CATALOG

2401 Hwy. 287 N.
Mansfield, TX 76063
MOUSER®
ELECTRONICS
Sales & Stocking Locations Nationwide
CIRCLE 117 ON FREE INFORMATION CARD

Learn VCR repair at home!
MAKE *GOOD* MONEY IN YOUR OWN FULL- OR PART-TIME JOB

Professional-level home study course. You will master easy-to-learn, high-profit repairs *without* investing in high-tech instruments or a costly workshop. Want more independence and higher income? Send or call today!
Free career literature:
800-223-4542
Name _____ Age ____
Address _____ Phone (___) _____
City _____ State ____ Zip _____
The School of VCR Repair
6065 Roswell Road
Dept. VB342, Atlanta, Georgia 30328
CIRCLE 176 ON FREE INFORMATION CARD

Whaddya Say To A Guy Who's Had The Same Job For 50 Years, Has Never Called In Sick Or Showed Up Late, Never Taken A Vacation Or A Holiday, Never Asked For A Raise Or Griped About His Bonus And, Believe It Or Not, Has No Plans For Retirement?

Thanks.

Remember - only you can prevent forest fires.

Ad Council A Public Service of the USDA Forest Service and Your State Forester.

NAMES AND NUMBERS

Adobe Acrobat System
1585 Charleston Road
Mountain View, CA 94039
(800) 833-6687
CIRCLE 334 ON FREE INFORMATION CARD

Am. Natl. Standards Institute
11 West 42nd Street, 13th Floor
New York, NY 10036
(212) 642-4900
CIRCLE 335 ON FREE INFORMATION CARD

Borderlands
PO Box 429
Garberville, CA 95542
(707) 986-7211
CIRCLE 336 ON FREE INFORMATION CARD

DynaArt Designs
3535 Stillmeadow Lane
Lancaster, CA 93536
(805) 943-4746
CIRCLE 337 ON FREE INFORMATION CARD

Eletech Electronics
16019 Kaplan Avenue
Industry, CA 91744
(818) 333-6394
CIRCLE 338 ON FREE INFORMATION CARD

GEnie
401 North Washington Street
Rockville, MD 20850
(800) 638-9636
CIRCLE 339 ON FREE INFORMATION CARD

Gerber Scientific
83 Gerber Road
S Windsor, CT 06074
(203) 644-1551
CIRCLE 340 ON FREE INFORMATION CARD

Stan Griffiths
18955 SW Blanton
Aloha, OR 97007
(503) 649-0837
CIRCLE 341 ON FREE INFORMATION CARD

Information Storage Devices
2841 Junction Avenue, Ste 204
San Jose, CA 95134
(408) 428-1400
CIRCLE 342 ON FREE INFORMATION CARD

Ming Engineering
17921 Rowland Street
City of Industry, CA 91748
(818) 912-9469
CIRCLE 343 ON FREE INFORMATION CARD

OKI
785 North Mary Avenue
Sunnyvale, CA 94086
(800) 832-6654
CIRCLE 344 ON FREE INFORMATION CARD

Olympus Industrial
4 Nevada Drive
Lake Success, NY 11042
(800) 446-5260
CIRCLE 345 ON FREE INFORMATION CARD

Dan Poynter
PO Box 4232
Santa Barbara, CA 93140
(800) PARAPUB
CIRCLE 346 ON FREE INFORMATION CARD

John Rees
Route 1 Box 1551
Sautee, GA 30571
(706) 865-5495
CIRCLE 347 ON FREE INFORMATION CARD

Skeptical Inquirer
PO Box 703
Buffalo, NY 14226
(716) 636-1425
CIRCLE 348 ON FREE INFORMATION CARD

Sound Practices
Box 180562
Austin, TX 78718
(512) 339-6229
CIRCLE 349 ON FREE INFORMATION CARD

Synergetics
PO Box 809
Thatcher, AZ 85552
(602) 428-4073
CIRCLE 350 ON FREE INFORMATION CARD

Techniks
45 J Ringo Road
Ringoes, NJ 08551
(908) 788-8249
CIRCLE 351 ON FREE INFORMATION CARD

Toshiba
1220 Midas Way
Sunnyvale, CA 94066
(800) 321-1718
CIRCLE 352 ON FREE INFORMATION CARD

Untapped Technology Review
PO Box 5185
Mesa, AZ 85211
CIRCLE 353 ON FREE INFORMATION CARD

can easily remove any amount of hum, noise, and distortion with a digital signal-processing chip and a decent DSP algorithm.

For more information on PostScript, use Adobe's *Red* and *Blue* Books, and my *PostScript Secrets* book/disk combo. The *Whole Works* package offers one each of everything needed to learn PostScript written by all the major authors at a substantial savings. See my nearby *Synergetics* ad for more information. Lots of ready-to-use PostScript files also appear on *GEnie* PSRT. Ω

Enter A World Of Excitement with a Subscription to

Popular Electronics®

Get the latest electronic technology and information monthly!

Now you can subscribe to the magazine that plugs you into the exciting world of electronics. With every issue of Popular Electronics you'll find a wide variety of electronics projects you can build and enjoy.

Popular Electronics brings you informative new product and literature listings, feature articles on test equipment and tools—all designed to keep you tuned in to the latest developments in electronics. So if you love to build fascinating electronics, just fill out the subscription form below to subscribe to Popular Electronics...It's a power-house of fun for the electronics enthusiast.

EXCITING MONTHLY FEATURES LIKE:

- ❑ **CONSTRUCTION**—Building projects from crystal sets to electronic roulette
- ❑ **FEATURES**—Educational training on digital electronics, Ohm's Law, Antennas, Communications, Antique Radio, Simplified Theory
- ❑ **HANDS-ON-REPORTS**—User test comments on new and unusual consumer products
- ❑ **SPECIAL COLUMNS**—Think Tank, Circuit Circus, Computer Bits, DX Listening, Antique Radio, Amateur, Scanner Scene

PLUS: ALL OUR GREAT DEPARTMENTS!

You'll get 12 exciting and informative issues of Popular Electronics for only $18.95. That's a savings of $23.05 off the regular single copy price. Subscribe to Popular Electronics today! Just fill out the subscription order form below.

48784
THE FIRST SMART VEHICLES ARE HERE
JANUARY 1994
Popular Electronics
BUILD A DIGITAL BAROMETER
Be your own weatherman with this easy-to-build forecasting aid
BUILD AN ANEMOMETER
Add this simple-but-accurate wind-speed measuring device to your weather-forecasting arsenal
BUILD A RELATIVE-HUMIDITY GAUGE
Check the humidity at a glance with this digital instrument
COLLISION AND OBSTACLE WARNING
THE ROBIX ROBOTICS CONSTRUCTION SET
A great learning tool that's lots of fun to build and use
GIZMO
$3.50 U.S.
$3.95 CANADA

Save 55% Off The Regular NEWSSTAND Rate

FOR FASTER SERVICE CALL TODAY

1-800-827-0383

(7:30AM-8:30PM)
EASTERN STANDARD TIME

AREB4

Popular Electronics® SUBSCRIPTION ORDER FORM

P.O. Box 338, Mt. Morris IL. 61054

YES! I want to subscribe to Popular Electronics for 1 Full year (12 Issues) for only $18.95. That's a savings of $23.05 off the newstand price.
(Basic Subscription Rate—1 yr/$21.95)

❑ Payment Enclosed ❑ Bill me later

Please charge my: ❑ Visa ❑ Mastercard

Acct. # _____

Signature Exp. Date

PLEASE PRINT BELOW:

NAME _____

ADDRESS _____

CITY STATE ZIP

Allow 6 to 8 weeks for delivery of first issue. U.S. Funds only.
In Canada add $6.68 Postage (Includes G.S.T.) All Other Foreign add $7.50 Postage.

AUDIO UPDATE

Audiophile Silliness: Absolute Sounds Off

LARRY KLEIN

The editor of *The Absolute Sound*, who signs himself "HP," has finally responded (in his Summer 1993 issue) to my repeated cage rattlings. In a fit of dudgeon, he quotes my comment that his publication includes "a witch's brew of pseudo-science and unabashed subjectivism" and that its reviews "are essentially unreliable, influenced by price, fads, technical ignorance, and unfettered egos." (You know, if I had it to write all over again, I couldn't have said it better.)

Since I've been crusading for years against the silliness and bad science that appears in most audiophile magazines, one might question why HP suddenly chose to respond—however inadequately—to my ongoing criticisms. The answer, I suspect, is that HP's ire was triggered by my praise and plug in the January 1993 issue of **Electronics Now** of his hated competitor, *The Audio Critic*.

HP's editorial was surprisingly weak, if only because of its several factual errors and the childish "nyaah, nyaah, nyaah" quality of his counterattack. It seems to me that if I go to the trouble of phrasing a literate assault, the least that HP could do is reply in kind.

Let's take his comments in order: For some reason, HP believes that I've gone from my "perch" as Technical Editor (actually, I was Technical Director) at *Stereo Review* to *Popular Photography*, where he thinks my column criticizing his publication appeared. (I haven't written for *Popular Photography* for at least 20 years.) He then attempts to invalidate my thinking, or hearing, or character—or all of the above—with a misquote that he's attributed to me before.

I did not write in *Stereo Review* that I did "not have to listen to music to know what it sounds like." During a 1977 six-page interview in *The Boston Phoenix* I said that "I'm not really sure how the process works, but I think I have an image in my head of what live sound is. So I really don't need an A/B comparison against live sound usually."

Obviously, HP and other audiophiles must also have an image (memory) of live music stored in their heads; otherwise there would be no way to audition components critically, given the absence of a concert-hall performance available as an immediate live reference for comparison purposes.

TAS test reports

HP supposes that I've not read *Stereophile* and *The Absolute Sound* in quite some time because "Both magazines are dramatically better in technical accuracy and solid judgments than they once were." Really? In HP's current issue there's a test report on the T4, a $7450 (!) power-line isolator that purports to improve audio performance by "isolating components from the power grid and from each other." In case you're wondering, all those thousands of dollars don't buy an extra-high current capacity; the T4 can handle a maximum of 2 amperes at each of its four AC sockets.

Now, because the report is appearing in *The Absolute Sound*, it would be silly to expect them to do any kind of reality-based testing of the T4. For example, they apparently never thought of something as simple as using a digital storage scope to look at and measure the device's ability to suppress injected power-line noise signals of various types and frequencies. Instead, all the reviewers did was listen to their audio systems with and without the isolator in series with the AC line.

One reviewer found that, at first the T4 seemed to clear haze from the highs, multiply the layers of stage depth, open up more space between the instruments, and maybe clarify the bass notes. But after listening for a few days, he became aware of an "unmusical glassiness in the upper midrange" and a diffusion of image focus. All that im-



THE SUMMER 1993 ISSUE of The Absolute Sound starts out with an attempt to bash Larry Klein's approach to audio issues.

provement, mind you, was from using a power-line isolator!

Elsewhere in the same issue, reviewers extol the virtues of 6-inch-long "cable jackets" at $70 each, which they find work sonic wonders when wrapped around line cords and system cables. One reviewer was so impressed that he said he added seventeen of them to his system at a list price (which I doubt he paid) of $1190.

Then we have the RFA-78 room-tuning devices. They are soft, fuzzy, adhesive-backed discs about the size of a quarter. They cost $595 for a box of 16; two boxes are recommended for a typical installation. HP's reviewers heard "enormous" improvements in their listening room acoustics when the discs were cemented on their walls. Needless to say, no before and after acoustic room measurements were made, nor were the operating principles of the devices explained in any way.

In that connection, I find it fascinating that not one of HP's equipment reviewers was moved to dissect one of the little fuzzy $37 discs in an attempt to understand how it works. Perhaps they thought that violating its integrity would break the magic spell. We must assume that something metaphysical is involved, because the discs appear to operate somewhere in an audio tweak Twilight Zone, outside the realm of conventional acoustic physics.

I'm truly flabbergasted to find that HP regards that sort of audiophile blather as demonstrating a dramatic improvement in technical accuracy and judgments. My God, what kind of evaluations were they making five or ten years ago?

One final note: HP closes his editorial comment with the suggestion that the sort of "irresponsibility" that prevents me from recognizing the technical improvements in his magazine has led to my shameful purported position at *Popular Photography* instead of an audio magazine. (Oh, the embarrassment of it all!) He goes on to imply that my plug for *The Audio Critic* was attempt to get hired by them. How silly can one get? My answer, in regard to HP, is: Very!

AES

Last October I attended the 95th Audio Engineering Society Convention held in the Jacob Javits Center on Manhattan's far-west side. There was a plethora of programs, papers, and exhibits but, unlike some previous conventions, I found that there was very little of home-audio interest.

A couple of typical paper titles will illustrate my problem: "A Perceptual Gain-Control Technique for Bioacoustic Transient Detection" and another one called "Idle Channel Tones and Dithering in Delta-Sigma Modulators."

There were special sessions on psychoacoustics and subjective assessment, auralization (which I understand refers to the accurate simulation of acoustic room environments), digital signal processing, multichannel and HDTV sound, and so forth.

In any case, I found most of the papers and sessions somewhat obscure and not particularly relevant to my concerns. Next month I'll discuss a few of those papers that I did find interesting. Ω

SALE!
CABLE TV
DESCRAMBLERS
WE'LL BEAT ANY PRICE!
CALL TOLL-FREE
1-800-284-8432
• JERROLD • TOCOM • ZENITH •
• OAK • PIONEER • HAMLIN •
• SCIENTIFIC ATLANTA •
24 HOUR SHIPMENTS!
QUANTITY DISCOUNTS!
MONEY BACK GUARANTEE!
FREE CATALOG & INFORMATION
MEMBER NCTA
MasterCard AMERICAN EXPRESS VISA
Mastercard • American Express • Visa • C.O.D.
HAVE MAKE AND MODEL NUMBER OF EQUIPMENT USED IN YOUR AREA
1-800-284-8432
FOR ORDERS ONLY
For technical & customer service: 305-749-3122
ALL SHIPPING & HANDLING FEES AT CUSTOMER'S EXPENSE
Anyone implying theft of service will be denied assistance.
CABLE WAREHOUSE
10117 WEST OAKLAND PARK BLVD., SUITE 315, SUNRISE, FL 33351
NO FLORIDA SALES
CIRCLE 185 ON FREE INFORMATION CARD

NEXT MONTH IN
Electronics NOW®

One way to become a smart test-equipment buyer is to build peripheral test equipment and learn about the design tradeoffs often required to achieve design goals. This issue features a pro-quality function generator that you can build. It sports a frequency coverage from 4 MHz to 2100 MHz, and it has the ability to serve as a tracking generator.

And there's much more!

☆ Build a Power Line Modem and transmit X10 control signals over power lines!

☆ Update on Audio Power Amplifier Principles in our Circuit Cookbook!

The March 1994 Issue is on Sale February 3, 1994 Watch for it!

Pick Up *Electronics Now* at your favorite Newsstand, Convenience Store, Bookstore or Supermarket

Choose from 44 Career Opportunities!
Get Your Specialized Associate Degree or Career Diploma at Home in Spare Time

Now without attending college classes and with no previous experience, you can train for a money-making career...even get a Degree. Send for free facts and color brochure on employment opportunities in the field that interests you most. See how easy it is to train at home for a great career or advancement in your present job.

CALL TOLL FREE 1-800-992-8765 Ext. 2584
CALL ANYTIME—24 hours a day, 7 days a week.
OR MAIL COUPON TODAY! 281XD

ICS SINCE 1890 International Correspondence Schools
Dept. ADES14S, 925 Oak Street, Scranton, PA 18515
Please send me free facts, color brochure and full information on how I can study at home for the career I have chosen. No obligation. CHECK ONE BOX ONLY!

ASSOCIATE IN SPECIALIZED BUSINESS DEGREE PROGRAMS
☐ Business Management
☐ Accounting
☐ Bus. Mgmt.—Finance Option
☐ Bus. Mgmt.—Marketing Option
☐ Applied Computer Science

ASSOCIATE IN SPECIALIZED TECHNOLOGY DEGREE PROGRAMS
☐ Civil Engineering Technology
☐ Mechanical Engineering Technology
☐ Electrical Engineering Technology
☐ Electronics Technology

CAREER DIPLOMA PROGRAMS
☐ High School
☐ Auto Mechanics
☐ Surveying and Mapping
☐ Drafting
☐ Air Conditioning & Refrigeration
☐ Wildlife/Forestry Conservation
☐ Police Sciences
☐ Diesel Mechanics
☐ Electrician
☐ Small Business Management
☐ Gun Repair
☐ Electronics
☐ Hotel/Restaurant Management
☐ Child Day Care
☐ Legal Assistant
☐ Interior Decorating
☐ Secretary
☐ Bookkeeping
☐ Art
☐ Motorcycle Repair
☐ Catering/Gourmet Cooking
☐ Computer Programming
☐ Personal Computer Specialist
☐ PC Repair
☐ Desktop Publishing & Design
☐ Fitness & Nutrition
☐ TV/VCR Repair
☐ Animal Care Specialist
☐ Photography
☐ Journalism/Short Story Writing
☐ Florist
☐ Teacher Aide
☐ Home Inspector
☐ Medical Transcriptionist
☐ Real Estate Appraiser

Name_____ Age_____
Address_____ Apt. #_____
City/State_____ Zip_____
Phone ( )_____
CIRCLE 177 ON FREE INFORMATION CARD

DRAWING BOARD

Our automotive power supply comes to life.

ROBERT GROSSBLATT

Adding homemade electronics to a modern car can be a complex business. Open the hood of your car and you might get the impression that there's more electrical wiring there than hoses, pipes, and other more traditional kinds of automotive hardware. Although it's hard to believe, once upon a time the only wire under the hood that was less than 14 gauge was for the lights, the charging system, and a handful of relays.

Eventually manufacturers added electronics that, in theory, would keep an eye on various aspects of engine operation. Unfortunately, those electronics don't tell the driver how well the car is running.

My favorite is the "oil" idiot light. While your owner's manual wants you to believe that it lights when the oil pressure becomes too low, the truth is really quite different. The oil-pressure light is more likely to let you know that the reason your car has stopped running (at 3:00 AM on an unmarked road) is that it ran out of oil, the engine has seized, and it's going to cost you a year's salary to get it repaired.

The first step in adding meaningful electronic monitoring to your car is to design a power supply, and the most important aspect of that is to get rid of the steep voltage spikes and gullies that are caused primarily by the high-voltage side of the ignition system. In a typical car you can expect to see voltage transients that are well over 20,000 volts! The electrical load we'll put on the supply is very small—certainly a lot less than a half ampere at either output voltage—so there's no need to get overly sophisticated in the choice of voltage regulators.

Considering the state of the hobbyist market, the shrinking number of suppliers who will sell in single quantities, and the needs of the circuits we'll be working on, the best choice for a voltage regulator is any member of the 78XX and 79XX family. These parts are easy to get, can supply the current we'll need, and are extremely reliable.

The simplest power supply you can build is the standard 78XX design shown in Fig. 1. I've left the regulator unspecified because the circuit layout is exactly the same for any member of this family and, since several of these regulators are required, the complete power supply circuit will be cloned from this layout—one for each regulated voltage. This layout has appeared a number of times here in the past, so you should be familiar with it.

About the only component you might find mysterious in Fig. 1 is the diode straddling the input and output of the regulator. The diode is sometimes referred to as the "quench" diode. It comes into play whenever the input to the regulator sees either a short circuit or a voltage drop that causes the input voltage to fall below the regulated output voltage. The second of these situations is a real possibility when you consider what can happen to the battery voltage when you're starting your car on a cold winter morning.

While all 78XX regulators are protected internally against output shorts, they have virtually no protection against input shorts. If there's an output short, the regulator will immediately attempt to supply the required current, although the shock will be somewhat smoothed because the 100-microfarad capacitor at the output will discharge and feed its own stored energy into the short circuit. Ultimately the current drawn from the regulator will cause it to overheat, the device will exceed its thermal overload point, and the regulator will turn itself off.

In the case of an input short, however, the situation is much more dangerous. Whenever there's either an input short or a severe drop in the input voltage, there will be a higher voltage at the output of the regulator than at the input. This means that the energy stored in the 100-microfarad capacitor is going to be discharged into the internal output circuitry of the regulator. Depending on the circuit parameters, this will probably reverse-bias the regulator's internal pass transistor and the IC will be toast.

The way to keep this from happening is to use the quench diode. In normal operation, the diode is going to be reverse biased and won't have any effect on the operation of the regulator. This will be true even if an output short occurs because, even then, the output voltage will be less than the input voltage. If, however, the input voltage falls below the output voltage, the diode will begin to conduct, and the energy



FIG. 1—THE STANDARD 78XX REGULATOR is in the simplest power supply we can build. The circuit layout is exactly the same for any member of this family.

from the capacitor will be shunted through the diode and it will prevent the regulator's output stage from being completely destroyed. The diode rating depends on the circuit but, since we're not extending the standard limits of the 78XX, a diode rated for 2 amperes should be more than adequate. Keep in mind that having the diode there doesn't mean that you can be more casual than usual in designing the circuits that are going to be powered by the supply.

Other than that diode, our power supply is pretty straightforward. All that's needed are a few capacitors, diodes, and a separate 78XX regulator for each of the voltages you want available. Since the supply will be providing both 5 and 12 volts, a 7805 and a 7812 are needed. (I made a mistake last month when I said I would use 9 volts as the design criteria for the supply—I meant 5 volts—sorry about that.)

The last serious bit of business we have to cover regarding the power supply is the issue of isolation. From a practical point of view, isolating the power supply from the car's electrical system requires only a single resistor. The value of the resistor is determined by calculating the maximum amount of current the supply will be drawing. For most applications, the amount of current drawn by the supply is the same as the amount of current the supply is expected to deliver—in this case that number is half an ampere per regulator. All that's left to determine, in order to calculate the value of the resistor, is the voltage available to the power supply.

Since the supply will usually be used while the car is running, it is reasonable to assume that 13.5 volts will be present at the input of the supply. The resistor's value, as a simple application of Ohm's law (I = V/R) reveals, is 13.5/0.5 or 270 ohms.

Adding a 270-ohm resistor to the supply leg of each regulator subsection as shown in Fig. 1 will help isolate the different sections of the supply from each other as well as from the hostile electrical environment of an automobile. Decoupling capacitors and isolation resistors are good things to include in the



FIG. 2—FINAL POWER-SUPPLY DESIGN. Electrical ground connects the car battery and chassis ground to some convenient bolt on the body of the car. The operating voltage is the battery voltage.

design of any power supply, especially non-switching ones. As you'll see later, each circuit powered by the supply will get the same treatment as well, because you want to ensure that glitches in the car's electrical system will have a minimum effect on the circuits that will be added to the car.

The final design of the power supply is shown in Fig. 2. It incorporates all the refinements discussed and has a few other things added that are needed to meet the list of criteria I drew up last time. Electrical and chassis ground are simply made by hooking up wires to the appropriate points—the former should come from the battery, and the latter can come from the body of the car.

The operating voltage of the car is just the battery voltage, and you'll notice that I've used isolation and decoupling components there as well. More than likely, the only use you'll ever have for the battery voltage is to feed it to a voltmeter, but it's a good idea to buffer it before feeding it to any other circuitry.

You will need access to the alternator voltage. Although this is also buffered, your car characteristics will determine how useful it will be. My car has a separate alternator and voltage regulator, so I also brought the field voltage to the power supply board. That lets me keep an eye on the operation of both the regulator and alternator, but if your car has its voltage regulator built into the alternator, the value of alternator voltage will be considerably less informative because it will usually be a duplicate of the car's operating voltage.

Probably the best thing for you to do now is find the service manual for your car and see how your alternator/generator and voltage regulator are set up. This will show you which power lines are the most useful for extending to the power-supply board.

In the interests of saving money (for the manufacturers, that is), some important voltage test points in newer cars are being hidden from the probing eyes of owners. A service manual will at least give you some clues about where the lines are, so owning the manual is well worth the cost. Next month I'll begin designing a versatile tachometer that will not only function as a tach, but will also add goodies such as rpm averaging. Ω

What Do These Prestigious Companies Have In Common?

Aerovox
DC Film and RFI Suppression Capacitors, AC Oil Capacitors, EMI Filters

AMP
Electrical/Electronic Connectors, IC Sockets, PCB Switches

AVX CORPORATION
A KYOCERA GROUP COMPANY
MLC, Tantalum and Thin Film Capacitors, Resistors, Networks, Trimmers, Oscillators, Resonators, Filters and Piezo Devices

BERG ELECTRONICS
High Density and Industry Standard Connectors/Subsystems

BURNDY
an FCI Company
Electronic Connectors

CAROL
CAROL CABLE COMPANY INC
Electronic and Electrical Wire and Cable and Power Supply Cords

COLE FLEX
Tubing, Conduits, Hose, Sleevings, Splices, Insulation and Cable Harness Products

CII Communications Instruments, Inc.
Relays and Solenoid Relays

COOPER Belden
Multi Conductor, Paired, Coaxial, Flat, Fiber Optic, Instrumentation/Process Control, LAN, Special Application Cables, Power Supply Cords & Molded Cable Assemblies

COOPER Bussmann
Fuses, Fuseholders, Fuse Blocks, and Fuse Accessories

CORNELL DUBILIER
Capacitors-Aluminum Electrolytics, Mica, AC Oil, Film, MICA Paper and Relays

A COMPANY OF VISHAY **DALE**
Dale Electronics, Inc.
Resistors, Networks, Oscillators, Displays, Inductors & Thermistors

DANTONA INDUSTRIES, INC.
BATTERIES: Computer, Cordless Phone, Scanner & R/C.
ANTENNAS: Cordless Phone (metal & rubber), Scanner Bumpers, Grommets and Stik-On Feet

DEARBORN WIRE AND CABLE L.P.

EATON
Eaton Corporation, Commercial & Military Controls Operation
Switches, Relays, Displays and Keyboards

A **GERNSBACK** PUBLICATION
Electronics Now Magazine

KOA SPEER ELECTRONICS, INC.
Resistors, SMT Tantalum Capacitors Inductors, Resistor Networks, SMT Thermistors

MALLORY
North American Capacitor Company
Tantalums, Aluminums, Sonalerts®
Ceramics, Films and AC's

M-tron
Quartz Crystal Clock Oscillators and Special Hybrid Products

muRata ERIE
MURATA ERIE NORTH AMERICA
Monolithics, Discs, Variable Capacitors, Oscillators, Potentiometers, RFI/EMI Filters, Microwave, Surface Mount Capacitors

NTE ELECTRONICS, INC.
A WORLDWIDE REPUTATION FOR QUALITY, SERVICE AND VALUE
Semiconductors, Resistors, Capacitors, Relays

Philips ECG
A North American Philips Company
Semiconductors, Test Equipment, Relays, A/V Parts and Chemicals

Quam
Loudspeakers and Commercial Sound Products

ROHM
Rohm Electronics Division
Resistors, Ceramic Capacitors, Transistors/Diodes, Opto Components and IC's

SELECTA
Electrical · Electronic Products
Switches, Relays, Terminals, Indicator/Pilot Lights, LED Indicators, Test Clips, Test Leads, Cable Ties and Heat Shrinkable Tubing

A COMPANY OF VISHAY **SPRAGUE**
Tantalum Capacitors, Wet & Foil Capacitors, Resistor Networks, Resistor Capacitors Networks, Filters

Switchcraft
A Raytheon Company
Switches, Connectors, Jacks, Plugs, Jackfields & Audio Accessories

TECH SPRAY
Non-CFC Cleaners/Degreasers, UV Cured Compounds, Swabs, Wipes, Brushes, Wick, Cleanroom Supplies, and Static Control Products.

They sell through distributors. They belong to the E.I.A. They belong on your vendor list.

Leadership in electronics is not just a matter of designing products better and manufacturing them better, but also of marketing them better. And the sponsors of this message understand that better service to customers *requires* effectively involving distributors as part of their marketing teams.

Distributor involvement means lower prices, quicker deliveries, better service over-all. The Buyer wins. . . the Seller wins.

Distributors help achieve marketing leadership. So does the manufacturer's involvement in the Components Group of the Electronic Industries Association. EIA fosters better industry relations, coherent industry standards, and the sharing of ideas, which helps one another *and* serves customers better.

In choosing your component supplier, look for the marks of leadership —

availability through distribution
membership in the E.I.A.

ELECTRONIC INDUSTRIES ASSOCIATION · EIA · EST. 1924

Electronic Industries Association/Components Group
2001 Pennsylvania Avenue, N.W. 11th Floor
Washington, D.C. 20006
Phone: (202) 457-4930 Fax: (202) 457-4985

Committed to the competitiveness of the American electronics producer

CALLER ID

continued from page 37

module. Pin 1 on the PC board is indicated by a rectangular pad instead of an oval one. Be sure to match this pad with the pad labeled 1 on the display module board.

The size of the PC board and the location of the mounting holes are arranged so it mounts directly into a 3- × 4- × 2-inch plastic enclosure (it's manufactured by Serpac, and available from Digi-Key as part no. SR232G-ND).

If you are mounting the board in a different enclosure, do not use metal standoffs. The standoffs could short against one of the traces on the bottom side of the board. Position the display and the three pushbutton switches on the bottom side of the top cover, and, being very careful, mark it for drilling and cutting.

Mount the switches and display to the cover and make the appropriate connections to the board. Label S1 "REVIEW FWD," S2 "REVIEW BCK," and S3 "CLEAR." Hook up the 9-volt power supply to the positive and negative terminals as shown in Fig. 4.

Use a telephone cord with a modular jack on one end and run the cord through a small hole in the case, tie a knot in the cord for strain relief, and solder the red and green wires to the correct pads. After all connections have been made to the board, place the board at its mounting location and mark the spot on the enclosure directly below the slot in potentiometer R14. Remove the board and drill a hole at that spot just big enough for a small screwdriver, and then re-mount the board in the enclosure. The hole will allow you to make adjustments to R14 without removing the case. Last, install the two ICs in their sockets. Figure 5 shows the completed caller-ID prototype.

Operation

Adjust R14 to its mid-position and apply power. If everything is wired up correctly, a logo will appear on the LCD display. While viewing this message you can adjust R14 to change the contrast of the display. If the message does not appear, there is an error in the wiring and you should remove power and closely examine the board. A prime spot for error would be the ribbon cable that connects the main PC board to the display module. Check for solder bridges on both ends of the cable, and verify that the pin numbers on the main board and on the display board correspond with each other.

At the end of the logo display the word "Ready" will be displayed and will remain for about 20 seconds before the display clears. Note that this will work without being plugged into a phone line.

The Caller ID unit is now ready to be hooked up to the telephone line and receive data. Use a modular duplex jack so that the unit can share the same wall jack with your telephone.

Remember that you must subscribe to the Caller ID service before your unit will work. It might take several days to be hooked up, depending on your local telephone company, so it is a good idea to do this in advance.

When each call comes in, the display shows the time of day on the left side and either the telephone number, the word "Private," or the word "Out Area" on the right side. Pressing S2 "REVIEW BCK" shifts the display to view previous calls and pressing S1, "REVIEW FWD" shifts the display back to the most recent call. Holding down either one of the review buttons causes the display to scroll through the calls, stopping at either the most recent or oldest call, depending on which direction you are scrolling.

You do not have to shift back to the most recent call before receiving a new one. The display automatically returns and adds the new call directly after the most recent call, knocking out the oldest call if five calls already exist in the unit's memory. Ω

FREE

Electronics & Computer Software Education Catalog

*Fast-Track Individual Learning Programs
*State-of-the-Art Classroom Courses
*The Best Values in Electronics Education

New

Career-Level Courses
Personal Computer Servicing
TV and VCR Servicing

New

Computer-Aided Instruction

DC & AC Electronics
Semiconductors
Electronic Circuits

The stunning animations, hypertext glossary, and easy-to-understand text make learning electronics a breeze...and fun!

Learn the easy and affordable way from the Masters in Electronics Training - Heathkit®. From Basic Electricity to Advanced Microprocessor Applications and more, Heathkit will provide you with an unparalleled learning experience at a fraction of the cost of other programs.

Heathkit®
Educational Systems
For your FREE Catalog, call
Toll-Free 1-800-44-HEATH
please mention this code when calling 020-019

CIRCLE 86 ON FREE INFORMATION CARD

SUPER 12 HOUR RECORDER
CALL TOLL FREE

Modified Panasonic Slimline,
6 hrs per side
120 TDK tape furnished.
AC/DC Operation.
Quality Playback.
Digital Counter.
Durable Lightweight Plastic.
$119.00*

PHONE RECORDING ADAPTER

Starts & Stops Recorder Automatically When Hand Set is Used.
Solid State!
FCC Approved

$28.50*

VOX VOICE ACTIVATED CONTROL

Solidstate Adjustable Sensitivity. Voices & Sounds Activate Recorder
Adjustable Sensitivity
Provisions for Remote Mike

$28.50*

* Add for ship. & handling. Phone Adapter & Vox $2.00 each, Recorders $5.00 each. Colo. Res add tax. Mail Order, VISA, M/C, COD's OK. Money Back Guar. Qty Disc. available. Dealer inquiries invited. Free data on other products.
AMC SALES INC. 193 Vaquero Dr.
Boulder, CO. 80303
Phones (303) 499-5405 **1-800-926-2488**
FAX (303) 494-4924
Mon-Fri 8-5 MTN. TIME

CIRCLE 108 ON FREE INFORMATION CARD



Plans for the world's zaniest plaything—
September 1989



Put together your own Macintosh computer—
September 1991

Build the Tesla Coil that went square!—
August 1989

Take a chance on our Dice-Roulette project—
April 1989

Get the one you missed!

Popular Electronics®

Popular Electronics back issues are available although quantities of some issues are nearly exhausted. Here's an opportunity to complete your collection, or obtain a selected back issue you cannot find elsewhere. This offer is valid only when using the coupon on this page or a photo copy.

Special Back Issue Offer!

Please circle the issue(s) ordered!

	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sep.	Oct.	Nov.	Dec.
1987	1	2	3	4	5	6	7				11	12
1988	1	**1987-1988 back issues not available**								22	23	24
1989	25	26	27	28	29	30	31	32	33	34	35	36
1990	37	38	39	40	41	42	43	44	45	46	47	48
1991	—	49	—	50	51	52	53	54	55	56	57	58
1992	59	60	61	62	63	64	65	66	67	68	69	70
1993	71	72	73									

Note: Issues prior to November 1988 are "Hands-on Electronics"—the predecessor of Popular Electronics.

How to determine cost!

Quantity	Price per copy United States	Canada	Foreign
1-5	$6.50 US	$6.50 US	*
6-11	5.50	5.75	$8.00 US
12-23	5.00	5.25	7.50
24 and more	4.50	4.75	7.00

Prices include handling and shipping. Prices subject to change. All orders payable in U.S.A. funds only, via international money order, check drawn on a U.S.A. bank, or acceptable credit card (Visa, MasterCard) in U.S.A. funds. Allow 6-8 weeks delivery. Foreign orders may take longer. *Minimum foreign order—6 issues.

☐ Visa ☐ MasterCard ☐ USA Bank Check ☐ US or Int. Money Order

[**Note:** Credit Card minimum order is $15.00.]

Credit Card Number _____ Exp. Date _____/_____

Signature _____

Name _____

Address _____

City _____ State _____ ZIP _____

Send Orders To: CLAGGK, Inc., P.O. Box 4099, Farmingdale, NY 11735. Sorry, no telephone orders.

HEAT DETECTOR

continued from page 43

housing assembly to the focus tube with plastic electrical tape. Then insert the focus tube in the larger circuit tube as shown in Fig. 5.

Operating instructions

Be sure to allow the detector to "soak" in the ambient temperature in which it will be operated until it becomes temperature stabilized. For example, if it is to be used outdoors in the winter or summer when the temperature is significantly lower or higher than room temperature (22°C), allow the unit to remain in that environment for at least one hour and possibly as long as two hours before attempting to detect objects.

The ability of the detector system to discriminate a heat-producing stationary object from its background environment will depend on chopper-motor speed. Maximum sensitivity is achieved with one-tenth chopper revolution per second, but a chopper speed of 1 to 3 rps is recommended.

However, if you elect not to use the chopper for some application or experiment, look into the open end of the tube and move the shutter so that it is aligned in the focal plane to minimize interference with the incoming infrared emission.

The field of view of this instrument with the Fresnel lens and pyroelectic detector specified is approximately 8°. Larger objects can be detected by panning the unit horizontally after mounting it on a rigid tripod.

After you are satisfied that the focus tube has been adjusted to the optimum focal length, mark the location of the end of the larger diameter tube on the smaller diameter tube. Drill a small hole in the end of the smaller diameter tube and insert a small plastic screw to act as a stop, as shown in Fig. 5. Either apply a patch of black plastic electrician's tape or slide an opaque plastic sleeve over the detector access port to keep out ambient light. Ω

Electronics NOW® mini-ADS



WORLD'S SMALLEST FM TRANSMITTERS! New Surface Mount Technology (SMT) makes all others obsolete! XST500 Transmitter—powerful 3 transistor audio amplifier, transmits whispers up to 1 mile. XSP250 Telephone Transmitter-line powered, transmits conversations up to ¼ mile. Both tune 88-108 MHz. Easy to assemble E-Z KITS (SMT components pre-assembled to circuit board)! XST500—**$44.95,** XSP250—**$34.95,** VISA/MC. COD add **$6. XANDI ELECTRONICS, 201 E. Southern Ave., Suite 111, Tempe, AZ 85282. 1-800-336-7389.**

CIRCLE 181 ON FREE INFORMATION CARD

CABLE TV 50dB NOTCH FILTERS for interference removal or channel censoring. Filters are user-adjustable to desired channel # or frequency. Eight Models available, each for certain channels: 2 & 3; 4 to 6; 7 to 13; 14 to 17; 18 to 22; 23 to 29; 30 to 36; 95 to 99 plus 0 & 1. Just **$30** each or 3 for **$75**, includes shipping. ONE MONTH MONEY BACK, fast delivery. Visa, MC, check or M.O. (C.O.D. is **$5** extra) Huge discounts for higher quantities. **STAR CIRCUITS, P.O. Box 94917, Las Vegas, NV 89193. Call 24 hours 1-800-535-7827.**



CALL NOW AND RESERVE YOUR SPACE

- 6 × rate $940.00 per each insertion.
- Fast reader service cycle.
- Short lead time for the placement of ads.
- We typeset and layout the ad at no additional charge.

Call 516-293-3000 to reserve space. Ask for Arline Fishman. Limited number of pages available. Mail materials to: mini-ADS, ELECTRONICS NOW, 500-B Bi-County Blvd., Farmingdale, NY 11735.

FAX: 516-293-3115

GET YOUR RECHARGE CATALOG FREE...EARN BIG $$ IN YOUR SPARE TIME—All supplies and Do-It-Yourself kits with complete instructions available. Supplies cost from **$9.95** in qty and you can sell recharged toner cartridges for **$40.00** to **$55.00** each. Printers include HP Laser-Jet Series I, II, III, IV, Apple LaserWriter, QMS, etc. Canon PC Copiers also. **CHENESKO PRODUCTS, 2221 Fifth Ave., Suite #4, Ronkonkoma, NY 11779, 516-467-3205. FAX 516-467-3223, 1-800-221-3516**

CIRCLE 110 ON FREE INFORMATION CARD



CRYSTAL-CONTROLLED! 5 MINUTE ASSEMBLY! MONEYBACK GUARANTEE! Attach 3 wires and hear every whisper up to 2 miles away on any programmable scanner or VHF surveillance receiver. Pre-tested surface mount module uses standard 9V battery for 100mW output! Includes battery box and crystal for 140MHZ. Custom frequencies available for Law Enforcement. Model VX-100 only **$79.95 + 2.00** S&H. VISA, MC, MO. COD add **$5.00. DECO INDUSTRIES, BOX 607, BEDFORD HILLS, NY 10507. 914-232-3878.**

CIRCLE 127 ON FREE INFORMATION CARD

COMPUTER CONNECTIONS

The National Information Infrastructure

JEFF HOLTZMAN

One good thing about the Clinton administration: It seems to value technology. Nowhere is the administration's acceptance of technology more apparent than in its Agenda for Action regarding the National Information Infrastructure (NII). NII has become the umbrella concept for uniting a disparate collection of technologies, including computers, networking, and wireless communications, to provide anytime anywhere access to anything. This time I'll talk about the nature of the NII agenda, as well as critical industry response to it. Many aspects of this agenda are still under debate, so things might have changed and probably will by the time you read this.

Why NII?

The agenda outlines three basic reasons why the NII is necessary: flexible employment, targeted education, and intelligent health care.

The first is a person's ability to live anywhere, without foregoing the opportunity for intellectual and economically rewarding employment. The idea is that information workers could telecommute to their jobs via high-bandwidth data links.

Second is a person's ability to learn anywhere, without being hampered by the lack of local resources or a physical disability. Bright kids in rural districts would be able to link to virtual electronic classrooms at leading schools, thereby having access to quality instruction.

Third is a person's ability to obtain appropriate health care when and where needed. Much health care might be unneeded or inappropriate. Trying to cure severe diseases after they have taken hold is more expensive than catching them at an early stage. People with on-line access to expert medical resources might pay more attention to preventive health care.

What is the NII?

The Agenda defines it this way: "A seamless web of communications networks, computers, databases, and consumer electronics that will put vast amounts of information at users' fingertips."

By contrast, what we have now are sets of building blocks that don't fit together very well—if at all. Our communications networks include multiple, unconnected webs and subwebs. These include the telephone networks, the cable-TV networks, the Internet, 50,000 electronic bulletin board systems (BBSs), and the local-, metropolitan-, and wide-area networks (LANs, MANs, and WANs) that are proliferating in corporate America and worldwide.

The cable-TV networks have high bandwidth and connectivity to most of urban America, but the industry has an extremely poor service record. The phone companies have less bandwidth, but equally broad connectivity, and a fairly good service record. However, their inability to implement even low-bandwidth (128K bps) ISDN (integrated services digital network) over the past decade does not reassure us about the future. The Internet was originated for scientists, engineers, and researchers, but its use is rapidly spreading to corporations and individuals. Nonetheless, navigating the Internet is still too difficult and expensive for average users. BBSs have evolved in an ad hoc way to support computer-user communications, but there is precious little of value for professionals. Its bandwidth is low, but its connectivity is flexible.

Our computer systems are just as varied, as they include PCs, Macintoshes, Unix boxes, and numerous minicomputer and mainframe systems. These are being supplemented by new technological systems including cellular telephone/modem systems and pen-based personal digital assistants. Those devices give us the promise of simpler, more efficient means for interacting via digital technology with remote systems. But right now, it's still only a hope.

The most important factor is the data. There is already a tremendous

TABLE 1—NII OBJECTIVES

1.	Promote private sector investment, through appropriate tax and regulatory policies.
2.	Extend the "universal service" concept to ensure that information resources are available to all at affordable prices.
3.	Act as a catalyst to promote technological innovation and new applications.
4.	As the NII evolves into a "network of networks," promote seamless, interactive, user-driven operation of it.
5.	Ensure information security and network reliability.
6.	Improve management of the radio frequency spectrum.
7.	Protect intellectual property rights.
8.	Coordinate with other levels of government, with other nations, with industry, with labor, with academia, and with the public.
9.	Provide access to government information and improve government procurement.

EN Computer Admart

Rates: Ads are 2¼" × 2⅞". **One** insertion **$995 each. Six** insertions **$950** each. **Twelve** insertions **$925** each. Closing date same as regular rate card. Send order with remittance to **Computer Admart,** Electronics Now Magazine, 500-B Bi-County Blvd., Farmingdale, NY 11735. Direct telephone inquiries to Arline Fishman, area code-**1-516-293-3000. FAX 1-516-293-3115.** ***Only 100% Computer ads are accepted for this Admart.***

Get Started in Lotus 1-2-3 The Easy Way

If you are getting started in Lotus 1-2-3 at any release level, you'll want these power-packed duo publications designed for first-time users and those who need refresher orientation. To get both (**BP261** and **BP302**) send **$12.20** plus **$2.50** for shipping in the U.S. only to **Electronics Technology Today Inc., P.O. Box 240, Massapequa Park, NY 11762-0240.**

GET THE MOST FROM YOUR PC'S HARD DISK

If you are disorganized and use your hard disk inefficiently, you need this book to help you organize your files, use batch files, and use backup and security procedures. To get your copy (**BP280**) send **$6.95** plus **$2.50** for shipping in the U.S. only to **Electronics Technology Today Inc., P.O. Box 240, Massapequa Park, NY 11762-0240.**

PC-BUS POWER MONITOR CARD



Diagnose intermittent crashes, detect power disturbances, and spot bad power supplies in PC, AT and EISA systems. It checks all four supply voltages, and remembers momentary out-of-tolerance operation.

WINTEK **Wintek Corporation**
1801 South Street
Lafayette, IN 47904

Phone: 800-742-6809 or (317) 448-1903

CIRCLE 186 ON FREE INFORMATION CARD

amount of data in digital format in data bases, and it seems to be growing exponentially. One priority of the Agenda is making the vast quantities of data created by various government agencies accessible to the taxpayers who paid for it. Making data available is half of the problem; the other half, one that will require gargantuan technological innovation, is providing tools that help the taxpayers find what they want.

NII objectives

The NII Agenda has nine objectives, shown in Table 1, that guide it. The following are a few notes about each:

1. At one time, Vice President Gore advocated direct government involvement in building and operating the NII. Wisely, he has retreated from that position. Now the administration advocates a government role limited to leadership and coordination, leaving implementation to industry.

2. The Communications Act of 1934 articulated in general terms a national goal of Universal Service for telephones, which called for widespread availability of a basic communications service at affordable rates. A major objective in developing the NII will be to extend the Universal Service concept to the information needs of the American people in the 21st Century. As a matter of fundamental fairness, this nation cannot accept the division of our people into telecommunications or information "haves" and "have-nots."

3. The Clinton/Gore administration plans to invest $1 to 2 billion annually in deploying NII technology. This investment will be applied to both computing and communications. U.S. industry, by contrast, has been investing about $50 billion annually on communications alone in recent years.

4. User-driven information tools will be a hot area of development. User interfaces must improve by an order of magnitude—maybe two—before the common man or woman will be able to make effective use of NII.

5. Security and reliability are crucial. The network must be impervious to, or at least tolerant of, natural disasters, war, and hacking/phreaking.

6. Wireless connectivity plays a key role in the anytime/anywhere portion of the NII goals. The technology here goes by the name Personal Communication Services (PCS); it typically includes spread-spectrum cellular radio transmission, but with higher reliability and more flexibility than current systems. Frequency spectrum allocation thus becomes critical. Recently, the National Telecommunications and Information Administration (NTIA), a division of the U.S. Department of Commerce, advocated a scheme allowing both "large" (30 MHz) and "small" (10 to 15 MHz) chunks of spectrum to be auctioned. The hope is that smaller, more innovative firms would be able to bid on the smaller chunks; in addition, spectrum space could be used more efficiently in smaller chunks.

7. Digital technology, with its ability to capture and modify information in just about any form, has created a morass of moral and legal issues regarding copyrights. Several current projects (e.g., Plexus and Project Gutenberg) seem to advocate a copyright-free world in which everything is available to everyone without obligation. But commercial publishers and media corporations will never go for that, nor will most individual authors be willing to assign their intellectual property rights over to the public domain. Thus a system for tracking the use of copyrighted materials, and compensating authors accord-

VCR Cross Reference

NOW Find the right Part for your VCR



With the

ISCET VCR CROSS REFERENCE

This 270-page reference contains both model and part-number cross-references updated to include 1992 units.

VCR's are made in a few factories from which hundreds of different brand names and model numbers identify cosmetically-changed identical and near-identical manufactured units. Interchangeable parts are very common. An exact replacement part may be available only a few minutes away from you even though the manufacturer supplier is out-of-stock. You may be able to cannibalize scrap units at no cost!

The ISCET VCR Cross Reference is pre-punched for standard loose-leaf binding. . .$38.00 plus $3.00 for shipping for each Reference.

Claggk Inc.
VCR CROSS REFERENCE OFFER
P.O. Box 4099
Farmingdale, New York 11735

Name _____
Business _____
Address _____
City _____
State _____ Zip _____
Phone _____

Enclose **$38.00** for the Third Edition of the ISCET VCR Cross Reference and **$3.00** for shipping for each Reference.
The total amount of my order is $ _____.
Check enclosed—do not send cash.
or please charge my credit card.
☐ Visa ☐ MasterCard Exp. Date ___/___/___
Card No. _____
Signature _____
New York State residents must add applicable local sales tax to total.

ingly, is required.

8. The Agenda clearly recognizes the need for coordinated action between Federal, state, and local governments, and their agencies, particularly the Congress, the FCC, and the Executive branch, as well as foreign governments. This is a big problem; half-cocked attempts are bound to fail and even harm efforts through loss of credibility, much as NASA has suffered in the past few years. It's critical that this job be done right, from the beginning.

9. "Information is the currency of democracy," said Thomas Jefferson; never was that statement more true than it is today. The federal government produces unbelievable quantities of information, some of which could be valuable, were it accessible at low cost and with ease. Some information is currently placed on expensive on-line services (e.g., Dialog), which can cost hundreds of dollars per hour to access. Other information is recorded on CD-ROMs, but then sold for exorbitant rates. Clearly, we the people—the taxpayers—paid for this information once; there is no reason why we should have to pay for it twice.

Convergence

People have been talking about convergence among the computing, communications, and publishing industries since the mid 1980s. (See my June and July 1993 columns for a more complete discussion of these concepts.) What's new now is that there is high-level political recognition of the importance of this trend, of the importance of not being a follower but a leader.

The Clinton administration has taken several steps to ensure follow-through on this initiative. It has convened an Information Infrastructure Task Force (IITF) for the purpose of pursuing the nine goals outlined above. The IITF has already spawned three subcommittees that are attacking various aspects of the problem, including telecommunications policy, information policy, and applications. The President is also expected to sign an executive order creating an advisory council, from industry, whose primary concern is NII matters. The administration is also encouraging, within government agencies closely allied with NII matters, the use of E-mail and other information technologies now taken for granted at most corporations. Perhaps after experiencing the productivity gains made possible by advanced computers and communications firsthand, the bureaucrats will learn to accomplish something.

Some in American industry will undoubtedly decry any kind of government involvement, but I think it's a good thing—as long as the government doesn't try to exert too much control or impede progress by over-bureaucratizing efforts. The problems of integrating our diverse digital information systems are just too great for industry to sort out by itself within a reasonable amount of time. We need strong leadership and a process for working out compromises among the many headstrong players in this game. We as citizens need to insist that the processes do not become bogged down in haggling over trivia, because Europe and the Pacific are working on similar initiatives, and getting there first will certainly provide strategic global advantage.

The ideal situation would allow anytime, anywhere access to anything, regardless of provider, platform, or transport. We're a long way from that now, so the current initiatives will encourage experiments covering various portions of the problem. Some of these experiments will be performed by IBM, AT&T, and Time-Warner, TCI. Others will be performed by small startups that do not yet exist. Indeed, the government has budgets earmarked expressly for the purpose of funding startups untainted by big-company thinking. You might want to get in on some of that. Ω



"He said service is no problem. . .just bring it into the shop."

BUYER'S MART

FOR SALE

TUBES: "oldest", "latest". Parts and schematics. SASE for lists. **STEINMETZ,** 7519 Maplewood Ave. RE, Hammond, IN 46324.

TUBES, new, up to 90% off, SASE, **KIRBY,** 298 West Carmel Drive, Carmel, IN 46032.

Quality Microwave TV Antennas

WIRELESS CABLE - IFTS - MMDS - Amateur TV
Ultra High Gain 50db(+) • Tuneable 1.9 to 2.7 Ghz.

- 55-Channel Dish System $199.95
- 36-Channel Dish System $149.95
- 20-Channel Dish System $124.95
- Optional Commercial Grid Antenna (not shown) Add $50.00
- Yagi Antennas, Components, Custom Tuning Available
- Call or write (SASE) for "**FREE**" Catalog

PHILLIPS-TECH ELECTRONICS
P.O. Box 8533 • Scottsdale, AZ 85252
(602) 947-7700 ($3.00 Credit all phone orders)
MasterCard • Visa • American Express • COD's • Quantity Pricing

Dish System
LIFETIME WARRANTY

CABLE test chips. Jerrold, Tocom, S.A., Zenith. Puts cable boxes into full service mode! $29.95 to $59.95. 1 (800) 452-7090, (310) 902-0841.

SECRET cable descramblers! Build your own descrambler for **less** than $12.00 in **seven easy steps! Radio Shack** parts list and **free** descrambling methods that **cost nothing** to try, included. Send $10.00 to: **INFORMATION FACTORY,** Dept. 4, PO Box 669, Seabrook, TX 77586. For COD's (713) 922-3512 any time!

DESCRAMBLE cable. Add simple circuit to Radio Shack RF modulator. Instructions $8.00. **TELCOM,** Box 832E2, Brusly, LA 70719.

PRINTED circuit boards from your artwork. Prototype and short runs. Reasonable rates. **ATLAS CIRCUITS,** PO Box 892, Lincolnton, NC 28093-0892. (704) 735-3943.

COMPUTER power supply repairs. Most manufacturers serviced. Fix sheets also available. **JATINAH COMPUTER SERVICES,** (214) 306-1448.

FREE CATALOG

FAMOUS "FIRESTIK" BRAND CB ANTENNAS AND ACCESSORIES. QUALITY PRODUCTS FOR THE SERIOUS CB'er. SINCE 1962

FIRESTIK ANTENNA COMPANY
2614 EAST ADAMS
PHOENIX, ARIZONA 85034

RESTRICTED information: surveillance & schematics, locks, cable, hacking, more. Details: **MENTOR,** Box 1549-Z, Asbury, NJ 07712.

CABLE TV converters. Jerrold, Zenith, Pioneer, Oak, Scientific Atlanta, and many more. 12 years experience gives us the **advantage.** Visa/MC Amex COD **ADVANTAGE ELECTRONICS, INC., 1 (800) 952-3916** 1125 Riverwood Dr., Burnsville, MN 55337.

ACE personal security **products.** Cable boxes have make and model ready. Call for free brochure 1 (800) 234-0726.

Look to the Future
With Your Own
Cable Converter & Descrambler !

1-800-228-7404

NU-TEK ELECTRONICS
FREE CATALOG!

3250 Hatch Rd.
Suite 1 C
Cedar Park, TX 78613

ALL MAJOR BRANDS

COD

MCM ELECTRONICS

YOUR ELECTRONIC SOURCE FOR THE 90's



When it comes to electronic parts and components, you'll find virtually everything under the stars at MCM. Our selection includes over 20,000 items and a state-of-the-art inventory system that will have your order ready to ship within 24 hours. Choose from our galaxy of VCR parts and accessories, TV components, connectors, semiconductors, test equipment, tools and chemicals, including many top brand names and hard-to-find items. And if you ever feel "lost in space" over a technical problem, call our friendly Toll-Free Technical Assistance Line at 1-800-824-TECH(8324). Let MCM be your electronic source for the 90's... and beyond.

FOR A FREE CATALOG CALL 1-800-543-4330
FAX: 1-513-434-6959

MCM ELECTRONICS
650 CONGRESS PARK DR.
CENTERVILLE, OH 45459-4072
*A **PREMIER** Company*



Serving you coast to coast. Distribution facilites in Dayton, OH and Reno, NV!

EN-86

CIRCLE 87 ON FREE INFORMATION CARD

CB RADIO OWNERS!

We specialize in a wide variety of technical information, parts and services for CB radios. 10-Meter and FM conversion kits, repair books, plans, high-performance accessories. Thousands of satisfied customers since 1976! Catalog $2.

CBC INTERNATIONAL
P.O. BOX 31500RE, PHOENIX, AZ 85046

300 Experimenters Circuits — Complete in 6 practical books using diodes, relays, FET's, LED's, IC 555's, and IC CA3130's for building blocks. Only $33.00 plus $5.50 for shipping. USA and Canada only. US funds. **ETT, INC.,** PO Box 240, Massapequa Park, NY 11762-0240.

CABLE Converters, accessories below wholesale! Immediate delivery from giant stock! COD orders only. 1 (800) 995-1749.

CABLE TV UNIVERSAL DESCRAMBLER

Product Guaranteed
Works With All Systems

Free Catalog 1-800-664-6999
No Florida Sales!
Halcyon Group

VISA

CABLE TV converters: Jerrold, Oak, Scientific Atlanta, Zenith & many others. "New MTS" stereo add-on: mute & volume. Ideal for 400 and 450 owners! 1 (800) 826-7623, Amex, Visa, M/C accepted. **B & B INC.,** 3584 Kennebec, Eagan, MN 55122.

TEST equipment pre-owned now at affordable prices. Signal generators from $50.00, oscilloscopes from $50.00. Other equipment including manuals available. Send $2.00 U.S. for catalog refunded on first order. **J.B. ELECTRONICS,** 3446 Dempster, Skokie, IL 60076. (708) 982-1973.

DESCRAMBLING secrets revealed. Free 24 hour hotline reveals secret satellite and cable descrambling information. (718) 390-7130.

CABLE test-chips as low as $9.95, for testing cable boxes in **full service** mode. Jerrold; Starcom VI & VII; Pioneer, clears E2 thru E5; Pioneer cubes: BA-5000 thru BA-6700; Tocom 5503/5507; Scientific Atlanta: 8500 thru 8600; Zenith: all but PZ1; remotes $10.00; money back guarantee. **N.E. ENGINEERING,** 1 (800) 926-4030, fax (617) 770-2305.

DESCRAMBLERS for cable and satellite. Kits and assembled units. All types. Guaranteed. From $19.95. Free catalog. (212) 330-8035.

CONVERTER — descramblers: Examples, Zenith Ztac $199.00, ST1600 $240.00, Scientific Atlanta 85XX $190.00, 8600 $325.00, Oak RTC56 $99.00, M35B $45.00. **All Pioneer test generator** $150.00. Most makes in stock, COD ok. **MOUNT HOOD ELECTRONICS,** (206) 260-0107.

CABLE doctor. Stop the bullet and ID signals in cable lines. Send $20.00 to: **R.R. ENTERPRISES,** PO Box 3532, Easton, PA 18043.

TV notch filters, cylinder type. Eliminates beeping on your system. Professionally manufactured. Discounts. 1 (800) 331-2156 ext #2156.

RECEIVING TUBES

OVER 3000 TYPES IN STOCK!
Also hard-to-find transformers, capacitors and parts for tube equipment.
Send $2.00 for our 32 page catalog.

ANTIQUE ELECTRONIC SUPPLY
6221 S. Maple Ave.•Tempe, AZ 85283•602-820-5411

CABLE descramblers, test turn-on kits, bullet stoppers. We have the lowest prices in the industry. Call everyone else, then call us for the best price. We will buy or repair your cable equipment. No Florida sales. (305) 425-0751.

CABLE TV descramblers. Nobody beats our price! Quantity discounts. 24 hour shipping. All brands. Call **V.C.I.,** 1 (800) 677-0321.

PAY TV AND SATELLITE DESCRAMBLING
Our Best Yet 1994 EDITION Our Best Yet

Includes the latest cable box and satellite (PLUS, B-MAC) fixes. Lots of schematics and chip files (all new), bullets, ECM's, etc. ONLY $15.95. Our best yet. Other Pay TV editions, volumes 1-5 (all different). $15.95 each. The Complete Wizzard. VCII PLUS hacking. $15.95. Satellite Systems Under $600. $12.95. Wireless Cable Hacking $12.95. Hacker Video $19.95. Any 3/$34.95 or 5/$52.95. Scrambling News monthly $29.95. Scrambling News Year One (176 pages) $39.95. Everything listed here and more $129.95. Includes all our information. Catalogs $1.

Scrambling News, 1552 Hertel Ave., #123
Buffalo, NY, 14216. Voice/Fax (716) 874-2088
COD'S ARE OK. ADD $6

PREVENT descrambler damage. Don't bite the bullet! Snooper Stopper Data Pulse Blocker $34.95 — Data Blocker with dual surge protection $54.95 — Wireless Video Sender $54.95 — remote control A/B switch $39.95 — **VIDEO CONNECTIONS,** 1 (800) 925-9426.

CABLE TV descramblers. All major brands. Have make and model of the type used in your area when calling. 1 (800) 327-3407. **K.D. VIDEO,** PO Box 29538, Mlps., MN 55429.

THE Case Against the Patents. Thoroughly tested and proven alternatives that work in the real world. $24.50. **SYNERGETICS PRESS,** Box 809-C, Thatcher, AZ 85552. (602) 428-4073. Visa/MC.

ANTIQUE RADIO CLASSIFIED

Free Sample!
Antique Radio's Largest Circulation Monthly. Articles, Ads & Classifieds.
6-Month Trial: $16.95. 1-Yr: $29.95 ($44.95-1st Class).
A.R.C., P.O. Box 802-L11, Carlisle, MA 01741

PATENTING

INVENTORS: THE CONCEPT NETWORK represents people who want to patent and market their new product ideas. Schematics or prototype preferred but not required. **Free** information kit. Call 1 (800) 835-2246 ext 67.

CB'S AND SCANNERS

SCANNERS, C.B.'s, radar detectors. Call or write for **free** catalog. (803) 829-3411. **C.B. DOCTOR,** PO Box 2842, Orangeburg, SC 29116-2842. To place order call 1 (800) 569-1393.

CABLE TV DESCRAMBLERS

1-800-233-9388
FREE CATALOG
GUARANTEED BEST PRICES • IMMEDIATE SHIPPING
APPLE ELECTRONICS
3389 Sheridan St. • Suite 257
Hollywood, FL 33021

"YOUR FREE CATALOG KNOCKED MY SOCKS OFF"

We get that sort of comment all the time. People are impressed that our free Consumer Information Catalog lists so many free and low-cost government booklets. There are more than 200 in all, containing a wealth of valuable information.

Our free Catalog will very likely impress you, too. But first you have to get it. Just send your name and address to:

Consumer Information Center
Department KO
Pueblo,
Colorado
81009

A public service of this publication and the Consumer Information Center of the U. S. General Services Administration

ELECTRIFYING DEALS!!

★ CABLE TV ★ DESCRAMBLERS

CONVERTERS ★ ACCESSORIES
★ Name Brands ★ Great Service ★
★ Immediate Delivery ★ Lowest Prices ★
NOT AVAILABLE IN CALIFORNIA
CALL FOR FREE CATALOG **(800) 777-7731**
PRIME TIME Electronics, Inc.

MULTI-VISION ELECTRONICS

Converters & Descramblers
✱Jerrold ✱SA
✱Tocom ✱Oak
✱Zenith ✱More

Why tolerate unbearable, monthly cable fees when you can buy for less at Multi-Vision?
1-800-835-2330

Since 1973

Your One Stop Component & Computer Source

Tubeaxial AC and DC Fans

2R100976 

2R100917

2R100896

Part No.	Size L" x H" x T"	Voltage	CFM	1-9	10-99
2R100896	1.50 x 1.50 x .750	5 VDC	6	$8.95	$7.95
2R75336	1.60 x 1.60 x .630	5 VDC	4	8.95	7.95
2R18770	1.60 x 1.60 x .620	12 VDC	6	8.95	7.95
2R75344	1.60 x 1.60 x .800	12 VDC	5	8.95	7.95
2R75352	2.35 x 2.35 x 1.00	12 VDC	14	7.95	6.95
2R75361	3.15 x 3.15 x 1.00	12 VDC	24	7.95	6.95
2R16993	3.15 x 3.15 x 1.00	12 VDC	27	9.95	8.95
2R75395	3.15 x 3.15 x 1.25	12 VDC	22	6.95	5.95
2R75441	3.63 x 3.63 x 1.00	12 VDC	35	7.95	6.95
2R75467	4.68 x 4.68 x 1.00	12 VDC	53	11.95	10.95
2R94625	4.68 x 4.68 x 1.50	12 VDC	75	12.95	11.95
2R100909	1.50 x 1.50 x .750	12 VDC	22	6.95	5.95
2R100925	3.15 x 3.15 x 1.25	24 VDC	25	8.95	7.95
2R100933	3.15 x 3.15 x 1.60	24 VDC	35	8.95	7.95
2R100941	3.63 x 3.63 x 1.00	24 VDC	35	9.95	8.95
2R100950	4.69 x 4.69 x 1.00	24 VDC	60	10.95	9.95
2R100968	4.69 x 4.69 x 1.50	24 VDC	80	10.95	9.95
2R100976	4.69 x 4.69 x 1.50	28 VAC	75	10.95	9.95
2R75408	3.15 x 3.15 x 1.0	115 VAC	18	6.95	5.95
2R16969	3.15 x 3.15 x 1.50	115 VAC	23	7.95	6.95
2R16977	3.15 x 3.15 x 1.50	115 VAC	25	10.95	9.95
2R75432	3.63 x 3.63 x .80	115 VAC	47	10.95	9.95
2R75459	3.63 x 3.63 x 1.0	115 VAC	35	10.95	9.95
2R16934	4.68 x 4.68 x 1.50	115 VAC	90	13.95	12.95
2R16951	4.68 x 4.68 x 1.50	115 VAC	90	5.95	4.95
2R100917	3.15 x 3.15 x 1.50	230 VDC	27	10.95	9.95

AC Wall Transformers

2R10073

- Male Plug - 3.5 mm
- Female Plug - 2.1 mm
- UL listed
- Current rating to 1200mA

DC Wall Transformers

 2R15392

Part No.	Voltage	Current	Plug	Price
2R10129	9 VAC	500mA	Male	$4.95
2R100061	9 VAC	780mA	Female	4.95
2R10073	12 VAC	500mA	Male	5.49
2R101258	12 VAC	500mA	Female	5.95
2R10081	12 VAC	1000mA	Female	5.95
2R10428	12 VAC	1000mA	Male	5.95
2R100108	16 VAC	1100mA	Female	5.95
2R100191	18 VAC	80mA	None	3.95
2R100036	20 VAC	400mA	None	5.95
2R87581	24 VAC	500mA	Female	4.95
2R10102	24 VAC	1000mA	Male	7.95
2R101119	26 VACT	1200mA	None	7.95

Part No.	Voltage	Current	Plug	Price
2R100159	4 VDC	700mA	Male[2]	$2.95
2R15544	6 VDC	500mA	Male[2]	5.95
2R101266	6 VDC	500mA	Female[2]	5.95
2R100845	9 VDC	200mA	Female[2]	5.19
2R100837	9 VDC	200mA	Male[2]	4.95
2R100853	9 VDC	500mA	Female[2]	4.95
2R15561	9 VDC	500mA	Male[2]	4.95
2R100095	12 VDC	200mA	Female[2]	4.95
2R15368	12 VDC	500mA	Female[1]	5.95
2R17267	12 VDC	500mA	Male[2]	5.95
2R100870	12 VDC	1000mA	Female[2]	7.95
2R15392	12 VDC	1000mA	Male[2]	7.95

Call for information on our complete line of wall transformers. 

6 Outlet Wall Plug-In



Part No.	Product No.	1-9	10-99
2R99291	EP6	$5.95	$5.49

7 Outlet Power Strip w/4 ft. Cord



Part No.	Product No.	1-9	10-99
2R98749	LR69225	$9.95	$8.95

EPROMS

Part No.	Product No.	Price
2R39909	2708	$4.95
2R33611	TMS2716	5.95
2R40002	2716	4.49
2R40125	2732A-25	4.49
2R40230	2764A-20	4.75
2R39829	27C64-15	4.49
2R39933	27128-25	7.75
2R39968	27128A-20	4.95
2R39984	27128A-25	3.95
2R39677	27C128-15	5.75
2R40037	27256-15	5.49
2R40061	27256-25	4.75
2R39714	27C256-15	5.25
2R39722	27C256-20	4.95
2R39781	27C512-15	6.49
2R65699	27C020-15	10.95
2R43692	68766-35	4.95

TTL Integrated Circuits

Part No.	Product No	1-9	10-99
2R46252	74LS00	$.29	$.25
2R46287	74LS02	.29	.25
2R46316	74LS04	.29	.25
2R46375	74LS08	.29	.25
2R46640	74LS14	.39	.35
2R47458	74LS30	.29	.25
2R47466	74LS32	.29	.25
2R48004	74LS74	.35	.29
2R48039	74LS76	.69	.59
2R48098	74LS86	.35	.29
2R46447	74LS112	.39	.35
2R46480	74LS123	.39	.35
2R46607	74LS138	.39	.35
2R46957	74LS175	.39	.35
2R47036	74LS193	.59	.49
2R47183	74LS244	.69	.59
2R47212	74LS245	.69	.59
2R47600	74LS373	.69	.59
2R47634	74LS374	.69	.59

Carbon Film 1/4 Watt 5% Resistor Assortments

Part No.	Description	Price
2R10719	5 each 70 values (every other value from R10 ohm-R5.6 meg) 1/4 Watt Carbon Film Resistor Values (350 pcs.)	$9.95
2R10663	100 each (27 values) 1/4 Watt Carbon Film Resistors R10 thru R10M (2,700 pcs.)	39.95

SIPP to SIMM Module Converter

- Use SIPP's in place of SIMM's
- Upgrade from a SIPP Motherboard to a new SIMM Motherboard without buying new RAM • Fits into standard 30 pin SIMM socket
- Double sided board for reliable operation
- Size: 1.6" maximum height x 3.5"wide (with 9 chip SIPP installed)

Part No.	Product No.	Description	1-9	10-99
2R93382	JE430	SIPP to SIMM Module Converter	$9.95	9.49

Call or write for your

FREE Component Catalog-

IC's, Components, Test Equipment and much more!

1•415•592•8097 ☎

For International Sales, Customer Service, Credit Department and all other inquiries: Call 415•592•8097 between 7AM-5PM P.S.T.

Call 1•800•831•4242 to order today!

JAMECO™ ELECTRONIC COMPONENTS COMPUTER PRODUCTS

1355 Shoreway Road
Belmont, CA 94002-4100
FAX: 1•800•237•6948 (Domestic)
FAX: 415•592•2503 (International)

MasterCard VISA FEDERAL EXPRESS UPS

Mention V.I.P.# 2R4

CA Residents please add applicable sales tax.

Terms: Prices subject to change without notice. Items subject to availability and prior sale. Complete list of terms/warranties is available upon request.

© 1994 Jameco 2/94 All trademarks are registered trademarks of their respective companies.

Machine Tooled Low Profile Tin Plated IC Sockets

- Gold contact pins
- Tin plated tails
- Lead length: .188"
- Body height: .125"

2R37401

Part No.	Product No.	Pins	1-9	10-99
2R51625	8MLP	8 pin	$.49	$.45
2R37196	14MLP	14 pin	.59	.49
2R37401	16MLP	16 pin	.65	.55
2R65584	18MLP	18 pin	.75	.65
2R38623	20MLP	20 pin	.79	.69
2R39351	24MLP	24 pin	.85	.75
2R39386	24SMLP	24 pin	.89	.79
2R40328	28MLP	28 pin	.99	.89
2R41136	40MLP	40 pin	1.19	1.09
2R42059	48MLP	48 pin	1.49	1.39

D-Subminiature Solder Cup Connectors

- Compatible with 24 AWG Cable
- Solder cups for 22 AWG wire
- Metal shell
- Male connectors with grounding tangs

 2R15114

 2R15157

Part No.	Product No.	Gender	1-9	10-99
2R15747	DE9P	M	$.45	$.35
2R15771	DE9S	F	.49	.39
2R15034	DA15P	M	.55	.45
2R15051	DA15S	F	.59	.49
2R15114	DB25P	M	.65	.55
2R15157	DB25S	F	.75	.63
2R15472	DC37P	M	1.19	.95
2R15499	DC37S	F	1.25	.99
2R15675	DD50P	M	1.79	1.49
2R15691	DD50S	F	2.25	1.69

CIRCLE 114 ON FREE INFORMATION CARD

DO-IT-YOURSELF ELECTRONIC KITS
HOLIDAY SALE !!
10% OFF ON SELECTED ITEMS!
SAME DAY SHIPPING/QUANTITY DISCOUNTS

More than 60 kits available including high-fidelity audio products, lab equipment, power supplies, light controllers, games and numerous projects! Audio amplifiers range from 6 to 300 W. Quality kits at unbeatable prices starting from $ 7 ! Dealer inquiries welcome. In business since 1985.

▲ Beginner ▲▲ Intermediate ▲▲▲ Advanced!!

STEREO LOUDSPEAKER PROTECTOR TY-25 ▲

Kit: $ 15.85

Super fast acting relay protects speaker against destructive DC voltage. Can connect directly to a power amp. or can use a separate power supply. Has a 3 second turn-on delay to avoid turn-on thumps.

120W MOSFET POWER MONO AMP. TA-477 ▲▲

Kit: $ 68.00

120W into 8 ohms RMS. THD: <0.007%. Frequency Response: 8 HZ-20 KHZ, +0-0.4 dB. 2.8 HZ-65 KHZ, +0-3 dB. Sensitivity: 1V. Power Requirement: 55V DC @ 3A. May use Mark V Model # 003 or # 012 transformer.

300W HIGH POWER MONO AMP. TA-3600 ▲▲▲

Kit: $ 85.00

300W into 8 ohms RMS. Frequency Response: 10 HZ-20 KHZ. THD :< 0.05%. Sensitivity: 1V rms at 47K. Power Requirements: 60-75V DC at 8A. May use Mark V Model # 007 or # 009 transformer.

3½ MULTI-FUNCTION LED DPM SM-43 ▲▲

Kit: $ 34.50

AC/DC voltage range:1mV-1000V. Thermometer range: 0-100C. DC current range: 1 microamp - 2 amps. Capacitance range: 1 pf-2 microfarads. Frequency counter: 10 HZ-20K HZ. Max indication -1999 or +1999. Power Supply: 5 - 6V DC, 200ma.

METAL CABINETS WITH ALUMINIUM FRONT PANEL

LG-1684	4X16X8"	$ 28.50
LG-1924	4X19X11½"	34.50
LG-1925	5X19X11½"	38.00
LG-1983	2¼X19X8"	32.50

Cabinet Toroidal Transformer

MARK V ELECTRONICS, INC.
ORDER 1-800-521-MARK/1-800-423-FIVE
FREE CATALOG 213/ 888-8988 FAX 213/ 888-6868
8019 E. SLAUSON AVE. MONTEBELLO, CA 90640

CIRCLE 93 ON FREE INFORMATION CARD

CABLE TV
DESCRAMBLERS
Best Prices in the U.S.A.!
Guaranteed to Work!

QUANTITY DISCOUNTS

JERROLD PANASONIC
SCIENTIFIC ATLANTA PIONEER

The Newest & the Latest

DMTB-A - all Jerrold Impulse & Starcom series
SA3-DFA - all Scientific Atlantas including 8536, 8536+, 8580, Drop-field
PN-3A - all Pioneer systems

ALSO
FTB3, SA3, TZPC145G

24 HOUR SHIPMENTS
30 DAY MONEY BACK GUARANTEE
FREE CATALOG & INFORMATION

1-800-772-6244
M-F: 9-6 EST
U.S. Cable TV, Inc. Dept.: KEN024
4100 N. Powerline Rd. Bldg. F-4 Pompano Beach FL 33073
NO FLORIDA SALES!

CIRCLE 188 ON FREE INFORMATION CARD

CABLE BOX
WHOLESALERS, INC.

BEST BOXES—BEST PRICES
Immediate Shipping—COD's
Satisfaction Guaranteed
FREE Catalog—Call Now

800-841-7835

WANTED

INVENTORS: We submit ideas to industry. Find out what we can do for you. 1 (800) 288-IDEA.

INVENTORS

INVENTORS! Can you patent and profit from your idea? Call **AMERICAN INVENTORS CORP.** for free information. Serving inventors since 1975. 1 (800) 338-5656.

PLANS AND KITS

60 SOLDERLESS Breadboard Projects in two easy-to-read pocket books. Complete with circuit descriptions, schematics, parts layouts, component listings, etc. Both books (BP107 & BP113) only $11.90 plus $3.50 for shipping. USA and Canada only. US funds. **ETT, INC.,** PO Box 240, Massapequa Park, NY 11762-0240.

ANNOUNCING OmniAlert! (pat.pend) Designed by F-18 tactical radar engineer. Revolutionary photosensitive alarm safeguards your home, office, car, & valuables. Professionally engineered board & plans, guaranteed foolproof! $11.95. **DRALIN DESIGNS,** PO Box 04, Ellenburg Depot, NY 12935.

Kits * Kits * Kits

ADVANCED TELEPHONE DIALER
240 Number memory, LCD Display, Group Dialing
MULTI STATION THERMOMETER
LCD Display, RS232 Interface
CALL FOR PRICING AND INFORMATION
1-800-772-3945
GENOA Group, 7334 S.Alton Way,#H,Englwd, CO 80112

FASCINATING electronic devices! Voice Disguiser! Vocal truth indicator! Lasers! Transmitters! Detectors! Free energy! High voltage! More! Kits/Assembled! Catalog $4.00 (refundable). **QUANTUM RESEARCH,** 17919-77th Ave., Edmonton, Alberta, Canada. T5T 2S1.

PRINTED circuit boards, etched & drilled. Free delivery. **K&F ELECTRONICS INC.,** 33041 Groesbeck, Fraser, MI 48026. (313) 294-8720, fax (313) 294-5999.

THE Encyclopedia of Surveillance Schematics $20.00. Surveillance Catalog $5.00. **VHS,** 1055 W. College Avenue #137, Santa Rosa, CA 95401-5036.

SINGERS! REMOVE VOCALS!
Unlimited Backgrounds™
From Standard Records & CD's with the Thompson Vocal Eliminator™ Call for Free Catalog & Demo Record.
Phone: (404)482-4189 Ext 72
Singer's Supply, Dept RL-1
7987 Hightower Trail
Lithonia, GA 30058
24 Hour Demo/Info Request Line (404)482-2485 Ext 72
Singer's Supply - We Have Anything & Everything For Singers

CREDIT card, ATM, read/write theory $29.00, backup your credit cards, system for PC, kits or complete systems, info $5.00. **CPU ADVANCE,** Box 1089, Waltham, MA 02154.

RADIATION alert! Our Geiger counter utilizes one of the most **sensitive** GM tubes available and no nonsense circuitry. Operating info, schematic, and parts availability $11.95 to: **ELECTRONIC SAFETY INSTRUM,** Box 156, 2927 West Liberty Ave., Pittsburgh, PA 15216.

ALL-in-one catalog. AM/FM/ham/spy, transmitters/amplifiers, voice disguisers, descramblers, audio/TV/science projects. Start your own licensed/unlicensed radio station, books/plans/kits for import and export. 60 mouth-watering pages for $1.00. **PAN-COM INTERNATIONAL,** PO Box 130-F2, Paradise, CA 95967.

DESCRAMBLING New secret manual. Build your own descramblers for **cable** and subscription TV. Instructions, schematics for SSAVI, gated sync, sinewave, (HBO, Cinemax, Showtime, UHF, Adult) $12.95, $2.00 postage. **CABLETRONICS,** Box 30502R, Bethesda, MD 20824.

MEMBRANE SWITCH KITS!

These highly durable water resistant flat-panel keypads can be assembled in minutes with YOUR legend! Available in 4, 12, 16, 24 & 40 Key models. Steel "clickdomes" optional. Connector and bezel included.



Call for free brochure

Sil-Walker 880 Calle Plano, Unit N,
Camarillo, CA 93012
(805) 389-8100 FAX (805) 484-3311

68HC11 controller board. Digital, analog, display/keypad expansion boards. Bare PCB and docs, $25.00 each. Docs only, $15.00 each. Assembled units available. **P.T.S.,** 609 Brent, Benton, AR 72015.

FREE hobby catalog. Lowest prices components, parts, tools, more! **GALLIMORE ELECTRONICS,** Box 70150-F, San Diego, CA 92167.

BEST BY MAIL

Rates: Write National, Box 5, Sarasota, FL 34230

OF INTEREST TO ALL

CAPS/EMBROIDERY PATCHES Iron-on 100% Markup, Free Wholesale Colored Catalogue: IRWIN, Box 2096-(RE), Baytown, TX 77522. (713-424-7651).

ETERNAL SECURITY: TRUE or False? Free Bible Studies. Light, St. Maries, ID 83861.

FINANCIAL

STOP BILL COLLECTORS COLD!! Extensive Report $29.00 FREE Information: 800-393-1114 Ext. 11.

RECIPES

20 ORIENTAL RECIPES. $4 (SASE) To: Sylvester, Box 528, Scranton, PA 18501.

20 ITALIAN RECIPES. $4.00 (SASE) To: Sylvester, Box 528, Scranton, PA 18501.

INVENTIONS

FREE invention package: DAVISON AND ASSOCIATES offers customized development, patenting, and licensing for new products and ideas. Proven results: 1 (800) 677-6382.

PATENT DRAWINGS

PATENT drawings done by qualified electronics engineer. Free consultation. Write for info. PO Box 4935, Seminole, FL 34642.

Learn to fix computers!

Home study. Earn great money repairing troubleshooting, upgrading, and installing PCs. Free literature: 800-223-4542.

Name_____ Age____

Address_____

City_____ State____ Zip____

The School of PC Repair, Dept. JB342
6065 Roswell Road, Atlanta, Georgia 30328

Be a TV/VCR Repair Specialist

Now you can train for a money-making career as a TV/VCR Repair Specialist. No previous experience necessary. No need to quit your job or school. Everything is explained in easy-to-understand language with plenty of drawings, diagrams and photos. We show you how to troubleshoot and repair video cassette recorders and TV sets. Send for free facts about the exciting opportunities in TV/VCR Repair and find out how you can start making money in this great career.

MAIL COUPON TODAY OR CALL TOLL FREE:

1-800-992-8765 Ext. 2728 K03D

CALL ANYTIME—24 hours a day, 7 days a week.

ICS SINCE 1890 **SCHOOL OF TV/VCR REPAIR, Dept. ADE014S**
925 Oak Street, Scranton, PA 18515

Please send me full information and color brochure on how I can learn TV/VCR Repair at home in my spare time. I understand there is no obligation and no salesman will visit me.

Name_____ Age____

Address_____ Apt. #____

City/State_____ Zip____

Phone ( )_____

BUSINESS OPPORTUNITIES

MAKE $75,000.00 to $250,000.00 yearly. Learn **IBM monitors** repairs. (solutions most brands). New home based business program. Software available. Information: **USA-Canada** $3.00 cash (no checks), dealers wanted worldwide ($35.00) **US funds. RANDALL DISPLAY,** PO Box 2168 R, Van Nuys, CA 91404 USA.

LET the government finance your small business. Grants/loans to $500,000.00. Free recorded message: **(707) 449-8600.** (KS1).

HOME assembly work available! Guaranteed easy money! Free details! SASE. **HOMEWORK-R,** Box 520, Danville, NH 03819.

EASY work! Excellent pay! Assemble products at home. Call toll free **1 (800) 467-5566** Ext. 5192.

START your own technical venture! Don Lancaster's newly updated **Incredible Secret Money Machine II** tells how. We now have autographed copies of the Guru's underground classic for $18.50. **SYNERGETICS PRESS,** Box 809-C, Thatcher, AZ 85552. (602) 428-4073. Visa/MC.

ATTENTION inventors. Turn your ideas into reality. Call **INNOVATIVE ELECTRONICS, INC.** your electronics engineering specialists. (313) 486-6625 or (313) 486-4892 fax.

SATELLITE TV

FREE catalog — Lowest prices worldwide. Satisfaction guarantee on everthing sold — systems, upgrades, parts, all major brands factory fresh and warrantied. **SKYVISION,** 1012 Frontier, Fergus Falls, MN 56537. 1 (800) 334-6455. Outside US (218) 739-5231.

VIDEOCYPHER II descrambling manual. Schematics, video and audio. Explains DES, Eprom, CloneMaster, Pay-per-view (HBO, Cinemax, Showtime, Adult, etc.) $16.95, $2.00 postage. Schematics for Videocypher Plus, $20.00. Schematics for Videocypher 032, $15.00. Collection of software to copy and alter Eprom codes, $25.00. VCII Plus Eprom, binary and source code, $30.00. **CABLETRONICS,** Box 30502R, Bethesda, MD 20824.

EDUCATION & INSTRUCTION

F.C.C. Commercial General Radiotelephone license. Electronics home study. Fast, inexpensive! "Free" details. **COMMAND,** D-176, Box 2824, San Francisco, CA 94126.

ELECTRONIC engineering. 8 volumes complete. $109.95. No prior knowledge required. Free brochure. **BANNER TECHNICAL BOOKS,** 1203 Grant Avenue, Rockford, IL 61103.

ELECTRICITY/Electronics training series used by U.S. military. 23 volumes, other courses available. Free info: **FEDERAL TECHNICAL PUBLISHERS,** Box 1061 N, Glen Lake, MN 55345.

CABLE TV
DESCRAMBLER LIQUIDATION!
FREE CATALOG!
Hamlin Combos $44, Oak M35B $60 (min. 5), etc.
WEST COAST ELECTRONICS
For Information: 818-709-1758
Catalogs & Orders: 800-628-9656

CABLE/SATELLITE

UNDETECTABLE cable/satellite descrambler will work on all systems **guaranteed!** Send SASE/info, $94.95/kit, $14.95/plans. **MYSTICAL ELECTRONICS,** PO Box 481, Cooper Station, New York, NY 10276.

CABLE TV TURN-ON CHIPS

SUPER Cable TV "Test Chips". Provides full service activation. Includes; instructions & illustrations. **Jerrold:** Starcom-6 ..Starcom-7. **Scientific Atlanta:** 8500 thru 8600. **Tocom:** 5503-VIP..5507. **Zenith:** ST-1000 thru ST-5000. **Call now!! MASTER COMPONENTS. 1 (800) 233-0570.**

SURVEILLANCE
& COUNTERSURVEILLANCE Electronic Devices
Bugging/Phone Tapping Detectors • Caller IDs • Covert Video • Phone Scramblers • Voice Changers • Shotgun Mics Vehicle Tracking • Transmitter Kits • Locksmithing • AND MORE!
NEW! *Telephone Recording Systems* *Disguise Video Cameras*
EDE **FOR CATALOG SEND $5.00 TO... P.O. Box 337, Buffalo, NY 14226 (716) 691-3476**

IMPROVE YOUR LOOKS, HEALTH AND POPULARITY.

QUIT SMOKING.

American Heart Association

© 1992, American Heart Association

BUY BONDS

Parts Express

Parts Express is pleased to announce that we are now stocking the complete line of fine multimeters from Tripplett Corporation. Tripplett has been producing high quality test and measurement equipment since 1904. For more information and to get a copy of our FREE 172 page catalog call our toll free number.

FREE CATALOG

1-800-338-0531
Phone: (513) 222-0173
FAX: (513) 222-4644
Parts Express Int'l Inc.
340 East First St.
Dayton, 45402

CIRCLE 56 ON FREE INFORMATION CARD

SEND ORDERS TO:
ELECTRONIC GOLDMINE
P.O. Box 5408
Scottsdale, AZ 85261

Minimum Order: $10.00 plus $4.00 Shipping and Handling. We accept MasterCard, Visa and Money orders.

PHONE ORDERS (602) 451-7454 • FAX ORDERS (602) 451-9495

HSE# NPN TRANSISTOR
Similar to the popular 2N3904 transistors these have long leads and are marked with a house#. T092 plastic case. Prime.
G3713
30/$1.00
500/$14.00



BOURNS 3500S 10K 10 TURN WIREWOUND POTENTIOMETER
Precision 10 turn ¾" diameter sealed blue case 10K potentiometer features standard ¾" bushing and nut for panel mounting. Power rating 2 watts, and linearity ±.2%. These are prime brand new units worth over $30.00 each.
G3714 $3.00

20W X 20W STEREO AMP KIT
Two separate high power amps on one PC board put out an incredible 20 watts RMS each. Features low distortion circuitry. Great stereo booster amp for your car sound system. Use with any speakers capable of handling at least 20 watts. Operates on 12VDC. Size of board: 6" x 2.25".
C6442 $19.95



SUPER BUY!
4" ROUND SOLAR CELL
Produces over 1 amp at 1/2 volt. Silicon type with solder tabs.
G2308 $7.50

HP HLMP-1340 "RED" ULTRABRIGHT T1 LED
Crystal clear case small T1 LED made by Hewlett Packard lights up a brilliant RED. Long leads prime HP quality.
G3712 10/$1.00
500/$45.00 1000/$85.00

HP HLMP-1540 "GREEN" ULTRABRIGHT T1 LED
Crystal clear case small T1 LED made by Hewlett Packard lights up a brilliant GREEN. Long leads prime HP quality.
G3711 8/$1.00
500/$50.00 1000/$90.00

SOLAR LANTERN
Small white light fluorescent lantern which has a built in solar panel that was to recharge 3 AA nicad batteries after at least a week of exposure to the sun. These units are complete except the manufacturer never installed the nicads. Simply snap off the battery cover and install your own nicads or regular AA batteries. These may have slight scratches or molding imperfections and are sold "As Is" only. Complete except for batteries.
G2961 $7.00



CIRCLE 125 ON FREE INFORMATION CARD

ALL ELECTRONICS

Courteous Service . Discount Prices . Fast Shipping

6 - 12 Vdc GEARHEAD MOTOR



Excellent motor for displays, robotics and other mechanical applications. No load ratings: 48 RPM @ 6 Vdc 92 RPM @ 12 Vdc. Motor dimensions: 1.08" diameter X 1.4" long. Gearhead dimensions: 1.34" X 0.93". Final drive shaft is 1/8" diameter X 0.35" long. A 0.55" diameter gear is press-fit onto the shaft.

CAT # DCM-43 **$ 9.50 each**

RECHARGEABLE GEL CELL BATTERIES



Maintenance free, rechargeable gel cell batteries are an excellent back-up power source for alarms, communications equipment, lighting or computers. They can be used in any position and can be trickle charged for long periods of time. These were removed from new equipment and are guaranteed functional.

6 Volts @ 4 A/h CAT# GC-64
Panasonic # LCR6V4P or equiv.
2.75" X 1.87" X 4" high
$12.00 each

12 Volts @ 1.2 A/h CAT# GC-1212
Yuasa # NP1.2-12 or equiv.
3.8" X 1.81" X 2" high.
$ 7.50 each

12 Volts @ 2 A/h CAT# GC-122
Yuasa# NP2-12 or equiv.
5.92" X 0.79" X 3.5" high
$ 8.50 each

12 Volts @ 7 A/h CAT# GC-127
Yuasa # NP7-12 or equiv.
5.95" X 2.53" X 3.71" high
$ 25.00 each

12 Volts @ 12 A/h CAT# GC-12
Yuasa # NP12-12 or equiv.
5.93" X 3.83" X 3.69" high
$ 35.00 each

ELECTROLUMINESCENT "Glow Strip"



4.75" X 10.25" glow strip operates on 80-120 Vac.

Emits a soft pink/white glow when energized. Great for backlighting control panels and special effects. Thin and flexible, can be used on curved surfaces. 0.04" thick. 2 wire connection.

CAT# GS-510
$6.00 each

ORDER TOLL FREE
1-800-826-5432
CHARGE ORDERS to Visa, MasterCard or Discover

TERMS: Minimum order $10.00.Shipping and handling for the 48 continental U.S.A. $4.00 per order. All others including AK, HI, PR or Canada must pay full shipping. All orders delivered in CALIFORNIA must include state sales tax (7 .25%, 7.5%, 7.75%, 8 .25%, 8.5%) .Quantities Limited. NO C.O.D. Prices subject to change w/out notice.

Call Or Write For A *Free* 64 Page CATALOG
Outside the U.S.A. send $2.00 postage.

MAIL ORDERS TO:
ALL ELECTRONICS CORPORATION
P.O. Box 567
Van Nuys, California 91408
FAX (818) 781-2653

CIRCLE 107 ON FREE INFORMATION CARD

ADVERTISING INDEX

Electronics Now does not assume any responsibility for errors that may appear in the index below.

Free Information Number		Page
108	AMC Sales	79
107	All Electronics	96
—	Amazing Concepts	17
77	B&K Precision	9
98	B.I.—A Division of WaveTek	18
109	C & S Sales	2
—	CIE	15
—	CLAGGK Inc. Video Offer	19
185	Cable Warehouse	81
110	Chenesko Products	87
—	Command Productions	17
127	Deco Industries	87
—	EIA	84
125	Electronic Goldmine	95
—	Electronics Book Club	7, 44
—	Electronics Tech. Today	71
121	Fluke Corporation	CV2
—	Grantham College	75
86	Heathkit	79
180	Howard W. Sams & Co.	25
177	ICS Computer Training	81, 95
182	Interactive Image Tech	12
114	Jameco	93
187	Kelvin	11
87	MCM Electronics	92
93	Mark V. Electronics	94
183,184	Mini-Circuits	CV4, 1
117	Mouser	77
—	NRI Schools	29, 63
179	Optoelectronics	CV3
56	Parts Express	95
—	Star Circuits	87
178	TECI	58
176	The School of VCR Repair	77
105	WPT Publications	58
186	Wintek	89
—	World College	5
181	Xandi Electronics	87
188	Zentek Corp.	94

Gernsback Publications, Inc.
500-B Bi-County Blvd.
Farmingdale, NY 11735
1-(516) 293-3000
Larry Steckler, EHF/CET
President

Christina Estrada
assistant to the President

For Advertising ONLY
516-293-3000
Fax 1-516-293-3115

Larry Steckler
publisher

Arline Fishman
advertising director

Denise Mullen
advertising assistant

Kelly Twist
credit manager

Subscriber Customer Service
1-800-288-0652

Order Entry for New Subscribers
1-800-999-7139
7:00 AM - 6:00 PM M-F MST

ADVERTISING SALES OFFICES

EAST/SOUTHEAST
Stanley Levitan
Eastern Advertising
1 Overlook Ave.
Great Neck, NY 11021
1-516-487-9357
Fax 1-516-487-8402

MIDWEST/Texas/Arkansas/Okla.
Ralph Bergen
Midwest Advertising
One Northfield Plaza, Suite 300
Northfield, IL 60093-1214
1-708-446-1444
Fax 1-708-559-0562

PACIFIC COAST
Blake Murphy
Pacific Advertising
Pattis/3M
1800 North Highland Avenue
Suite 717
Hollywood, CA 90028
1-213-462-2700
FAX 1-213-463-0544

Electronic Shopper
Joe Shere
National Representative
P.O. Box 169
Idyllwild, CA 92549
1-909-659-9743
Fax 1-909-659-2469

It's kinda

s m a l l ,

but it sure packs a

WALLOP!



Includes: Internal Nicad Battery Pack & A/C Charger.
TA100S Telescoping Whip Antenna - $12

Sometimes size isn't everything. Take for example the new Model 3300 Mini-Counter. A small, yet powerful device that not only outperforms any model in its class, but has features that are unprecedented. Like the implementation of the LCD display, which, unlike energy-sapping LED's, uses lower power and is easier to read, even in bright sunlight! Best of all, with its smaller package, you'll have more time enjoying its features and less time worrying about fitting it in your pocket.

$129

5% Ship/Handling (Min $5 & Max $10)
15% Outside continental U.S.
Visa, Master Card, C.O.D., Cash or Money Orders only.

- 1 MHz-2.8GHz Frequency Range
- Direct Count Range From 1MHz to 250MHZ with 1Hz/Sec high resolution display
- Prescaled to 2.8GHz
- Select up to 6 Gate/Measurement Periods
- 10 MHz industry Standard Time Base
- Ultra Compact true pocket size; 3.4" x 2.6" x 1.2"
- Maximized sensitivity for picking up radio transmissions from the greatest distance
- Display Hold Switch Locks current Measurement

ORDER LINE
800 • 327 • 5912

OPTOELECTRONICS

(305) 771-2050 • FAX (305) 771-2052 • 5821 NE 14th Ave., Ft. Lauderdale FL 33334

CIRCLE 179 ON FREE INFORMATION CARD



DC-2000 MHz

AMPLIFIERS

In plastic and ceramic packages, for low-cost solutions to dozens of application requirements, select Mini-Circuits' flatpack or surface-mount wideband monolithic amplifiers. For example, cascade three MAR-2 monolithic amplifiers and end up with a 25dB gain, 0.3 to 2000MHz amplifier for less than $4.50. Design values and circuit board layout available on request.

It's just as easy to create an amplifier that meets other specific needs, whether it be low noise, high gain, or medium power. Select from Mini-Circuits' wide assortment of models (see Chart), sketch a simple interconnect layout, and the design is done. Each model is characterized with S parameter data included in our 740-page RF/IF Designers' Handbook.

All Mini-Circuits' amplifiers feature tight unit-to-unit repeatability, high reliability, a one-year guarantee, tape and reel packaging, off-the-shelf availability, with prices starting at 99 cents.

Mini-Circuits' monolithic amplifiers...for innovative do-it-yourself problem solvers.



Models above shown actual size

from **99¢** Unit price $ (25 qty)

PLASTIC SURFACE-MOUNT			++VAM-3 1.45		+VAM-6 1.29	++VAM-7 1.75		
add suffix SM to model no. (ex. MAR-1SM)	MAR-1 1.04	MAR-2 1.40	MAR-3 1.50	MAR-4 1.60	MAR-6 1.34	MAR-7 1.80	MAR-8 1.75	
	MAV-1 1.15	+MAV-2 1.45	+MAV-3 1.55	MAV-4 1.65				MAV-11 2.15
CERAMIC SURFACE-MOUNT	RAM-1 4.95	RAM-2 4.95	RAM-3 4.95	RAM-4 4.95	RAM-6 4.95	RAM-7 4.95	RAM-8 4.95	
PLASTIC FLAT-PACK	MAV-1 1.10	+MAV-2 1.40	+MAV-3 1.50	+MAV-4 1.60				MAV-11 2.10
	MAR-1 0.99	MAR-2 1.35	MAR-3 1.45	MAR-4 1.55	MAR-6 1.29	MAR-7 1.75	MAR-8 1.70	
Freq.MHz,DC to	1000	2000	2000	1000	2000	2000	1000	1000
Gain, dB at 100MHz	18.5	12.5	12.5	8.3	20	13.5	32.5	12.7
Output Pwr. +dBm	1.5	4.5	10.0	12.5	2.0	5.5	12.5	17.5
NF, dB	5.5	6.5	6.0	6.5	3.0	5.0	3.3	3.6

Notes: + Frequency range DC-1500MHz ++ Gain 1/2 dB less than shown

designer's kit, KH-1 available only $59.95 includes:
40 AMPLIFIERS* 10 MAR-1, 10 MAR-3, 10 MAR-4, 10 MAR-8
150 CAPACITORS* 50 100 pf, 50 1,000 pf, 50 10,000 pf
740 page RF/IF DESIGNER'S HANDBOOK

• MIXERS • POWER SPLITTER/COMBINERS • AMPLIFIERS • ELECTRONIC ATTENUATORS
• I&Q/QPSK MODULATORS • ATTENUATORS/TERMINATIONS • DIRECTIONAL COUPLERS
• RF TRANSFORMERS • DIGITAL ATTENUATORS • PHASE DETECTORS • SWITCHES/DRIVERS
• FILTERS • LIMITERS • FREQUENCY DOUBLERS

*values or models may be substituted without notice, depending on supplies.

Typical Circuit Arrangement



finding new ways...
setting higher standards

Mini-Circuits™

WE ACCEPT AMERICAN EXPRESS AND VISA

P.O. Box 350166, Brooklyn, New York 11235-0003 (718) 934-4500 Fax (718) 332-4661

Distribution Centers NORTH AMERICA 800-654-7949 • 417-335-5935 Fax 417-335-5945 EUROPE 44-252-835094 Fax 44-252-837010

CIRCLE 183 ON FREE INFORMATION CARD

F155 REV. A